

# **PICEANCE VLY NAD 83**

**PA 29-06S-095W**

**DOE 3-W-29 Pad**

**PA 412-29 - Slot B11**

**Wellbore #1**

**Plan: Plan #2 26Jan10 kjs**

## **Standard Planning Report - Geographic**

**23 March, 2010**

**Williams**  
Planning Report - Geographic

<b>Database:</b>	Compass R5000 WIN AUTH	<b>Local Co-ordinate Reference:</b>	Well PA 412-29 - Slot B11
<b>Company:</b>	PICEANCE VLY NAD 83	<b>TVD Reference:</b>	WELL @ 5702.0usft (Nabors 577 (26') kjs)
<b>Project:</b>	PA 29-06S-095W	<b>MD Reference:</b>	WELL @ 5702.0usft (Nabors 577 (26') kjs)
<b>Site:</b>	DOE 3-W-29 Pad	<b>North Reference:</b>	True
<b>Well:</b>	PA 412-29	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	Wellbore #1		
<b>Design:</b>	Plan #2 26Jan10 kjs		

<b>Project</b>	PA 29-06S-095W, Garfield County, CO		
<b>Map System:</b>	US State Plane 1983	<b>System Datum:</b>	Mean Sea Level
<b>Geo Datum:</b>	North American Datum 1983		
<b>Map Zone:</b>	Colorado Central Zone		Using geodetic scale factor

Site		DOE 3-W-29 Pad			
Site Position:		Northing:	1,613,247.00 usft	Latitude:	39° 29' 23.965 N
From:	Map	Easting:	2,287,962.20 usft	Longitude:	108° 1' 23.779 W
Position Uncertainty:	0.0 usft	Slot Radius:	13.200 in	Grid Convergence:	-1.591 °

Well	PA 412-29 - Slot B11					
Well Position	+N/-S	0.0 usft	Northing:	1,613,239.10 usft	Latitude:	39° 29' 23.885 N
	+E/-W	0.0 usft	Easting:	2,287,956.00 usft	Longitude:	108° 1' 23.856 W
Position Uncertainty		0.0 usft	Wellhead Elevation:		Ground Level:	5,676.0 usft

<b>Wellbore</b>	Wellbore #1				
<b>Magnetics</b>	<b>Model Name</b>	<b>Sample Date</b>	<b>Declination (°)</b>	<b>Dip Angle (°)</b>	<b>Field Strength (nT)</b>
	IGRF2010	2/3/2009	10.666	65.794	52,486

<b>Design</b>	Plan #2 26Jan10 kjs			
<b>Audit Notes:</b>				
<b>Version:</b>	<b>Phase:</b>	PLAN	<b>Tie On Depth:</b>	0.0
<b>Vertical Section:</b>	<b>Depth From (TVD) (usft)</b>	<b>+N/-S (usft)</b>	<b>+E/-W (usft)</b>	<b>Direction (°)</b>
	0.0	0.0	0.0	327.52

<b>Plan Sections</b>										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.000	
120.0	0.00	0.00	120.0	0.0	0.0	0.00	0.00	0.00	0.000	
1,256.3	39.77	327.52	1,167.2	319.6	-203.4	3.50	3.50	0.00	327.524	
4,991.4	39.77	327.52	4,038.0	2,335.3	-1,486.4	0.00	0.00	0.00	0.000	
6,580.0	8.00	327.37	5,472.0	2,870.9	-1,827.6	2.00	-2.00	-0.01	-179.959	Top Gas (25' Radius)
6,980.0	0.00	0.00	5,870.7	2,894.3	-1,842.6	2.00	-2.00	8.16	180.000	
8,731.2	0.00	0.00	7,622.0	2,894.3	-1,842.6	0.00	0.00	0.00	0.000	

**Williams**  
Planning Report - Geographic

<b>Database:</b>	Compass R5000 WIN AUTH	<b>Local Co-ordinate Reference:</b>	Well PA 412-29 - Slot B11
<b>Company:</b>	PICEANCE VLY NAD 83	<b>TVD Reference:</b>	WELL @ 5702.0usft (Nabors 577 (26') kjs)
<b>Project:</b>	PA 29-06S-095W	<b>MD Reference:</b>	WELL @ 5702.0usft (Nabors 577 (26') kjs)
<b>Site:</b>	DOE 3-W-29 Pad	<b>North Reference:</b>	True
<b>Well:</b>	PA 412-29	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	Wellbore #1		
<b>Design:</b>	Plan #2 26Jan10 kjs		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude	
0.0	0.00	0.00	0.0	0.0	0.0	1,613,239.10	2,287,956.00	39° 29' 23.885 N	108° 1' 23.856 W	
120.0	0.00	0.00	120.0	0.0	0.0	1,613,239.10	2,287,956.00	39° 29' 23.885 N	108° 1' 23.856 W	
Start Build 3.50										
1,256.3	39.77	327.52	1,167.2	319.6	-203.4	1,613,564.17	2,287,761.57	39° 29' 27.044 N	108° 1' 26.450 W	
Hold 39.77 Inclination										
2,329.4	39.77	327.52	1,992.0	898.7	-572.0	1,614,153.27	2,287,409.21	39° 29' 32.767 N	108° 1' 31.152 W	
Top of "G" Sand										
2,459.5	39.77	327.52	2,092.0	968.9	-616.7	1,614,224.70	2,287,366.49	39° 29' 33.461 N	108° 1' 31.722 W	
Base of "G" Sand										
2,589.6	39.77	327.52	2,192.0	1,039.1	-661.4	1,614,296.13	2,287,323.77	39° 29' 34.155 N	108° 1' 32.292 W	
9 5/8"										
4,991.4	39.77	327.52	4,038.0	2,335.3	-1,486.4	1,615,614.69	2,286,535.11	39° 29' 46.965 N	108° 1' 42.817 W	
Begin 2"/100 Drop										
5,086.3	37.87	327.52	4,112.0	2,385.5	-1,518.3	1,615,665.77	2,286,504.56	39° 29' 47.462 N	108° 1' 43.224 W	
Mesaverde										
6,580.0	8.00	327.37	5,472.0	2,870.9	-1,827.6	1,616,159.49	2,286,208.90	39° 29' 52.258 N	108° 1' 47.170 W	
Top Gas - Approx. Top Gas										
6,980.0	0.00	0.00	5,870.7	2,894.3	-1,842.6	1,616,183.38	2,286,194.52	39° 29' 52.490 N	108° 1' 47.362 W	
Vertical										
8,026.2	0.00	0.00	6,917.0	2,894.3	-1,842.6	1,616,183.38	2,286,194.52	39° 29' 52.490 N	108° 1' 47.362 W	
Cameo Coals										
8,581.2	0.00	0.00	7,472.0	2,894.3	-1,842.6	1,616,183.38	2,286,194.52	39° 29' 52.490 N	108° 1' 47.362 W	
Rollins SS										
8,731.2	0.00	0.00	7,622.0	2,894.3	-1,842.6	1,616,183.38	2,286,194.52	39° 29' 52.490 N	108° 1' 47.362 W	
TD at 8731.2 - TD										

Design Targets									
Target Name									
- hit/miss target	Dip Angle	Dip Dir.	TVD	+N/-S	+E/-W	Northing	Easting		
- Shape	(°)	(°)	(usft)	(usft)	(usft)	(usft)	(usft)	Latitude	Longitude
Top Gas (25' Radius) P/	0.00	0.00	5,472.0	2,888.8	-1,838.9	1,616,177.70	2,286,198.10	39° 29' 52.435 N	108° 1' 47.314 W
- plan misses target center by 21.0usft at 6581.4usft MD (5473.5 TVD, 2871.0 N, -1827.7 E)									
- Circle (radius 25.0)									
TD / PBHL PA 412-29	0.00	0.00	7,622.0	2,888.8	-1,838.9	1,616,177.70	2,286,198.10	39° 29' 52.435 N	108° 1' 47.314 W
- plan misses target center by 6.7usft at 8731.2usft MD (7622.0 TVD, 2894.3 N, -1842.6 E)									
- Point									

Casing Points						
Measured Depth (usft)	Vertical Depth (usft)	Name			Casing Diameter (in)	Hole Diameter (in)
2,589.6	2,192.0	9 5/8"			9.625	12.250

**Williams**  
Planning Report - Geographic

<b>Database:</b>	Compass R5000 WIN AUTH	<b>Local Co-ordinate Reference:</b>	Well PA 412-29 - Slot B11
<b>Company:</b>	PICEANCE VLY NAD 83	<b>TVD Reference:</b>	WELL @ 5702.0usft (Nabors 577 (26') kjs)
<b>Project:</b>	PA 29-06S-095W	<b>MD Reference:</b>	WELL @ 5702.0usft (Nabors 577 (26') kjs)
<b>Site:</b>	DOE 3-W-29 Pad	<b>North Reference:</b>	True
<b>Well:</b>	PA 412-29	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	Wellbore #1		
<b>Design:</b>	Plan #2 26Jan10 kjs		

Formations						
Measured Depth (usft)	Vertical Depth (usft)	Name	Lithology	Dip (°)	Dip Direction (°)	
2,329.4	1,992.0	Top of "G" Sand				
2,459.5	2,092.0	Base of "G" Sand				
5,086.3	4,112.0	Mesaverde				
6,580.0	5,472.0	Approx. Top Gas				
8,026.2	6,917.0	Cameo Coals				
8,581.2	7,472.0	Rollins SS				
8,731.2	7,622.0	TD				

Plan Annotations					
Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates			
		+N/-S (usft)	+E/-W (usft)	Comment	
120.0	120.0	0.0	0.0	Start Build 3.50	
1,256.3	1,167.2	319.6	-203.4	Hold 39.77 Inclination	
4,991.4	4,038.0	2,335.3	-1,486.4	Begin 2"/100 Drop	
6,580.0	5,472.0	2,870.9	-1,827.6	Top Gas	
6,980.0	5,870.7	2,894.3	-1,842.6	Vertical	
8,731.2	7,622.0	2,894.3	-1,842.6	TD at 8731.2	