

FORM
2
Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE ZONE COMMINGLE ZONE

Refiling
Sidetrack

Document Number:
400036839
Plugging Bond Surety
20030009

3. Name of Operator: NOBLE ENERGY INC 4. COGCC Operator Number: 100322

5. Address: 1625 BROADWAY STE 2200
City: DENVER State: CO Zip: 80202

6. Contact Name: MARI CLARK Phone: (303)228-4413 Fax: (303)228-4286
Email: mclark@nobleenergyinc.com

7. Well Name: REI H Well Number: 17-29D

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7972

WELL LOCATION INFORMATION

10. QtrQtr: SESW Sec: 8 Twp: 3N Rng: 65W Meridian: 6
Latitude: 40.233890 Longitude: -104.689780

Footage at Surface: 455 FNL/FSL FSL 1965 FEL/FWL FWL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4899 13. County: WELD

14. GPS Data:

Date of Measurement: 11/13/2009 PDOP Reading: 1.8 Instrument Operator's Name: ROBERT DALEY

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 75 FSL 1220 FWL FWL Bottom Hole: FNL/FSL 75 FSL 1220 FEL/FWL FWL
Sec: 8 Twp: 3N Rng: 65W Sec: 8 Twp: 3N Rng: 65W

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 730 ft

18. Distance to nearest property line: 290 19. Distance to nearest well permitted/completed in the same formation: 819 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL	407-87	160	GWA
J SAND	JSND	232-23	160	GWA
NIOBRARA	NBRR	407-87	160	GWA

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: 20030012

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No Surface Owners Agreement Attached or \$25,000 Blanket Surface Bon \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
 ALL: SECTION 8, T3N-65W

25. Distance to Nearest Mineral Lease Line: 75 ft 26. Total Acres in Lease: 2259

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? Yes No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal: Offsite Onsite
 Method: Land Farming Land Spreading Disposal Facility Other: CLOSED LOOP

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	650	230	650	0
1ST	7+7/8	4+1/2	11.6	7,972	765	7,972	

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments NO CONDUCTOR CASING WILL BE USED. 1ST STRING TOP OF CEMENT = 200' ABOVE NIOBRARA. UNIT CONFIGURATION = S/2SW, SECTION 8 & N/2NW OF SECTION 17, T3N, R65W. WELL IS TO BE TWINNED WITH EXISTING BB DRAW H8-14JI

34. Location ID: 330968

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: MARI CLARK

Title: REG. ANALYST II Date: 4/8/2010 Email: mclark@nobleenergyinc.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER	Permit Number: _____	Expiration Date: _____
05	CONDITIONS OF APPROVAL, IF ANY:	

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name	Doc Description
400053231	WELL LOCATION PLAT	2415-Sharp-5001N_20100408_094019.pdf
400053232	30 DAY NOTICE LETTER	2415-Sharp-5001N_20100408_094056.pdf
400053233	SURFACE AGRMT/SURETY	2415-Sharp-5001N_20100408_094109.pdf
400053234	DEVIATED DRILLING PLAN	2415-Sharp-5001N_20100408_094126.pdf
400053239	EXCEPTION LOC REQUEST	2415-Sharp-5001N_20100408_100929.pdf
400053240	EXCEPTION LOC WAIVERS	2415-Sharp-5001N_20100408_100942.pdf
400053241	PROPOSED SPACING UNIT	2415-Sharp-5001N_20100408_100955.pdf

Total Attach: 7 Files