



(2) 2557134

COGCC

5. Lease Serial No.
Fed. Beezley D-051174


APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		7. If Unit or CA Agreement, Name and No. COC 47675X	
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		8. Lease Name and Well No. BEEZLEY 5X22	
2. Name of Operator Chevron USA Inc		9. API Well No. TO BE ASSIGNED	
3a. Address 100 Chevron Road Rangely, CO 81648		3b. Phone No. (include area code) 970-675-3842	
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface 2117 FNL & 1622 FEL (SWNE) Section 22, T2N, R103W, 6TH P.M. At proposed prod. zone 1262 FNL & 2249.4 FEL		10. Field and Pool, or Exploratory Rangely Weber Sand Unit	
14. Distance in miles and direction from nearest town or post office* West from Rangely on HWY 64, 8 miles, then 3/4 miles on lease road (south).		12. County or Parish Rio Blanco	
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 525' to the south		13. State CO	
16. No. of acres in lease 19,143 Unit Acres		17. Spacing Unit dedicated to this well 20 acres	
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 125'		19. Proposed Depth 6897' MD	
20. BLM/BIA Bond No. on file ES 0022		21. Elevations (Show whether DF, KDB, RT, GL, etc.) GL = 5594'	
22. Approximate date work will start* 07/30/2010		23. Estimated duration 2 WEEKS DRILLING TIME	

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, must be attached to this form:

- | | |
|--|---|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the BLM. |

25. Signature 	Name <i>(Printed/Typed)</i> Diane L. Peterson	Date 04/02/2010
Title Regulatory Specialist Chevron USA Inc		
Approved by <i>(Signature)</i>	Name <i>(Printed/Typed)</i>	Date
Title	Office	

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

*(Instructions on page 2)

CHEVRON U.S.A., INC.
BEEZLEY #6X22 & #5X22
LOCATED IN RIO BLANCO COUNTY, COLORADO
SECTION 22, T2N, R103W, 6th P.M.

RECEIVED

APR 23 2010

COGCC




PHOTO: VIEW FROM CORNER #1 TO LOCATION STAKES

CAMERA ANGLE: NORTHERLY




PHOTO: VIEW OF EXISTING ACCESS

CAMERA ANGLE: SOUTHEASTERLY



- Since 1964 -

U E L S Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

LOCATION PHOTOS

11 19 09
MONTH DAY YEAR

TAKEN BY: D.R.

DRAWN BY: Z.L.

REVISED: 00-00-00

PHOTO
P1

RECEIVED

APR 23 2010

COGCC

CHEVRON U.S.A., INC.
BEEZLEY #6X22 & #5X22
LOCATED IN RIO BLANCO COUNTY, COLORADO
SECTION 22, T2N, R103W, 6th P.M.



PHOTO: VIEW OF LOCATION STAKES

CAMERA ANGLE: NORTHERLY




PHOTO: VIEW OF LOCATION STAKES

CAMERA ANGLE: SOUTHERLY



- Since 1964 -

**U
E
L
S**

Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

LOCATION PHOTOS

11
MONTH

19
DAY

09
YEAR

TAKEN BY: D.R.

DRAWN BY: Z.L.

REVISED: 00-00-00

PHOTO
P2

CHEVRON U.S.A., INC.
BEEZLEY #6X22 & #5X22
LOCATED IN RIO BLANCO COUNTY, COLORADO
SECTION 22, T2N, R103W, 6th P.M.

RECEIVED

APR 23 2010

COGCC



PHOTO: VIEW OF LOCATION STAKES

CAMERA ANGLE: EASTERLY



PHOTO: VIEW OF LOCATION STAKES

CAMERA ANGLE: WESTERLY



- Since 1964 -

UELS Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

LOCATION PHOTOS

11 19 09
MONTH DAY YEAR

TAKEN BY: D.R.

DRAWN BY: Z.L.

REVISED: 00-00-00

PHOTO
P3

CHEVRON U.S.A., INC.

Well location, BEEZLEY #5X22, located as shown in the SW 1/4 NE 1/4 of Section 22, T2N, R103W, 6th P.M., Rio Blanco County, Colorado.



BASIS OF ELEVATION

GOLF TRIANGULATION STATION LOCATED IN THE SE 1/4 OF SECTION 30, T2N, R102W, 6th P.M. TAKEN FROM THE BANTY POINT, QUADRANGLE, COLORADO, RIO BLANCO COUNTY, 7.5 MINUTE QUAD (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5311 FEET.

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.

T2N, R103W, 6th P.M.



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

RECEIVED

APR 23 2010

REGISTERED LAND SURVEYOR
REGISTRATION NO. 17492
STATE OF COLORADO

COCCO ENGINEERING & LAND SURVEYING

85 SOUTH 200 EAST - VERNAL, UTAH 84078
(435) 789-1017

NOTE:
SEE ADDENDUM TO LEGAL PLAT FOR
EXISTING IMPROVEMENTS WITHIN 400'
OF THE PROPOSED WELL DISTURBANCE.

LEGEND:

- = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.

PDOP = 2.5	
NAD 83 (TARGET BOTTOM HOLE)	NAD 83 (SURFACE LOCATION)
LATITUDE = 40°07'56.74" (40.132428)	LATITUDE = 40°07'48.27" (40.130075)
LONGITUDE = 108°56'28.22" (108.941172)	LONGITUDE = 108°56'19.78" (108.938828)
NAD 27 (TARGET BOTTOM HOLE)	NAD 27 (SURFACE LOCATION)
LATITUDE = 40°07'56.85" (40.132458)	LATITUDE = 40°07'48.37" (40.130103)
LONGITUDE = 108°56'25.81" (108.940503)	LONGITUDE = 108°56'17.70" (108.938770)

SCALE 1" = 1000'	DATE SURVEYED: 10-30-09	DATE DRAWN: 12-10-09
PARTY D.R. J.F.	REFERENCES G.L.O. PLAT	
WEATHER C.O.D	FILE	

NINE POINT DRILLING PLAN


Beezley 5X22

Rangely Weber Sand Unit

Directional Well

Surface: 2117' FNL & 1622' FEL, Section 22, T2N, R103W
Bottomhole: 1259' FNL & 2279' FEL, Section 22, T2N, R103W

Rio Blanco County, CO



a. **NAMES & ESTIMATED TOPS OF GEOLOGIC GROUPS:**

Name	Estimated Tops
Mancos group	Surface

b. **NAMES, ESTIMATED TOPS & THICKNESS OF FORMATIONS:**
(based upon est. surface elev. of 5,594')

Name	Estimated Tops	Thickness
Mancos	Surface	2,820'
Frontier	3,535' TVD/ 3,566' MD	353'
Dakota	3,887' TVD/ 3,929' MD	85'
Morrison	3,984' TVD/ 4,029' MD	683'
Curtis	4,676' TVD/ 4,743' MD	112'
Entrada	4,774' TVD/ 4,844' MD	140'
Carmel	4,915' TVD/ 4,990' MD	61'
Navajo	4,985' TVD/ 5,062' MD	591'
Chinle	5,603' TVD/ 5,699' MD	109'
Shinarump	5,697' TVD/ 5,796' MD	98'
Moenkopi	5,799' TVD/ 5,902' MD	646'
Weber	6,452' TVD/ 6,575' MD	723'
TD	6,764' TVD/ 6,897' MD	
Base of Weber	7,175' TVD/ 7,320' MD	

c. **PRESSURE CONTROL EQUIPMENT:**

For drilling surface hole to 2000':

No BOP equipment required. A diverter will be utilized if a Surface Hole Drilling Rig equipped to drill with air/air mist is used to preset surface casing.

For drilling through 9 5/8" surface casing to TD:

Maximum anticipated surface pressure is <3000 psi.

Pressure control equipment shall be in accordance with BLM minimum standards.

A casing head with an 11", 3000 psi flange will be welded onto the 9 5/8" surface casing.

BOP stack will consist of either 2 single gate or a double gate and annular preventer. The gate preventers will be equipped with pipe rams on bottom and blind rams on top. The choke and kill lines will be connected to outlets below the bottom rams, utilizing either the ram body outlet or a drilling spool with side outlets. Co-flex hose will be utilized from the BOP to the choke manifold. The BOP stack will be 11" or 13.625" bore, 3000 psi working pressure or greater. The choke and kill lines will be 3" bore, 3000 psi working pressure or greater. Please refer to attached schematic.

Test procedure and frequency shall be in accordance with BLM minimum standards for 3000 psi equipment, per BLM Oil & Gas Order #2.

d. **PROPOSED CASING PROGRAM, DRILLED HOLE SIZE:**

Casing Information: All casing will be new pipe and tested to 1500 psi.

Casing	Weight	Grade	Conn.	Stage	Centralizers
9 5/8"	36.0#/ft	K-55	LTC	No	*
7"	23.0#/ft	J-55	LTC	No	As Needed

*Centralizers will be placed on the bottom three joints and every fourth joint thereafter.

Casing Design Information (9 5/8" casing @ 2000'):

Collapse value for new pipe: 2020 psi Actual Load: 862 psi S.F.: 2.3

Burst value for new pipe: 3520 psi Actual Load: 1169 psi* S.F.: 3.0

Tension value for new pipe: 489,000# Actual Load: 61,000# S.F.: 8.0

*Surface casing burst load based on a formation fracture gradient of 1.0 psi/ft.

(7" casing @ top of Weber at 6452' TVD):

Collapse value for new pipe: 3270 psi Actual Load: 2981 psi S.F.: 1.1

Burst value for new pipe: 4360 psi Actual Load: 1869 psi S.F.: 2.3

Tension value for new pipe: 313,000# Actual Load: 125,000# S.F.: 2.5

Surface Hole (0'-2000')

Drilling of the surface hole will be with a Surface Hole drilling rig equipped to drill with air/air mist if the rig is available. Hole size will be in the 12 1/4" - 11" range at the discretion of the drilling contractor.

Variance to Onshore Oil and Gas Order No. 2 III -E. Special Drilling Operations which addresses additional drilling equipment required for drilling with air/gas is requested for the Surface Hole drilling rig which may be used to preset surface casing. To our knowledge, it is possible (but not probable) that minor amounts of shallow gas (<2000') could be encountered while drilling in this area. The Mancos formation was oil productive in the 1920's but has been mostly depleted and there are no productive Mancos wells with 1/4 mile of the proposed well. Consequently, the majority of the equipment specified in the Special Drilling Operations is not necessary to drill surface holes (<2000') in this area. Auxiliary Equipment to be used is outlined in Section 8. Air/gas will not be used to drill below surface casing.

If the Surface Hole drilling rig is not available to preset the surface casing a conventional rotary drilling rig will be used to drill the surface hole. A 12 1/4" hole will be drilled utilizing fresh water mud.

Production Hole (2000' - 6452' TVD)

Drilling below surface casing will be with conventional rotary equipment utilizing fresh water mud. Hole size will be 8 3/4".

Open Hole (6452' - 6764' TVD - TD)

The Weber Payzone will be drilled and completed open hole utilizing NaCl brine. Hole size will be 6-1/8".

e. AMOUNT AND TYPES OF CEMENT TO BE USED SETTING CASING STRING:

Casing	Cement
9 5/8"	Two-slurry system with oilfield type cement circulated in place. Lead: 35:65 Poz: Class "G" cement mixed at 12.7 ppg with a yield of 1.97cf/sx. Theoretical volume of lead cement is 480 sacks including 80% excess in the open hole. Tail: Class "G" cement mixed at 15.8 ppg with a yield of 1.17cf/sx. Theoretical volume of tail cement is 290 sacks. Volumes based on calculated plus 100% excess. Tail plug used. Allowed to set under pressure. Theoretical open hole annular volume is 626 cu ft.
7"	Two-slurry system with oilfield "light weight" cement with additives ahead of oilfield premium cement with additives circulated in place. Lead: Class G cement mixed at 11.0 ppg with a yield of 3.52cf/sx. Theoretical volume of lead cement is 290 sacks including 80% excess in the open hole. Tail: LiteCRETE Blend mixed at 12.5 ppg with a yield of 1.61cf/sx. Theoretical volume of tail cement is 370 sacks including 80% excess in the open hole. If cement does not reach the surface in cementing the production string, a bond log will be run to determine the

top of cement (TOC) to ensure isolation between the Frontier formation and the surface casing shoe.

f. TYPES AND CHARACTERISTICS OF PROPOSED CIRCULATING MEDIUM:

Surface Hole (0'-2000')

Surface hole will be drilled with air/air mist if a Surface Hole drilling rig is utilized to preset surface casing prior to moving in and rigging up a conventional rotary drilling rig.

Mud circulating equipment and materials as specified in Onshore Order #2, III - E will not be kept on location due to the fact that the Surface Hole drilling rig equipped to drill with air/air mist is not equipped to circulate mud.

If a Surface Hole drilling rig is not utilized to preset the surface casing a conventional rotary rig will be used to drill the surface hole. Water based drilling fluids consisting primarily of fresh water, bentonite, lignite, caustic, lime, soda ash, and polymers will be used. No chromate's will be used. It is not intended to use oil in the mud, however, in the event it is used, oil concentration will be less than 4% by volume. Maximum anticipated mud weight is ± 9.0 ppg.

A minimum quantity of weighting material will be kept on location

Production Hole (2000'-6452' TVD')

Drilling below surface casing will be with water based drilling fluids consisting primarily of fresh water, bentonite, lignite, caustic, lime, soda ash, and polymers. No chromate's will be used. It is not intended to use oil in the mud, however, in the event it is used, oil concentration will be less than 4% by volume. Maximum anticipated mud weight is ± 10.0 ppg.

A minimum quantity of weighting material will be kept on location.

H₂S and CO₂ detector will be used at all times during drilling operation.

Open Hole (6452' – 6764' TVD'-TD)

The Weber Payzone will be drilled and completed open hole utilizing NaCl brine.

g. TESTING, LOGGING AND CORING PROCEDURES:

Logging:

Electric Logging: Cased Hole logs / gamma ray and porosity
Open Hole logs (possible)

Coring: None planned.

Testing: None planned.

h. EXPECTED BOTTOM HOLE PRESSURES, ABNORMAL PRESSURES, TEMPERATURES OR POTENTIAL HAZARDS:

Normal pressure gradient to top of Weber. Offset pressure history indicates that the pressure gradient in the Weber should be between a minimum of 0.32 psi/ft to a maximum of 0.50 psi/ft.

Maximum expected BHP @ TD: ~ 3000 psi
Maximum expected BHT @ TD: ~ 160° F

Hydrogen Sulfide:

Hydrogen sulfide (H₂S) gas exists in the Weber Formation within the Rangely Field. Concentrations vary across the Field (+/-100-700 ppm) due to a long history of production in conjunction with water and CO₂ injection.

Chevron's "H₂S Contingency Plan" will be adhered to minimize any potential hazard.

Possible Aquifers: None

Oil: Probable in Weber @ 6452' – 6764' TVD

Gas: Probable minor gas in Weber @ 6452' TVD decreasing to TD.

Protection of oil, gas, water, or other mineral bearing formations:

Protection shall be accomplished by cementing surface casing back to the surface. Production casing will be cemented with a sufficient cement volume to attempt to bring cement back to surface. If cement does not reach the surface in cementing the production string, a bond log will be run to determine the top of cement (TOC) to ensure isolation between the Frontier formation and the surface casing shoe.

i. OTHER INFORMATION:

Auxiliary Equipment

Conventional Rotary Drilling Rig

Geograph

PVT-Flowmeter

Desilter

Desander

Full Opening Safety Valve

Upper Kelly Valve

Lower Kelly Valve

Surface Hole Rig Equipped to Drill with Air/Air Mist

Diverter; 100' Discharge Line

Closed-Loop Drilling System

Additional Fluid Storage

Cuttings Catch Tank


Dewatering System

Centrifuge System


BOP Schematic

RECEIVED
APR 23 1991
COGCC

Class III BOP Stack



Class III Choke Manifold



NO Normally Open
NC Normally Closed



Scientific Drilling
Directional Drilling Operations

Project: Rangely County Colorado
Site: SEC22-T2N-R103W
Well: BEEZLEY 5X22
Wellbore: Wellbore #1
Plan: Plan 2 (BEEZLEY 5X22/Wellbore #1)

RECEIVED

APR 23 2019

COG66



SECTION DETAILS

MD	Inc	Azi	TVD	+N-S	+E-W	Dleg	TFace	VSec	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
2000.0	0.00	0.00	2000.0	0.0	0.0	0.00	0.00	0.0	
2080.0	0.00	0.00	2080.0	0.0	0.0	0.00	0.00	0.0	
2791.0	14.22	323.73	2783.7	70.8	-51.9	2.00	323.73	87.8	
6897.1	14.22	323.73	6764.0	884.0	-648.7	0.00	0.00	1096.4	PBHL 5X22



Azimuths to Grid North
True North: 2.22°
Magnetic North: 13.26°
Magnetic Field
Strength: 52658.4 nT
Dip Angle: 66.13°
Date: 2009/11/17
Model: IGRF 2005/10

DESIGN TARGET DETAILS

Name	TVD	+N-S	+E-W	Northing	Easting	Latitude	Longitude	Shape
PBHL 5X22	6764.0	884.0	-648.7	1309754.75	2038057.21	40° 7' 56.744 N	108° 56' 28.215 W	Circle (Radius: 100.0)

Rangely County Colorado


Geodetic System: US State Plane 1983
Datum: North American Datum 1983
Ellipsoid: GRS 1980
Zone: Colorado Northern Zone
System Datum: Mean Sea Level

WELL DETAILS: BEEZLEY 5X22

North	Ground Level:	5592.4	Longitude
1308870.77	Easting	Latitude	2038705.87 40° 7' 48.263 N 108° 56' 19.428 W

FORMATION TOP DETAILS

TVDPath	MDPath	Formation
3535.0	3566.0	Frontier
3887.0	3929.2	Dakota
3984.0	4029.2	Morrison
4676.0	4743.1	Curtis
4774.0	4844.2	Entrada
4915.0	4989.6	Carmel
4985.0	5061.9	Navajo
5603.0	5699.4	Chinle
5697.0	5796.4	Shinarump
5799.0	5901.6	Moenkopi
6452.0	6575.2	Weber



RECEIVED

APR 23 2010

COGCC

LEASE NUMBER -
FEDERAL Beezley D-051174

12 POINT SURFACE USE PLAN
and
CERTIFYING STATEMENT per 3/7/2007 Federal Register Posting

BEEZLEY 5X22

API# applied for with COGCC

LOCATED IN

RANGELY WEBER SAND UNIT

2117 FNL & 1622' FEL (SW NE) Section 22, T2N, R103W

RIO BLANCO COUNTY, COLORADO

Please note that this will be
the 1st well of 2 on this location.

CHEVRON USA, Inc

Beezley 5X22

LEGAL DESCRIPTION : 2117 FNL & 1622 FEL (SWNE) Section 22, T2N, R103W, 6TH P.M.

1. EXISTING ROADS

See attached Topographic Map "B" and attached full Rangely Weber Sand Unit (COC 47675X) field map referenced as "ROAD MAP". Please note on "Addendum to Legal Plat" this location will be built on the existing road, no new access road needed.

To reach CHEVRON proposed BEEZLEY 5X22 location -
Proceed west out of Rangely, Colorado on Colorado State Highway 64 approximately 8 miles, turn South on Chevron lease road, proceed 3/4 mile to well location.

All of the improved surface roads in the area are maintained by Chevron or its subcontractors. This maintenance consists of some minor grade work for smoothing of road grades and for snow removal by road maintainers with dozer blades and other contractor's equipment as required.

2. PLANNED ACCESS ROAD

See Topographic Map "B".

The planned access road is directly off existing lease road. **No new access road is needed.** There are no fences on the property. Installing gates, cattle guards, or cutting fences will not be required. The terrain that is traversed by this road is relatively flat and is vegetated with sparse amounts of sagebrush and grasses. Turn outs will not be required.

Approval shall be requested to continue operations should the surface become saturated to a depth of three (3) inches. All permanent facilities placed on the location will be painted Carlsbad Canyon Brown (Fuller Brand Colorant 31293 or equivalent) to blend with the natural environment. ("Based on any location visits by BLM White River Office personnel or COGCC personnel, this could change".) The well cellar will be covered with steel grating and no hazards will exist for livestock or wildlife. Rehabilitation of the disturbed areas no longer needed for operation will meet the requirements the BLM.

3. EXISTING WELLS

See Topographic Map "C".

There are numerous wells within a one mile radius of this location. This is a long time established field.

4. LOCATION OF EXISTING AND PROPOSED FACILITIES

There are numerous facilities owned by Chevron within the Rangely Weber Sand Unit. **No** new production facilities will be required for this new well. All facilities maps are on file with the BLM – Meeker office. A complete set is of the oil (FLOWLINES), water (PROD. WATER) and gas (LP GAS GATHERING) gathering system maps have been submitted with this request. All produced fluids will be transported via 1989' pipeline to the central collection station to the northwest.

5. **LOCATION OF AND TYPE OF WATER SUPPLY AND FUEL GAS**

Water to be used in the drilling of this well will be from existing injection line on location. Fresh water required for boilers and other needs will be trucked from Chevron's domestic water treatment plant. Diesel fuel for drilling will be kept on location in a properly installed above ground diesel tank. (see "TYPICAL RIG LAYOUT – FUEL TRAILER")

There will be no water well drilled on the location site.

6. **SOURCE OF CONSTRUCTION MATERIALS**

See "Figure #1 and Figure #2"

Materials to be used in the re-arrangement of this location will be acquired during the re-arrangement. Any extra gravels, sand, or road base will be acquired from Ace West Trucking Inc, 15672 US Hwy 64, Rangely 675-2753 gravel pits, which are privately owned or leased from the Bureau of Land Management (BLM).

7. **METHODS FOR HANDLING WASTE DISPOSAL**

A closed – loop drilling system will be utilized, using a cuttings catch tank, dewatering system, centrifuge system and additional fluid storage. All waste products will be handled by RN Industries, 244 West Hwy 40, Roosevelt, Utah 84066 Dale Price 435-722-2800.

Trash will be confined in a covered container. After the rig is moved off the location the well site will be cleaned and all refuse removed by Rangely Trash Service 675-2878, and hauled to the approved landfill in Rio Blanco County.

A portable toilet will be supplied for human waste. Redi Services LLC, 235 County Rd 15, Meeker Colorado 970-878-4444 services toilets and removes portable toilet waste.

8. **ANCILLARY FACILITIES**

There are no ancillary facilities planned for at the present time and none foreseen in the near future.

9. WELL SITE LAYOUT . See Figure #1 and Figure #2

The White River Resource Area Manager shall be notified 24 hours in advance before any construction begins on the proposed location site.

10. PLANS FOR RESTORATION OF SURFACE

When all drilling and production activities have been completed, the location site will be reshaped to the original contour.

Any drainage re-routed during the construction activities shall be restored to their original line of flow as near as possible. Cuttings and drilling fluids will be buried in the reserve pit. Prior to burial of cutting and mud, any liquid oil or water will be trucked to the Recovery Plant.

The disturbed area not needed for well operation and access roads will be re-vegetated and rehabilitated per the remainder of this season.

The White River Resource Area Manager will be notified at least 24 hours prior to commencing reclamation work.

COMMON NAME	CULTIVAR	GENUS	SPECIES	97 RMP LBS PLS/ACRE	PERCENTAGE
Annual Sunflower Western	VNS	Helianthus	annus	2	12.50%
Wheatgrass Crested	Arriba	Agropyron	smithii	4	25.00%
Wheatgrass Pubescent	Nordan	Agropyron	cristatum intermediu	3	18.75%
Wheatgrass	Luna	Agropyron	m	4	25.00%
Russian Wildrye	Vinall	Psathyrostachys	junceus	3	18.75%
					100.00%

The seedbed will be prepared by disking following the natural contour. Drill seed on contour at a depth no greater than 1/2 inch. In areas that cannot be drilled, broadcast at double the seeding rate and harrow seed into soil. Certified seed will be used. Fall seeding must be completed after September 1, and prior to prolonged ground frost.

The access roads will be upgraded and maintained as necessary to prevent soil erosion, and accommodate year round traffic. Reshape areas unnecessary to operations, distribute topsoil, disk and seek all disturbed areas outside the work area according to the seed mixture chart. Perennial vegetation must be established. Additional work will be required in case of seeding failures, etc.1

When the well is abandoned, the location will be restored to approximately the original contours. During reclamation of the site, push the fill material into cuts and up over the back slope. Depressions will not be left that will trap water or form ponds. Distribute topsoil evenly over the location, and seed according to the seed

mixture chart. The access road and location will be disked prior to seeding. Perennial vegetation must be established.

Clean up and rehabilitation operations will begin as soon as the well is completed and should be finished within 90 – 120 days after well completion depending on seasonal growing months.

The permit holder will treat noxious weeds associated with the project by using Best Management Practices identified in Appendix D of the White River RMP of 1997.

11. SURFACE OWNERSHIP

A check of the records indicates that the surface owner is Bureau of Land Management.

12. OTHER INFORMATION

a) The Chevron will contact either the petroleum engineer or petroleum engineering technician 24 hours prior to the following operations:

- construction of well site
- spudding (including dry hole digger or rat hole rig)
- running and cementing of all casing strings
- pressure testing of BOPE or any casing string
- surface reclamation work.
- commencing completion operations.

b) Chevron will be responsible for informing all persons who are associated with the project operations that they will be subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. During operations, if discoveries of any cultural remains, monuments or sites, or any object of antiquity subject to the Antiquities Act of June, 1906 (34 Stat. 225; 16 U.S.C. Secs 431-433), the Archaeological Resources Protection Act of 1979 (PL 96-95), and 43 CFR, Part 3, operations will immediately cease and will be reported directly to the Area Manager. In cases where salvage excavation is necessary, the cost of such excavation shall be borne by the Operator, unless otherwise agreed upon. There are no known archeological, historic, or cultural sites in the immediate area. Much of the Unit area, over the past ninety three years, has been subjected to surface disturbance by roads, pipelines, and other producing surface facilities, and the probability of finding any artifactual remains or architecture of archeological significance is remote. An archeological study of the Rangely Unit area has been conducted and clearance given. An archaeologist's report of federal land within the Unit boundary is on file with the BLM.

c) Pursuant to 43 CFR 10.4(g) Chevron will notify the authorized officer (AO), by telephone, with written confirmation, immediately upon the discovery of human remains, funerary items, sacred objects, or objects of cultural patrimony. Further, pursuant to 43 CFR 10.4 (c) and (d), Chevron will stop activities in the vicinity of the discovery and protect it for 30 days or until notified to proceed by the authorized officer.

d) If paleontological materials (fossils) are uncovered during project activities, Chevron will immediately stop activities that might further disturb such materials, and contact the authorized officer (AO). The operator and the authorized officer will consult and determine the best option for avoiding or mitigating paleontological site damage.

e) An H2S Contingency Plan for this field is on file with the BLM. – copy available if requested

f) See attached "**Best Management Practices for Beezley 5X22 and Beezley 6X22 Location**" to be utilized at this well site.

Final reclamation at the completion of well plugging for this location is as follows:

Procedure for the Reclamation of P& A well site [Beezley 5X22 and 6X22](#).

Chevron will notify the WRFO 24 hours prior to any reclamation activities.

Rig anchors will be pulled and removed from location. The well pad will be re-contoured to original contour that blends with the surrounding landform and topsoil re-spread over the entire disturbed site to ensure successful re-vegetation. The topsoiled site will be prepared to provide a seedbed for re-establishment of vegetation. Water breaks will be installed only if absolutely necessary to prevent erosion. The seedbed will be prepared by disking following the natural contour. Drill seed on contour at a depth no greater than 1/2 inch. In areas that cannot be drilled, broadcast at double the seeding rate and harrow seed into soil. Certified seed will be used. Fall seeding must be completed after September 1, and prior to prolonged ground frost.

T2N

RECEIVED
APR 23 2013
COGCC

PROPOSED LOCATION:
BEEZLEY #6X22 & #5X22

BREEZLEY
562#4X22

0.35 MI. +/-

0.2 MI. +/-

0.2 MI. +/-

RANGELY 8.0 MI. +/-

R
103
W

LEGEND:

EXISTING ROAD

CHEVRON U.S.A., INC.

BEEZLEY #6X22 & #5X22
SECTION 22, T2N, R103W, 6th P.M.
SW 1/4 NE 1/4



Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813



ACCESS ROAD	1	1	00
MAP	MONTH	DAY	YEAR
SCALE: 1" = 2000'	DRAWN BY: Z.L.	REVISED: 00-00-00	
			B TOPO

T2N

RECEIVED
APR 23 2003
COGCC

PROPOSED LOCATION:
BEEZLEY #6X22 & #5X22

R
103
W

LEGEND:

- DISPOSAL WELLS
- PRODUCING WELLS
- SHUT IN WELLS
- WATER WELLS
- ABANDONED WELLS
- TEMPORARILY ABANDONED

CHEVRON U.S.A., INC.

BEEZLEY #6X22 & #5X22
SECTION 22, T2N, R103W, 6th P.M.
SW 1/4 NE 1/4



Utah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813



TOPOGRAPHIC MAP			
MONTH	DAY	YEAR	
SCALE: 1" = 2000'	DRAWN BY: J.H.	REVISED: 00-00-00	





SCALE: 1" = 200'

DATE: 12-10-09


DRAWN BY: D.R.B.

Revised: 02-18-10 D.R.B.

CHEVRON U.S.A., INC.

ADDENDUM TO LEGAL PLAT FOR

BEEZLEY #6X22 & #5X22
SECTION 22, T2N, R103W, 6th P.M.
SW 1/4 NE 1/4



RECEIVED

APR 23 2010

COGCC

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

RECEIVED

APR 23 2013




FIGURE #1

CHEVRON U.S.A., INC.

CONSTRUCTION LAYOUT FOR **COGCC**

BEEZLEY #6X22 & #5X22
SECTION 22, T2N, R103W, 6th P.M.
SW 1/4 NE 1/4

SCALE: 1" = 50'
DATE: 12-10-09
DRAWN BY: D.R.B.
Rev: 02-18-10 D.R.B.



Elev. Ungraded Ground At 6X22 Loc. Stake = 5594.1'
FINISHED GRADE ELEV. AT 6X22 LOC. STAKE = 5589.8'

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

CHEVRON U.S.A., INC.

CONSTRUCTION LAYOUT CROSS SECTION FOR

BEEZLEY #6X22 & #5X22

SECTION 22, T2N, R103W, 6th P.M.

SW 1/4 NE 1/4





FIGURE #2

1" = 20'
X-Section
Scale
1" = 50'

DATE: 12-10-09

DRAWN BY: D.R.B.

Revised: 02-18-10 D.R.B.



RECEIVED
APR 23 2010
COGCC

NOTE:

Topsoil should not be Stripped Below Finished Grade on Substructure Area.

APPROXIMATE ACREAGES

WELL SITE DISTURBANCE = ± 1.646 ACRES
PIPELINE DISTURBANCE = ± 1.370 ACRES
TOTAL = ± 3.016 ACRES

* NOTE:
FILL QUANTITY INCLUDES 5% FOR COMPACTION

APPROXIMATE YARDAGES

(6") Topsoil Stripping = 910 Cu. Yds.
(New Construction Only)
Remaining Location = 4,160 Cu. Yds.
TOTAL CUT = 5,070 CU.YDS.
FILL = 3,650 CU.YDS.

EXCESS MATERIAL = 1,420 Cu. Yds.
Topsoil & Pit Backfill = 1,420 Cu. Yds.
(1/2 Pit Vol.)
EXCESS UNBALANCE = 0 Cu. Yds.
(After Interim Rehabilitation)

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017



SCALE: 1" = 50'
DATE: 12-10-09
DRAWN BY: D.R.B.
Revised: 02-18-10 D.R.B.

CHEVRON U.S.A., INC.

TYPICAL RIG LAYOUT FOR

BEEZLEY #6X22 & #5X22

SECTION 22, T2N, R103W, 6th P.M.

SW 1/4 NE 1/4

FIGURE #3




Access Road

NOTE:

Flare Pit is to be located a min. of 100' from the Well Head.

Total Pit Capacity
W/2' of Freeboard
= 3,500 Bbls.±
Total Pit Volume
= 1,010 Cu. Yds



RECEIVED
APR 23 2010
COGCC

CHEVRON U.S.A., INC.

LOCATION DRAWING FOR

BEEZLEY #6X22 & #5X22

SECTION 22, T2N, R103W, 6th P.M.

Section Line

SW 1/4 NE 1/4

N87°44'17"W - 2640.63' (Meas.)

2007 UELS Alum.
Cap, Buried 0.3' Deep
Lat: 40.135886°
Long: 108.942453°




FIGURE #4

SCALE: 1" = 400'
DATE: 12-10-09
DRAWN BY: D.R.B.
Revised: 02-18-10 D.R.B.

1/2" Sucker Rod,
Set Marked Stone,
Pile of Stones
Lat: 40.135878°
Long: 108.933011°

B.L.M.
U.S.A.)



PLANT COMMUNITY

- ☐ DISTURBED GRASSLAND
- ☐ NATIVE GRASSLAND
- ☐ SHRUB LAND
- ☐ PLAINS RIPARIAN
- ☐ MOUNTAIN RIPARIAN
- ☐ FOREST LAND
- ☐ WETLANDS AQUATIC
- ☐ ALPINE
- ☐ OTHER (Describe):

RECEIVED
APR 23 2010
COGCC

LINE TABLE		
LINE	BEARING	LENGTH
L1	N12°56'56"W	142.64'
L2	N78°39'47"E	204.31'

B.L.M.
U.S.A.)



B.L.M.
U.S.A.)

CURRENT LAND USE

CROP LAND: ☐ IRRIGATED ☐ DRY LAND ☐ IMPROVED PASTURE ☐ HAY MEADOW ☐ CRP
NON-CROP LAND: ☐ RANGELAND ☐ TIMBER ☐ RECREATIONAL ☐ OTHER (Describe)
SUBDIVIDED: ☐ INDUSTRIAL ☐ COMMERCIAL ☐ RESIDENTIAL


FUTURE LAND USE

CROP LAND: ☐ IRRIGATED ☐ DRY LAND ☐ IMPROVED PASTURE ☐ HAY MEADOW ☐ CRP
NON-CROP LAND: ☐ RANGELAND ☐ TIMBER ☐ RECREATIONAL ☐ OTHER (Describe)
SUBDIVIDED: ☐ INDUSTRIAL ☐ COMMERCIAL ☐ RESIDENTIAL

2007 UELS Alum.
Cap, 0.4' High,
Steel Post
Lat: 40.128647°
Long: 108.933033°

UINTAH ENGINEERING & LAND SURVEYING

85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017



13. LESSEE'S OR OPERATOR'S REPRESENTATIVE and CERTIFICATION

**Application for Permit to Drill
Certifying Statement**

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in the APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

Executed this Day: Jan 19, 2010

Name: [Signature]

Printed Name: Jeff Roedell

Position Title: Technical Team Leader

Address: 100 Chevron Road, Chevron Rd, Rangely CO 81648

Telephone: 970-675-3816

Field Representative: Luke Allred - Operations Supervisor

Address: 100 Chevron Rd, Rangely CO

Telephone: 970-675-3846

RECEIVED

APR 23 2010

COGCC

Best Management Practices for Beezley 5x22 and 6x22 Location

Site Selection:

Site was selected to utilize one location for 2 directionally drilled wells, and this location is located along an existing lease road and utilizing part of a existing well pad. No additional road disturbance will be necessary. These 2 (two) producing wells will have gathering lines run to a centralized production facility placed offsite, no large haul truck will be need to collect fluids.

Erosion Control:

Topsoil Salvage and Storage: "Topsoil will be stockpiled where no vehicle traffic will cross topsoil mounds. Stockpiles shall be protected from wind and water erosion through the use of suitable weed-free mulch, seeding, and other measures as approved by BLM."

"Erosion and polluted runoff from oil and gas operations will be controlled. All Storm Water Discharge Permitting Regulations and BMP's currently required by the State of Colorado will be strictly complied with, particularly when streams may be affected." To minimize sedimentation of drainage channels and wetlands during the interim period between construction activity and final reclamation, temporary erosion and sediment control measures should be applied." If secondary containment will be engineered to handle 150% of calculated volumes per Chevron policy.

"Surface disturbance minimization. Existing roads shall be used to the greatest extent practicable to avoid erosion and minimize the land area devoted to oil and gas operations. Roadbeds shall be engineered to avoid or minimize impacts to riparian areas or wetlands to the extent practicable. Unavoidable impacts shall be mitigated. To the greatest extent practicable, all vehicles used by the operator, contractors, and other parties associated with the well shall not travel outside of the original access road boundary"

Wildlife Issues:


Design powerlines to minimize raptor electrocution risk. "Incorporate powerline and pole or tower designs to minimize the risk of raptor electrocution."

Health and Safety:

Chevron has a zero-tolerance policy regarding drug usage. All subcontractors prior to working in the Rangely Weber Sand Unit will have to demonstrate active drug, alcohol, and safety programs regarding hiring, training and conducting spot-checking programs. Chevron has a education and compliance program to help reinforce the zero-tolerance policy."

Train employees in safety practices; ensure use of protective equipment.

Emergency Response Plan: Hazardous/toxic materials safety: "Train all employees in effective environmental health and safety practices and ensure that proper personal protective equipment is available and being used"



Best Management Practices for Beezley 5x22 and 6x22 Location

Site Selection:

Site was selected to utilize one location for 2 directionally drilled wells, and this location is located along an existing lease road and utilizing part of a existing well pad. No additional road disturbance will be necessary. These 2 (two) producing wells will have gathering lines run to a centralized production facility placed offsite, no large haul truck will be need to collect fluids.

Erosion Control:

Topsoil Salvage and Storage: "Topsoil will be stockpiled where no vehicle traffic will cross topsoil mounds. Stockpiles shall be protected from wind and water erosion through the use of suitable weed-free mulch, seeding, and other measures as approved by BLM."

"Erosion and polluted runoff from oil and gas operations will be controlled. All Storm Water Discharge Permitting Regulations and BMP's currently required by the State of Colorado will be strictly complied with, particularly when streams may be affected." To minimize sedimentation of drainage channels and wetlands during the interim period between construction activity and final reclamation, temporary erosion and sediment control measures should be applied." If secondary containment will be engineered to handle 150% of calculated volumes per Chevron policy.

"Surface disturbance minimization. Existing roads shall be used to the greatest extent practicable to avoid erosion and minimize the land area devoted to oil and gas operations. Roadbeds shall be engineered to avoid or minimize impacts to riparian areas or wetlands to the extent practicable. Unavoidable impacts shall be mitigated. To the greatest extent practicable, all vehicles used by the operator, contractors, and other parties associated with the well shall not travel outside of the original access road boundary"

Wildlife Issues:

Design powerlines to minimize raptor electrocution risk. "Incorporate powerline and pole or tower designs to minimize the risk of raptor electrocution."

Health and Safety:

Chevron has a zero-tolerance policy regarding drug usage. All subcontractors prior to working in the Rangely Weber Sand Unit will have to demonstrate active drug, alcohol, and safety programs regarding hiring, training and conducting spot-checking programs. Chevron has a education and compliance program to help reinforce the zero-tolerance policy."

Train employees in safety practices; ensure use of protective equipment.

Emergency Response Plan: Hazardous/toxic materials safety: "Train all employees in effective environmental health and safety practices and ensure that proper personal protective equipment is available and being used"