

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refilling ☐
Sidetrack ☐

Document Number:

2589199

Plugging Bond Surety

20090080

3. Name of Operator: GREAT WESTERN OIL & GAS COMPANY LLC

4. COGCC Operator Number: 10110

5. Address: 503 MAIN ST

City: WINDSOR State: CO Zip: 80550

6. Contact Name: JEFF REALE Phone: (970)686-8831 Fax: (866)413-3354

Email: JREALE@GWOGCO.COM

7. Well Name: HCW Well Number: 24-24

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7500

WELL LOCATION INFORMATION

10. QtrQtr: SESW Sec: 24 Twp: 6N Rng: 67W Meridian: 6

Latitude: 40.467090 Longitude: -104.844310

Footage at Surface: 660 FNL/FSL FSL 1984 FEL/FWL FWL

11. Field Name: LAPOUDRE Field Number: 48125

12. Ground Elevation: 4754 13. County: WELD

14. GPS Data:

Date of Measurement: 01/20/2010 PDOP Reading: 1.6 Instrument Operator's Name: E. HERNANDEZ

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____

Sec: _____ Twp: _____ Rng: _____ Sec: _____ Twp: _____ Rng: _____

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 685 ft

18. Distance to nearest property line: 638 ft 19. Distance to nearest well permitted/completed in the same formation: 925 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA-CODELL	NB-CD		80	E/2SW4

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
SEE ATTACHED EXHIBIT "A" FOR DESCRIPTION AND PLAT.

25. Distance to Nearest Mineral Lease Line: 638 ft 26. Total Acres in Lease: 146

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	530	265	530	0
1ST	7+7/8	4+1/2	11.6	7,500	525	7,500	3,000

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments CONDUCTOR CASING WILL NOT BE SET. 30 DAY LETTER WAIVED IN SUA.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: JEFF REALE

Title: VP OPERATIONS Date: 3/18/2010 Email: JREALE@GWOGCO.COM

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nashin Director of COGCC Date: 4/28/2010

API NUMBER

05 123 31499 00

Permit Number: _____ Expiration Date: 4/27/2012

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) Note surface casing setting depth change from 500' to 530'. Increase cement coverage accordingly. 2) Provide 24 hour notice of MIRU to Ed Binkley at 970-506-9834 or e-mail at ed.binkley@state.co.us 3) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Sussex to 200' above Sussex. Verify coverage with cement bond log.

Attachment Check List

Att Doc Num	Name	Doc Description
1770235	SURFACE CASING CHECK	LF@2454394 1770235
2109872	SURFACE AGRMT/SURETY	LF@2439382 2109872
2589199	MINERAL LEASE MAP	LF@2439383 2589199
2589200	WELL LOCATION PLAT	LF@2439366 2589200
2589202	TOPO MAP	LF@2439384 2589202
2589206	SURFACE AGRMT/SURETY	LF@2439367 2589206

Total Attach: 6 Files