

FORM
2
Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE ZONE COMMINGLE ZONE

Refiling
Sidetrack

Document Number:
2096407
Plugging Bond Surety

3. Name of Operator: EXXON MOBIL CORPORATION 4. COGCC Operator Number: 28600

5. Address: P O BOX 4358
City: HOUSTON State: TX Zip: 77210-4358

6. Contact Name: MARK DEL PICO Phone: (281)654-1926 Fax: (281)654-1940
Email: MARK.DELPICO@EXXONMOBIL.COM

7. Well Name: FREEDOM UNIT Well Number: 297-33A4

8. Unit Name (if appl): FREEDOM UNIT Unit Number: COC69547X

9. Proposed Total Measured Depth: 12400

WELL LOCATION INFORMATION

10. QtrQtr: SENE Sec: 33 Twp: 2S Rng: 97W Meridian: 6
Latitude: 39.835599 Longitude: -108.276830

Footage at Surface: 1716 FNL/FSL FNL 195 FEL/FWL FEL

11. Field Name: PICEANCE CREEK Field Number: 68800

12. Ground Elevation: 6314 13. County: RIO BLANCO

14. GPS Data:

Date of Measurement: 04/16/2008 PDOP Reading: 2.3 Instrument Operator's Name: D. PETTY

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1990 FNL 1158 FWL 1990 FNL 1158 FWL
Sec: 33 Twp: 2S Rng: 97W Sec: 33 Twp: 2S Rng: 97W

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 265 ft

18. Distance to nearest property line: 195 ft 19. Distance to nearest well permitted/completed in the same formation: 934 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
MESAVERDE	MVRD			
OHIO CREEK	OHCRK			
WASATCH	WSTC			

21. Mineral Ownership: Fee State Federal Indian Lease #: COC62806

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No Surface Owners Agreement Attached or \$25,000 Blanket Surface Bon \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
SEE ATTACHED MAP AND MINERAL LEASE DESCRIPTION.

25. Distance to Nearest Mineral Lease Line: 1158 ft 26. Total Acres in Lease: 1467

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? Yes No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal: Offsite Onsite

Method: Land Farming Land Spreading Disposal Facility Other: BURIAL

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	20	16	LINEPIPE	120	100	120	0
SURF	14+3/4	10+3/4	45.5	3,900	2,180	3,900	0
1ST	9+7/8	7	26	8,300	1,310	8,300	3,400
2ND	6+1/8	4+1/2	15.1	12,400	650	12,400	5,600

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments THIS IS A REFILE OF APD. NO CHANGES TO ORIGINAL APD. THE PAD & PITS HAVE BEEN BUILT, THUS NO FORM 2A IS REQUIRED. CURRENT APD EXPIRES 05/27/2009. THE FRU 297-33A5 WELL HAS BEEN SPUD. 1. The pad has been built.
2. The pits have been constructed.
3. The refiled well will not require any expansion / additional surface disturbance of the pad.
4. The location does not require a variance from any of the rules listed in Rule 306.d.(1).(A).(ii).
5. The location is not in a wildlife restricted surface occupancy area.
Statements added per Mark Del Pico 04/26/2010 RE

34. Location ID: 336020

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: MARK DEL PICO

Title: REGULATORY Date: 2/22/2010 Email: MARK.DELPICO@EXXONMO

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 4/28/2010

API NUMBER

05 103 11293 00

Permit Number: _____

Expiration Date: 4/27/2011**CONDITIONS OF APPROVAL, IF ANY:**

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1)COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED. 2)RESERVE PIT MUST BE LINED. 3)CEMENT TOP VERIFICATION BY CBL REQUIRED. 4) OPERATOR MUST ENSURE 110 PERCENT SECONDARY CONTAINMENT FOR ANY VOLUME OF FLUIDS CONTAINED AT WELL SITE DURING DRILLING AND COMPLETION OPERATIONS.IF FLUIDS ARE CONVEYED VIA PIPELINE, OPERATOR MUST IMPLEMENT BEST MANAGEMENT PRACTICES TO CONTAIN ANY UNINTENTIONAL RELEASE OF FLUIDS. 5)THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE MINIMIS AMOUNTS. AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1. 6)NO PORTION OF ANY PIT THAT WILL BE USED TO HOLD LIQUIDS SHALL BE CONSTRUCTED ON FILL MATERIAL, UNLESS THE PIT AND FILL SLOPE ARE DESIGNED AND CERTIFIED BY A PROFESSIONAL ENGINEER, SUBJECT TO REVIEW AND APPROVAL BY THE DIRECTOR PRIOR TO CONSTRUCTION OF THE PIT.THE CONSTRUCTION AND LINING OF THE PIT SHALL BE SUPERVISED BY A PROFESSIONAL ENGINEER OR THEIR AGENT. THE ENTIRE BASE OF THE PIT MUST BE IN CUT. 7)THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 000 FEET DEEP.

Attachment Check List

Att Doc Num	Name	Doc Description
2096407	APD ORIGINAL	LF@2423448 2096407
2096408	LEGAL/LEASE DESCRIPTION	LF@2423449 2096408
400042819	FORM 2 SUBMITTED	LF@2430901 400042819

Total Attach: 3 Files