

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400051957

Plugging Bond Surety

20060021

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: ROSETTA RESOURCES OPERATING LP

4. COGCC Operator Number: 10159

5. Address: 717 TEXAS STE 2800

City: HOUSTON State: TX Zip: 77002

6. Contact Name: SHAWN HILDRETH Phone: (713)335-4104 Fax: (281)763-2320

Email: SHAWN.HILDRETH@ROSETTARESOURCES.COM

7. Well Name: TRUITT Well Number: 10-03

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 2209

WELL LOCATION INFORMATION

10. QtrQtr: NENW Sec: 10 Twp: 3S Rng: 44W Meridian: 6

Latitude: 39.816855 Longitude: -102.290803

Footage at Surface: 334 FNL/FSL FNL 1530 FEL/FWL FWL

11. Field Name: WILDCAT Field Number: 99999

12. Ground Elevation: 3720 13. County: YUMA

14. GPS Data:

Date of Measurement: 01/29/2010 PDOP Reading: 1.4 Instrument Operator's Name: CHRIS PEARSON

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_ Bottom Hole: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_

Sec: \_\_\_\_\_ Twp: \_\_\_\_\_ Rng: \_\_\_\_\_ Sec: \_\_\_\_\_ Twp: \_\_\_\_\_ Rng: \_\_\_\_\_

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 2115 ft

18. Distance to nearest property line: 1530 ft 19. Distance to nearest well permitted/completed in the same formation: 1480 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR			

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20060022

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
T3S R44W SECTION 10:NW/4, N/2NE/4, SW/4NE/4, SW/4, S/2SE/4, NW/4SE/4 AND OTHER LANDS

25. Distance to Nearest Mineral Lease Line: 1530 ft 26. Total Acres in Lease: 1770

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	9+7/8	7	17	400	180	400	0
1ST	6+1/8	4+1/2	10.5	2,209	90	2,209	1,809

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☐ Rotating Head ☐ None

33. Comments NO CONDUCTOR CASING WILL BE USED.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: SHAWN HILDRETH

Title: REGULATORY ANALYST Date: 4/1/2010 Email: SHAWN.HILDRETH@ROSETT

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 4/28/2010

#### API NUMBER

05 125 11844 00

Permit Number: \_\_\_\_\_ Expiration Date: 4/27/2012

CONDITIONS OF APPROVAL, IF ANY:

**All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.**

1) Provide 24 hr notice of spud to Craig Quint at 719-767-8939 or e-mail at craig.quint@state.co.us. 2) Set surface casing at least 50' into Pierre Shale for aquifer coverage, (400' minimum - as proposed). Setting surface casing less than the approved depth is a permit violation unless prior written approval is obtained from the COGCC. 3) If completed, provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log. 4) If dry hole, set 35 sks cement 50' above Niobrara top, 35 sks cement ½ out, ½ in surface casing, 10 sks cement at top of surface casing, cut casing 4' below GL, weld on plate, 5 sks cement in rat hole & 5 sks cement in mouse hole.

### **Attachment Check List**

Att Doc Num	Name	Doc Description
2110239	SURFACE CASING CHECK	LF@2451456 2110239
400051974	WELL LOCATION PLAT	LF@2446906 400051974
400051975	TOPO MAP	LF@2448035 400051975
400051994	30 DAY NOTICE LETTER	LF@2446907 400051994
400051995	30 DAY NOTICE LETTER	LF@2446908 400051995
400053680	FORM 2 SUBMITTED	LF@2448036 400053680

Total Attach: 6 Files