

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400027358

Plugging Bond Surety

20030009

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: NOBLE ENERGY INC

4. COGCC Operator Number: 100322

5. Address: 1625 BROADWAY STE 2200

City: DENVER State: CO Zip: 80202

6. Contact Name: KATE MILLER Phone: (303)228-4449 Fax: (303)228-4280

Email: kmiller@nobleenergyinc.com

7. Well Name: MARLEY C Well Number: 01-28D

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 6995

WELL LOCATION INFORMATION

10. QtrQtr: NENW Sec: 1 Twp: 4N Rng: 64W Meridian: 6

Latitude: 40.346980 Longitude: -104.500900

Footage at Surface: 613 FNL/FSL 2021 FEL/FWL FWL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4605 13. County: WELD

14. GPS Data:

Date of Measurement: 10/01/2009 PDOP Reading: 2.4 Instrument Operator's Name: ROBERT DALEY

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 150 FSL 2515 FEL/FWL FWL Bottom Hole: FNL/FSL 150 FSL 2515 FEL/FWL FWL
Sec: 36 Twp: 5N Rng: 64W Sec: 36 Twp: 5N Rng: 64W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 450 ft

18. Distance to nearest property line: 553 ft 19. Distance to nearest well permitted/completed in the same formation: 765 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL	407-87	160	GWA
NIOBRARA	NBRR	407-87	160	GWA

21. Mineral Ownership: ☐ Fee ☒ State ☐ Federal ☐ Indian Lease #: 0/7324-S

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
Section 36, T5N, R64W: SW/4

25. Distance to Nearest Mineral Lease Line: 150 ft 26. Total Acres in Lease: 160

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: CLOSED LOOP

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	500	215	500	0
1ST	7+7/8	4+1/2	11.6	6,995	621	6,995	

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☐ Rotating Head ☐ None

33. Comments NO CONDUCTOR CASING WILL BE USED. TOC=200' ABOVE THE NIOBRARA. UNIT CONFIGURATION: SEC. 1,T4N,R64W: NWNE, NENW. SEC. 36,T5N,R64W: SWSE,SESW

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: KATE MILLER

Title: REGULATORY ANALYST Date: 3/1/2010 Email: kmiller@nobleenergyinc.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 4/28/2010

API NUMBER

05 123 31508 00

Permit Number: _____ Expiration Date: 4/27/2012

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COGCC ENG COA - SME 1) Provide 24 hr notice of spud to to Bo Brown at 970-330-6085 or email at bo.brown@state.co.us . 2) Set surface casing per Rule 317d, cement to surface. Setting surface casing less than the approved depth is a permit violation unless prior written approval is obtained from the COGCC. 3) If completed, provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log. 4) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name	Doc Description
1725694	SURFACE CASING CHECK	LF@2443105 1725694
400043724	PROPOSED SPACING UNIT	LF@2432699 400043724
400043728	SURFACE AGRMT/SURETY	LF@2432704 400043728
400043729	30 DAY NOTICE LETTER	LF@2432707 400043729
400043730	DEVIATED DRILLING PLAN	LF@2432718 400043730
400043731	WELL LOCATION PLAT	LF@2432719 400043731
400043732	FORM 2 SUBMITTED	LF@2432720 400043732

Total Attach: 7 Files