

FORM

2

Rev  
12/05

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400056335

Plugging Bond Surety

## APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

## 2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐Refiling ☐Sidetrack ☐3. Name of Operator: BARRETT CORPORATION\* BILL4. COGCC Operator Number: 100715. Address: 1099 18TH ST STE 2300City: DENVER State: CO Zip: 802026. Contact Name: Matt Barber Phone: (303)312-8168 Fax: (303)291-0420Email: mbarber@billbarrettcorp.com7. Well Name: GGU Federal Well Number: 43C-29-6918. Unit Name (if appl): Gibson Gulch Unit Number: COC-052447X9. Proposed Total Measured Depth: 7621

## WELL LOCATION INFORMATION

10. QtrQtr: NWSE Sec: 29 Twp: 6S Rng: 91W Meridian: 6Latitude: 39.496661 Longitude: -107.575761Footage at Surface: 1829 FNL/FSL FSL 2074 FEL/FWL FEL11. Field Name: Mamm Creek Field Number: 5250012. Ground Elevation: 6030.7 13. County: GARFIELD

## 14. GPS Data:

Date of Measurement: 03/23/2010 PDOP Reading: 2.7 Instrument Operator's Name: D. Slaugh15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone:	FNL/FSL	FEL/FWL	Bottom Hole:	FNL/FSL	FEL/FWL
<u>2064</u>	<u>FSL</u>	<u>664</u>	<u>2064</u>	<u>FSL</u>	<u>664</u>
		<u>FEL</u>			<u>FEL</u>
Sec: <u>29</u>	Twp: <u>6S</u>	Rng: <u>91W</u>	Sec: <u>29</u>	Twp: <u>6S</u>	Rng: <u>91W</u>

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No17. Distance to the nearest building, public road, above ground utility or railroad: 299 ft18. Distance to nearest property line: 513 ft 19. Distance to nearest well permitted/completed in the same formation: 352 ft

20.

## LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Iles	ILES	191-9		
Williams Fork	WMFK	191-65		

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
Please see the attached lease map

25. Distance to Nearest Mineral Lease Line: 664 ft 26. Total Acres in Lease: 600

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: Evaporation & Backfilling

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	26	16	42#	40		40	0
SURF	12+1/4	9+5/8	36#	800	250	800	0
1ST	8+3/4	4+1/2	11.6#	7,621	510	7,621	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments SEE ADDENDUM TO LEGAL PLAT (SHEET 2o) FOR VISIBLE IMPROVEMENTS WITHIN 400'. A NEW LOCATION ASSESSMENT HAS BEEN SUBMITTED FOR THE PROPOSED PAD EXPANSION: GGU FED (MDP #15) 34D-29-691 (DOC:400056347). IN ADDITION, THIS WELL IS APPROVED UNDER A FEDERAL ENVIRONMENTAL ASSESSMENT THROUGH THE BLM SILT, CO. OFFICE. PRODUCTION CEMENT TOP IS 500' ABOVE TOP OF SURFACE. PRODUCTINO STRING SECOND HOLE SIZE = 7 7/8.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Matt Barber

Title: Permit Analyst Date: \_\_\_\_\_ Email: mbarber@billbarrettcorp.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

API NUMBER

05

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

**CONDITIONS OF APPROVAL, IF ANY:** \_\_\_\_\_

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

**Attachment Check List**

Att Doc Num	Name	Doc Description
400056341	WELL LOCATION PLAT	43C.pdf
400056342	ACCESS ROAD MAP	Access Road Map.pdf
400056343	LEASE MAP	Lease Map.pdf
400056344	LOCATION DRAWING	Location Drawing.pdf
400056345	DRILLING PLAN	WBD GGU Swanson Federal 43C-29-691.pdf
400056346	DEVIATED DRILLING PLAN	GGU Federal 43C-29-691 Directional Plan.pdf
400056431	OTHER	Addendum.pdf
400056702	SURFACE AGRMT/SURETY	Swanson Memo SUA 12-22-2005.pdf

Total Attach: 8 Files