

FORM

2

Rev  
12/05

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

## APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

## 2. TYPE OF WELL

 OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
 SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐
Refiling ☐Sidetrack ☐

Document Number:

400057026

Plugging Bond Surety

20030107

3. Name of Operator: WILLIAMS PRODUCTION RMT COMPANY

4. COGCC Operator Number: 96850

5. Address: 1515 ARAPAHOE ST STE 1000

City: DENVER State: CO Zip: 80202

6. Contact Name: Howard Harris Phone: (303)606-4086 Fax: (303)629-8272

Email: howard.harris@williams.com

7. Well Name: Federal Well Number: PA 311-21

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 9067

## WELL LOCATION INFORMATION

10. QtrQtr: SENW Sec: 21 Twp: 6S Rng: 95W Meridian: 6

Latitude: 39.510786 Longitude: -108.008150

Footage at Surface: 2501 FNL/FSL FNL 1398 FEL/FWL FWL

11. Field Name: Parachute Field Number: 67350

12. Ground Elevation: 6024 13. County: GARFIELD

## 14. GPS Data:

Date of Measurement: 02/23/2009 PDOP Reading: 1.5 Instrument Operator's Name: Robert Kay

15. If well is ☒ Directional ☐ Horizontal (highly deviated) submit deviated drilling plan.
 Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL  
 533 FNL 793 FWL 533 FNL 793 FWL  
 Sec: 21 Twp: 6S Rng: 95W Sec: 21 Twp: 6S Rng: 95W
16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 7716 ft

18. Distance to nearest property line: 3026 ft 19. Distance to nearest well permitted/completed in the same formation: 322

## 20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Williams Fork	WMFK	440-25		Unspaced

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: 62161

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
See Attached

25. Distance to Nearest Mineral Lease Line: 533 ft 26. Total Acres in Lease: 2299

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Re-Use, Evaporation & Back

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	24	18	48	45	25	45	0
SURF	13+1/2	9+5/8	32.3	1,239	432	1,239	0
1ST	7+7/8	4+1/2	11.6	9,067	627	9,067	5,213

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Closed Mud System. See Williams Production RMT Master APD dated 4/27/06 for Federal 10 Point Drilling Plan and 13 Point Surface Use Plan. Top of cement for production string will be approx. 200' above the top of Mesaverde.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Howard Harris

Title: Sr. Regulatory Specialist Date: \_\_\_\_\_ Email: howard.harris@williams.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

API NUMBER

05

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

**Attachment Check List**

Att Doc Num	Name	Doc Description
400058696	DEVIATED DRILLING PLAN	PA 311-21 Dir Page Plot 20Apr10 JMS.pdf
400058697	DEVIATED DRILLING PLAN	PA 311-21 Dir Plan 20Apr10 JMS.pdf
400058698	WELL LOCATION PLAT	Plat PA 311-21.pdf
400058699	LEASE MAP	Lease 62161.pdf
400058700	FED. DRILLING PERMIT	Fed APD PA 311-21.pdf

Total Attach: 5 Files