

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refiling ☐
Sidetrack ☐

Document Number:

1813817

Plugging Bond Surety

20030107

3. Name of Operator: WILLIAMS PRODUCTION RMT COMPANY

4. COGCC Operator Number: 96850

5. Address: 1515 ARAPAHOE ST STE 1000

City: DENVER State: CO Zip: 80202

6. Contact Name: GREG DAVIS Phone: (303)606-4071 Fax: (303)629-8272

Email: GREG.J.DAVIS@WILLIAMS.COM

7. Well Name: SAVAGE Well Number: RWF 331-35

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7759

WELL LOCATION INFORMATION

10. QtrQtr: NWNE Sec: 35 Twp: 6S Rng: 94W Meridian: 6

Latitude: 39.487244 Longitude: -107.853259

Footage at Surface: 694 FNL/FSL FNL 2060 FEL/FWL FEL

11. Field Name: RULISON Field Number: 75400

12. Ground Elevation: 5442 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 04/23/2008 PDOP Reading: 6.0 Instrument Operator's Name: J. KIRPATRICK

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 719 FNL 1775 FEL 719 FEL 1775 FEL
Sec: 35 Twp: 6S Rng: 94W Sec: 35 Twp: 6S Rng: 94W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 260 ft

18. Distance to nearest property line: 554 ft 19. Distance to nearest well permitted/completed in the same formation: 356 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
WILLIAMS FORK	WMFK	139-66	640	ALL

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
SEE ATTACHED

25. Distance to Nearest Mineral Lease Line: 435 ft 26. Total Acres in Lease: 1016

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: CLOSED LOOP/RE-USE

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	24	18	48	45		45	0
SURF	13+1/2	9+5/8	32.3	1,104		1,104	0
1ST	7+7/8	4+1/2	11.6	7,759		7,759	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments CLOSED LOOP

34. Location ID: 323908

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: Y Print Name: GREG DAVIS

Title: SUPERVISOR PERMITS Date: 6/25/2009 Email: GREG.J.DAVIS@WILLIAMS.C

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 9/27/2009

API NUMBER

05 045 18749 00

Permit Number: _____ Expiration Date: 9/26/2011

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

NO CONDITIONS FOUND

24-HOUR SPUD NOTICE REQUIRED. E-MAIL david.Andrews@state.co.us GARFIELD COUNTY RULISON-FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE.

CEMENT-TOP VERIFICATION BY CBL REQUIRED. THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE-MINIMIS AMOUNTS. AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1. THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 250 FEET DEEP.

Attachment Check List

Att Doc Num	Name	Doc Description
1711131	LOCATION PICTURES	LF@2089247 1711131
1711132	LOCATION PICTURES	LF@2089245 1711132
1711133	LOCATION PICTURES	LF@2089243 1711133
1711134	WELL LOCATION PLAT	LF@2089077 1711134
1711135	TOPO MAP	LF@2089078 1711135
1711136	OIL & GAS LEASE	LF@2089079 1711136
1711137	SURFACE AGRMT/SURETY	LF@2089080 1711137
1711138	DEVIATED DRILLING PLAN	LF@2089081 1711138
1711139	DRILLING PLAN	LF@2089082 1711139
400007199	APD ORIG & 1 COPY	LF@2089076 400007199

Total Attach: 10 Files