

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400028348

Plugging Bond Surety

20030058

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: EOG RESOURCES INC

4. COGCC Operator Number: 27742

5. Address: 600 17TH ST STE 1100N

City: DENVER State: CO Zip: 80202

6. Contact Name: Nick Mathis Phone: (303)262-2894 Fax: (303)262-2895

Email: Nick.Mathis@eogresources.com

7. Well Name: Critter Creek Well Number: 08-14H

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 11462

WELL LOCATION INFORMATION

10. QtrQtr: SESE Sec: 14 Twp: 11N Rng: 63W Meridian: 6

Latitude: 40.916886 Longitude: -104.392964

Footage at Surface: 600 FNL/FSL FSL 600 FEL/FWL FEL

11. Field Name: Wildcat Field Number: 99999

12. Ground Elevation: 5214.1 13. County: WELD

14. GPS Data:

Date of Measurement: 12/16/2009 PDOP Reading: 1.3 Instrument Operator's Name: ROBERT L. KAY

15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 994 FSL 865 FEL 600 FEL/FWL 2300 FEL 600  
Sec: 14 Twp: 63W Rng: 11N Sec: 14 Twp: 11N Rng: 63W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 4701 ft

18. Distance to nearest property line: 600 ft 19. Distance to nearest well permitted/completed in the same formation: 10560 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR	NA		NA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
All Section 14, T11N, R63W of the 6th P.M.

25. Distance to Nearest Mineral Lease Line: 600 ft 26. Total Acres in Lease: 640

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Back fill and cover

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	20	16		60		0	0
SURF	13+1/2	9+5/8	36	1,400	730	1,400	0
1ST	8+3/4	7	23	7,501	795	7,501	0
1ST LINER	6+1/4	4+1/2	11.6	11,462	355	11,462	6,650

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments EOG will earn the lease, upon drilling the well, pursuant to the Farmout Option Contract between EOG and Anadarko

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Nick Mathis

Title: Regulatory Assistant Date: 2/3/2010 Email: Nick\_Mathis@eogresources.co

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 3/2/2010

#### API NUMBER

05 123 31222 00

Permit Number: \_\_\_\_\_ Expiration Date: 2/29/2012

CONDITIONS OF APPROVAL, IF ANY:

**All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.**

COGCC ENG COA – SME 1) Provide 24 hr notice of MIRU to Bo Brown at 970-392-4124 or e-mail at bo.brown@state.co.us. 2) Set surface casing per Rule 317d, setting surface casing less than the approved depth is a permit violation unless prior written approval is obtained from the COGCC. 3) If production casing is set, cement coverage shall be at a minimum from the production casing shoe to 200' above Niobrara. Verify all placed cement with cement bond log. 4) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

### **Attachment Check List**

Att Doc Num	Name	Doc Description
1725589	SURFACE CASING CHECK	LF@2426192 1725589
400029736	SURFACE AGRMT/SURETY	LF@2272205 400029736
400029997	TOPO MAP	LF@2272218 400029997
400029998	WELL LOCATION PLAT	LF@2272232 400029998
400034396	DEVIATED DRILLING PLAN	LF@2272243 400034396
400034397	DEVIATED DRILLING PLAN	LF@2272253 400034397
400035196	DRILLING PLAN	LF@2272263 400035196
400035269	FORM 2 SUBMITTED	LF@2272274 400035269

Total Attach: 8 Files