

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

1774889

Plugging Bond Surety

20020067

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☒

Refiling ☐

Sidetrack ☐

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: NICK G CURRAN Phone: (720)876-5288 Fax: (720)876-6288  
Email: NICK.CURRAN@ENCANA.COM

7. Well Name: CANYON CREEK Well Number: 43-13

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 8607

WELL LOCATION INFORMATION

10. QtrQtr: NWSE Sec: 13 Twp: 1N Rng: 69W Meridian: 6

Latitude: 40.049570 Longitude: -105.063100

Footage at Surface: 2045 FNL/FSL FSL 2133 FEL/FWL FEL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 5058 13. County: BOULDER

14. GPS Data:

Date of Measurement: 09/23/2009 PDOP Reading: 1.5 Instrument Operator's Name: TOM WINANS

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1990 FSL 510 FEL FEL Bottom Hole: FNL/FSL 1990 FSL 510 FEL FEL  
Sec: 13 Twp: 1N Rng: 69W Sec: 13 Twp: 1N Rng: 69W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 307 ft

18. Distance to nearest property line: 213 ft 19. Distance to nearest well permitted/completed in the same formation: 2360 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL	407-87	160	SE/4
J SAND	JSND	232-23	160	SE/4
NIOBRARA	NBRR	407-87	160	SE/4

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20090011

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
NESE LESS THE 5 ACRE TRACT DESCRIBED AS W2SWNESE

25. Distance to Nearest Mineral Lease Line: 50 ft 26. Total Acres in Lease: 35

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	790	280	790	
1ST	7+7/8	4+1/2	11.6	8,607	300	8,607	7,442
			Stage Tool	5,496	250	5,496	4,460

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments NO CONDUCTOR CASING WILL BE USED.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: NICK G CURRAN

Title: PERMITTING AGENT Date: 12/8/2009 Email: NICK.CURRAN@ENCANA.CO

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 1/19/2010

API NUMBER

05 013 06632 00

Permit Number: \_\_\_\_\_ Expiration Date: 1/18/2012

CONDITIONS OF APPROVAL, IF ANY:

**All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.**

1) Note surface casing setting depth change from 650' to 790'. Increase cement coverage accordingly and cement to surface. 2) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us 3) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log. 4) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

### **Attachment Check List**

Att Doc Num	Name	Doc Description
1769729	SURFACE CASING CHECK	LF@2202013 1769729.00000
1774890	WELL LOCATION PLAT	LF@2192286 1774890
1774891	TOPO MAP	LF@2192287 1774891
1774892	MINERAL LEASE MAP	LF@2192487 1774892
1774893	30 DAY NOTICE LETTER	LF@2192288 1774893
1774894	DEVIATED DRILLING PLAN	LF@2192289 1774894
400020582	FORM 2 SUBMITTED	LF@2198380 400020582
400033959	APD ORIGINAL	LF@2192285 400033959

Total Attach: 8 Files