

FORM
2
Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE ZONE COMMINGLE ZONE

Refiling
Sidetrack

Document Number:
2585273
Plugging Bond Surety
20030107

3. Name of Operator: WILLIAMS PRODUCTION RMT COMPANY 4. COGCC Operator Number: 96850

5. Address: 1515 ARAPAHOE ST STE 1000
City: DENVER State: CO Zip: 80202

6. Contact Name: GREG DAVIS Phone: (303)606-4071 Fax: (303)629-8272
Email: GREG.J.DAVIS@WILLIAMS.COM

7. Well Name: FEDERAL Well Number: RU 31-5

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 10028

WELL LOCATION INFORMATION

10. QtrQtr: NENW Sec: 5 Twp: 7S Rng: 93W Meridian: 6
Latitude: 39.474819 Longitude: -107.798791

Footage at Surface: 197 FNL/FSL FNL 2607 FEL/FWL FWL

11. Field Name: RULISON Field Number: 75400

12. Ground Elevation: 7604 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 07/03/2008 PDOP Reading: 6.0 Instrument Operator's Name: J. KIRKPATRICK

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
177 FNL 1789 FEL 177 FNL 1789 FEL
Sec: 5 Twp: 7S Rng: 93W Sec: 5 Twp: 7S Rng: 93W

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 9269 ft

18. Distance to nearest property line: 1254 ft 19. Distance to nearest well permitted/completed in the same formation: 768 ft

20. LEASE, SPACING AND POOLING INFORMATION

| Objective Formation(s) | Formation Code | Spacing Order Number(s) | Unit Acreage Assigned to Well | Unit Configuration (N/2, SE/4, etc.) |
|------------------------|----------------|-------------------------|-------------------------------|--------------------------------------|
| WILLIAMS FORK | WMFK | 139-76 | | |

21. Mineral Ownership: Fee State Federal Indian Lease #: COC41916

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No Surface Owners Agreement Attached or \$25,000 Blanket Surface Bon \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
 T6S-R93W: SEC 20: SE; SEC 32: ALL. T7S-R93W: SEC 5: LOTS 1, 2: S/2 SEC 6: SE

25. Distance to Nearest Mineral Lease Line: 1789 ft 26. Total Acres in Lease: 1361

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? Yes No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal: Offsite Onsite

Method: Land Farming Land Spreading Disposal Facility Other: RE-USED

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

| Casing Type | Size of Hole | Size of Casing | Weight Per Foot | Setting Depth | Sacks Cement | Cement Bottom | Cement Top |
|-------------|--------------|----------------|-----------------|---------------|--------------|---------------|------------|
| CONDUCTOR | 24+1/1 | 18 | 48 | 45 | 25 | 45 | 0 |
| SURF | 13+1/2 | 9+5/8 | 32.3 | 1,106 | 400 | 1,106 | 0 |
| 1ST | 7+7/8 | 4+1/2 | 11.6 | 10,028 | 775 | 10,028 | |

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments **CLOSED LOOP. PAD HAS NOT BEEN BUILT. THERE HAVE BEEN NO CHANGES TO LEASE CONDITIONS OR DRILLING PLANS SINCE THE ORIGINAL FORM 2 WAS FILED. SEE WILLIAMS PRODUCTION RMT COMPANY MASTGER APD, STANDARD OPERATING PRACTICES VERSION: APRIL 27, 2006 FOR DRILLING PLAN AND SURFACE USE PLAN.**

34. Location ID: 383328

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: GREG DAVIS

Title: PERMIT Date: 12/18/2009 Email: GREG.J.DAVIS@WILLIAMS.C

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 3/2/2010

API NUMBER
05 045 18260 00

Permit Number: _____ Expiration Date: 2/29/2012

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

(1) 24-HOUR SPUD NOTICE REQUIRED. E-MAIL Shaun.Kellerby@state.co.us (2) GARFIELD COUNTY RULISON-FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE. (3) NEW MAMM CREEK FIELD NOTICE TO OPERATORS APPLIES TO THIS WELL. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE. (4) THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE-MINIMIS AMOUNTS. AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1. (5) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 160 FEET DEEP.

Attachment Check List

| Att Doc Num | Name | Doc Description |
|-------------|----------------------|----------------------|
| 2585274 | FED. DRILLING PERMIT | LF@2201760 2585274 |
| 400024530 | FORM 2 SUBMITTED | LF@2208058 400024530 |
| 400046532 | APD ORIGINAL | LF@2201759 400046532 |

Total Attach: 3 Files