

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

1774404

Plugging Bond Surety

20030107

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: WILLIAMS PRODUCTION RMT COMPANY

4. COGCC Operator Number: 96850

5. Address: 1515 ARAPAHOE ST STE 1000

City: DENVER State: CO Zip: 80202

6. Contact Name: HOWARD HARRIS Phone: (303)606-4086 Fax: (303)629-8272

Email: HOWARD.HARRIS@WILLIAMS.COM

7. Well Name: DIAMOND ELK Well Number: PA 442-12

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 8620

WELL LOCATION INFORMATION

10. QtrQtr: NWNE Sec: 12 Twp: 7S Rng: 95W Meridian: 6

Latitude: 39.458612 Longitude: -107.944351

Footage at Surface: 421 FNL/FSL FNL 1930 FEL/FWL FEL

11. Field Name: PARACHUTE Field Number: 67350

12. Ground Elevation: 6289 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 07/08/2009 PDOP Reading: 6.0 Instrument Operator's Name: J. KIRKPATRICK

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 2071 FNL 335 FEL FEL Bottom Hole: FNL/FSL 2071 FNL 335 FEL FEL
Sec: 12 Twp: 7S Rng: 95W Sec: 12 Twp: 7S Rng: 95W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 331 ft

18. Distance to nearest property line: 606 ft 19. Distance to nearest well permitted/completed in the same formation: 335 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
WILLIAMSFORK	WMFK	440-16	640	SECTION(ALL)

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: CACO07217
9

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20010113

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
SEE ATTACHED

25. Distance to Nearest Mineral Lease Line: 678 ft 26. Total Acres in Lease: 669

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: RE-USE

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	24	18	48	45	25	45	0
SURF	13+1/2	9+5/8	32.3	2,837	990	2,837	0
1ST	7+7/8	4+1/2	11.6	8,620	612	8,620	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments CLOSED LOOP MUD SYSTEM. THERE WILL BE TOTAL OF 64 WELLS IN SECTION WHEN DRILLED OUT, THERE IS TOTAL OF 658 ACRES IN SECTION.

34. Location ID: 334723

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: HOWARD HARRIS

Title: REGULATORY Date: 11/25/2009 Email: HOWARD.HARRIS@WILLIAM

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 1/20/2010

API NUMBER

05 045 19022 00

Permit Number: _____ Expiration Date: 1/19/2012

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

24 HOUR SPUD NOTICE REQUIRED. E-MAIL: david.andrews@state.co.us GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE CEMENT TOP VERIFICATION BY CBL REQUIRED. THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 390 FEET DEEP.

Attachment Check List

Att Doc Num	Name	Doc Description
1774405	LOCATION PICTURES	LF@2181867 1774405
1774406	LOCATION PICTURES	LF@2181868 1774406
1774407	LOCATION PICTURES	LF@2181866 1774407
1774408	WELL LOCATION PLAT	LF@2191669 1774408
1774409	TOPO MAP	LF@2182097 1774409
1774410	MINERAL LEASE MAP	LF@2182098 1774410
1774411	DEVIATED DRILLING PLAN	LF@2182099 1774411
1774412	DRILLING PLAN	LF@2182100 1774412
1791442	LOCATION DRAWING	LF@2209820 1791442
400018276	FORM 2 SUBMITTED	LF@2191495 400018276
400034221	APD ORIGINAL	LF@2182096 400034221

Total Attach: 11 Files