

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400030566

Plugging Bond Surety

20030009

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: NOBLE ENERGY INC

4. COGCC Operator Number: 100322

5. Address: 1625 BROADWAY STE 2200

City: DENVER State: CO Zip: 80202

6. Contact Name: MARI CLARK Phone: (303)228-4413 Fax: (303)228-4286

Email: mclark@nobleenergyinc.com

7. Well Name: SHABLE USX AB Well Number: 11-09P

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 9150

WELL LOCATION INFORMATION

10. QtrQtr: NESE Sec: 11 Twp: 7N Rng: 64W Meridian: 6

Latitude: 40.585970 Longitude: -104.509280

Footage at Surface: 1980 FNL/FSL FSL 660 FEL/FWL FEL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4834 13. County: WELD

14. GPS Data:

Date of Measurement: 12/18/2009 PDOP Reading: 2.8 Instrument Operator's Name: DAVID C HOLMES

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____

Sec: _____ Twp: _____ Rng: _____ Sec: _____ Twp: _____ Rng: _____

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 3285 ft

18. Distance to nearest property line: 660 ft 19. Distance to nearest well permitted/completed in the same formation: 1725 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL	UNSPACED	80	N/2SE/4
LYONS	LYNS	UNSPACED	80	N/2SE/4
NIOBRARA	NBRR	UNSPACED	80	N/2SE/4

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20030012

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
T7N, R64W, SECTION 11: ALL

25. Distance to Nearest Mineral Lease Line: 660 ft 26. Total Acres in Lease: 640

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	9+5/8	36	750	165	750	0
1ST	8+3/4	7+0/0	26	9,150	622	9,150	

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☐ Rotating Head ☐ None

33. Comments No conductor casing will be used. 1st string top of cement = 200' above Niobrara

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: MARI CLARK

Title: REG. ANALYST II Date: 2/10/2010 Email: mclark@nobleenergyinc.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nashin Director of COGCC Date: 3/19/2010

API NUMBER

05 123 31319 00

Permit Number: _____ Expiration Date: 3/17/2012

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COGCC ENG COA - SME 1) Provide 24 hr notice of spud to Bo Brown at 970-330-6085 or email at bo.brown@state.co.us. 2) Set surface casing per Rule 317d, cement to surface. Setting surface casing less than the approved depth is a permit violation unless prior written approval is obtained from the COGCC. 3) If completed, provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log.

Attachment Check List

Att Doc Num	Name	Doc Description
1725630	SURFACE CASING CHECK	LF@2431310 1725630
400037612	WELL LOCATION PLAT	LF@2424565 400037612
400037613	30 DAY NOTICE LETTER	LF@2424566 400037613
400039221	FORM 2 SUBMITTED	LF@2424567 400039221

Total Attach: 4 Files