

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

1783941

Plugging Bond Surety

20090067

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: WIEPKING-FULLERTON ENERGY LLC

4. COGCC Operator Number: 96340

5. Address: 4600 S DOWNING ST

City: ENGLEWOOD State: CO Zip: 80110

6. Contact Name: JACK FINCHAM Phone: (303)906-3335 Fax: (303)761-9067

Email: FINCHAM4@MSNC.COM

7. Well Name: ALOHA MULA Well Number: 8

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 8400

WELL LOCATION INFORMATION

10. QtrQtr: nsw Sec: 19 Twp: 10s Rng: 55w Meridian: 6

Latitude: 39.162380 Longitude: -103.600940

Footage at Surface: 1984 FNL/FSL FSL 656 FEL/FWL FWL

11. Field Name: great plains Field Number: 32756

12. Ground Elevation: 5257 13. County: LINCOLN

14. GPS Data:

Date of Measurement: 06/05/2009 PDOP Reading: 1.7 Instrument Operator's Name: keith westfall

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_ Bottom Hole: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_

Sec: \_\_\_\_\_ Twp: \_\_\_\_\_ Rng: \_\_\_\_\_ Sec: \_\_\_\_\_ Twp: \_\_\_\_\_ Rng: \_\_\_\_\_

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 4600 ft

18. Distance to nearest property line: 656 ft 19. Distance to nearest well permitted/completed in the same formation: 1315 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
ARBUCKLE	ABCK			
CHEROKEE	CHRK			
LANSING	LNSNG			
MARMATON	MRTN			
MORROW	MRRW			

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
SEC 19: ALL, T10s, R55W

25. Distance to Nearest Mineral Lease Line: 656 ft 26. Total Acres in Lease: 640

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	300	240	300	0
1ST	7+7/8	5+1/2	17	8,400	325	8,400	5,000

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☐ Rotating Head ☐ None

33. Comments NO CONDUCTOR CASING TO BE USED

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: JACK FINCHAM

Title: AGENT Date: 7/21/2009 Email: FINCHAM4@MSN.COM

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nashin Director of COGCC Date: 8/31/2009

#### API NUMBER

05 073 06385 00

Permit Number: \_\_\_\_\_ Expiration Date: 8/31/2011

CONDITIONS OF APPROVAL, IF ANY: \_\_\_\_\_

**All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.**

1) Provide 24 hour notice of MIRU to Mike Leonard at 719-767-2805 or e-mail at mike.leonard@ state.co.us. 2) If production casing is set provide cement coverage to at least 200' above Lansing, and stage cement Cheyenne Dakota (4630'-4070' minimum). Run CBL to verify primary and stage cement jobs. 3) If well is a dry hole set plugs at the following depths: 40 sks cement +/- 50' above the Lansing, 40 sks cement above any DST zone, 40 sks cement 100' below base of Cheyenne (4630' up), 40 sks cement 50' above top of Dakota (4070' up), 50 sks cement from 50' below surface casing shoe up into surface casing, 10 sks cement in top of surface casing, cut 4 ft below GL, weld on plate, 5 sks cement in rat hole and mouse hole.

SEE ATTACHED NOTICE CONCERNING OPERATING REQUIREMENTS FOR WILDLIFE PROTECTION

### **Attachment Check List**

Att Doc Num	Name	Doc Description
1783942	WELL LOCATION PLAT	LF@2103616 1783942
1783943	TOPO MAP	LF@2103617 1783943
1783944	SURFACE AGRMT/SURETY	LF@2103618 1783944
1783945	30 DAY NOTICE LETTER	LF@2103619 1783945
400003900	APD ORIG & 1 COPY	LF@2103615 400003900

Total Attach: 5 Files