

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refilling ☐
Sidetrack ☐

Document Number:

400016130

Plugging Bond Surety

20020067

3. Name of Operator: ENCANA OIL & GAS (USA) INC 4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700
City: DENVER State: CO Zip: 80202-5632

6. Contact Name: Julia Carter Phone: (720)876.5240 Fax: (720)876.6240
Email: Julia.Carter@encana.com

7. Well Name: N. Parachute Well Number: WF04C-25 H26 59

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 10922

WELL LOCATION INFORMATION

10. QtrQtr: SENE Sec: 26 Twp: 5S Rng: 96W Meridian: 6
Latitude: 39.586658 Longitude: -108.129664

Footage at Surface: 2453 FNL/FSL FNL 650 FEL/FWL FEL

11. Field Name: Grand Valley Field Number: 31290

12. Ground Elevation: 6090 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 10/30/2008 PDOP Reading: 1.7 Instrument Operator's Name: Robert Kay

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 699 FNL 303 FWL 699 FNL 303 FWL
Sec: 25 Twp: 5S Rng: 96W Sec: 25 Twp: 5S Rng: 96W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 7142 ft

18. Distance to nearest property line: 5479 ft 19. Distance to nearest well permitted/completed in the same formation: 442 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Williams Fork	WMFK	510-13		

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
Please see attached maps

25. Distance to Nearest Mineral Lease Line: 621 ft 26. Total Acres in Lease: 25889

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Recycle & Bury

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	26	16	Line Pipe	90	8	90	0
SURF	13+1/2	9+5/8	36	1,700	321	1,700	0
2ND	7+7/8	4+1/2	11.6	10,922	815	10,922	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments EnCana Oil & Gas (USA) Inc. owns surface, EnCana minerals. Please see attached maps. The full well number is WF04C-25 H26 596. Surface casing hole size will be both 13-1/2" and 12-1/4". Second string, or production casing, hole size will be 7-7/8", 8-1/2" and 8-3/4" with cement top 200' above Williams Fork. Cement top for both conductor and surface casing will be run to surface. A request to pass through BLM minerals leased to Williams to reach our fee BHL minerals was submitted to the BLM via sundry notice. This correspondence was included with the Form 2A.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Julia M. Carter

Title: Regulatory Analyst Date: 11/16/2009 Email: Julia.Carter@encana.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline Director of COGCC Date: 1/20/2010

Permit Number: _____ Expiration Date: 1/19/2012

API NUMBER

05 045 19045 00

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

24-HOUR SPUD NOTICE REQUIRED. E-MAIL david.Andrews@state.co.us GARFIELD COUNTY RULISON-FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE. CEMENT-TOP VERIFICATION BY CBL REQUIRED. OPERATOR MUST ENSURE 110 PERCENT SECONDARY CONTAINMENT FOR ANY VOLUME OF FLUIDS CONTAINED AT WELL-SITE DURING DRILLING AND COMPLETION OPERATIONS. IF FLUIDS ARE CONVEYED VIA PIPELINE, OPERATOR MUST IMPLEMENT BEST-MANAGEMENT-PRACTICES TO CONTAIN ANY UNINTENTIONAL RELEASE OF FLUIDS. THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE-MINIMIS AMOUNTS. AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1. THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 000 FEET DEEP.

This is an exception location as it is the second pad in the QQ have requested such letter and waiver. This letter was attached to the 2A doc. # 400006984 BY 1/20/10

Attachment Check List

Att Doc Num	Name	Doc Description
400016131	PLAT	LF@2395429 400016131
400016132	DEVIATED DRILLING PLAN	LF@2395430 400016132
400016133	LEASE MAP	LF@2395431 400016133
400016134	TOPO MAP	LF@2395432 400016134
400016135	FORM 2 SUBMITTED	LF@2395433 400016135

Total Attach: 5 Files