

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refiling ☐
Sidetrack ☐

Document Number:

400018427

Plugging Bond Surety

20050043

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: Judith Walter Phone: (720)876-3702 Fax: (720)876-4702
Email: judith.walter@encana.com

7. Well Name: Story Gulch Unit Well Number: 8507D-25 F25496

8. Unit Name (if appl): Story Gulch Unt Unit Number: COC69333X

9. Proposed Total Measured Depth: 13828

WELL LOCATION INFORMATION

10. QtrQtr: SENW Sec: 25 Twp: 4S Rng: 96W Meridian: 6

Latitude: 39.674231 Longitude: -108.119808

Footage at Surface: 2308 FNL/FSL FNL 1894 FEL/FWL FWL

11. Field Name: Wildcat Field Number: 99999

12. Ground Elevation: 8298 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 08/07/2009 PDOP Reading: 2.0 Instrument Operator's Name: Robert Kay

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 2628 FNL 2010 FEL 2628 FNL 2010 FEL
Sec: 25 Twp: 4S Rng: 96W Sec: 25 Twp: 4S Rng: 96W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 333 ft

18. Distance to nearest property line: 1894 ft 19. Distance to nearest well permitted/completed in the same formation: 350 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Iles	ILES			
William Fork	WMFK	510-13	10	

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: COC61136

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 0

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
T4S, R96W, Section 25: ALL

25. Distance to Nearest Mineral Lease Line: 2010 ft 26. Total Acres in Lease: 640

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: Recycle. Amend and bury

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	26	20	Line Pipe	120	176	120	0
SURF	14+3/4	9+5/8	36	3,000	2,069	3,000	0
2ND	8+3/4	4+1/2	11.6	13,828	857	13,828	8,167

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments Surface hole: 12-1/4" or 13-1/2" or 14-3/4", Production hole: 7-7/8" or 8-3/4", Production Cmt Top calc 500' above TOG. On-site was 8/12/2009 with BLM and CDOW both from Meeker, Colorado.

34. Location ID: 0

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Judith Walter

Title: Regulatory Analyst Date: 12/1/2009 Email: judith.walter@encana.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 2/11/2010

API NUMBER

05 045 19137 00

Permit Number: _____ Expiration Date: 2/10/2012

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1)24 HOUR SPUD NOTICE REQUIRED. E-MAIL: david.andrews@state.co.us 2)GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE 3)CEMENT TOP VERIFICATION BY CBL REQUIRED. 4)THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 000 FEET DEEP.

Attachment Check List

Att Doc Num	Name	Doc Description
400018429	PLAT	LF@2198696 400018429
400018430	ACCESS ROAD MAP	LF@2198697 400018430
400018431	MINERAL LEASE MAP	LF@2198698 400018431
400018432	DEVIATED DRILLING PLAN	LF@2198699 400018432
400018433	FED. DRILLING PERMIT	LF@2198700 400018433
400019119	LOCATION DRAWING	LF@2198701 400019119
400019120	FORM 2 SUBMITTED	LF@2198702 400019120

Total Attach: 7 Files