

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

1758449

Plugging Bond Surety

20030009

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: NOBLE ENERGY INC

4. COGCC Operator Number: 100322

5. Address: 1625 BROADWAY STE 2200

City: DENVER State: CO Zip: 80202

6. Contact Name: MARI CLARK Phone: (303)228-4413 Fax: (303)228-4286

Email: MCLARK@NOBLEENERGYINC.COM

7. Well Name: GUTTERSEN STATE CC Well Number: 20-21

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 6870

WELL LOCATION INFORMATION

10. QtrQtr: NESW Sec: 20 Twp: 4N Rng: 63W Meridian: 6

Latitude: 40.297580 Longitude: -104.462370

Footage at Surface: 2576 FNL/FSL FSL 2422 FEL/FWL FWL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4746 13. County: WELD

14. GPS Data:

Date of Measurement: 04/21/2009 PDOP Reading: 1.5 Instrument Operator's Name: STEVEN A. LUND

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____

Sec: _____ Twp: _____ Rng: _____ Sec: _____ Twp: _____ Rng: _____

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 5280 ft

18. Distance to nearest property line: 2422 ft 19. Distance to nearest well permitted/completed in the same formation: 780 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL	407-87	160	GWA
NIOBRARA	NBRR	407-87	160	GWA

21. Mineral Ownership: ☐ Fee ☒ State ☐ Federal ☐ Indian Lease #: 70/7860S

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20030012

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
4N, 63W, SEC. 20: ALL

25. Distance to Nearest Mineral Lease Line: 2422 ft 26. Total Acres in Lease: 640

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☒ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	550	232	550	0
1ST	7+7/8	4+1/2	11.6	6,870	602	6,870	

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☐ Rotating Head ☐ None

33. Comments NO CONDUCTOR CASING WILL BE USED.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: MARI CLARK

Title: REGULATORY ANALYST Date: 8/18/2009 Email: MCLARK @NOBLEENERGYIN

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 11/13/2009

API NUMBER

05 123 30752 00

Permit Number: _____ Expiration Date: 11/12/2011

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) Provide 24 hr notice of spud to Ed Binkley at 970-506-9834 or e-mail at ed.binkley@state.co.us . 2) Setting surface casing less than the approved depth is a permit violation unless prior written approval is obtained from the COGCC. 3) If completed, provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log. 4) If dry hole, 40 sks cement 50' above Niobrara top, 50 sks cement ½ out, ½ in surface casing, 10 sks cement top of surface casing, cut 4' below GL, weld on plate, 5 sks cement in rat hole 5 sks cement in mouse hole. Restore surface location.

Attachment Check List

Att Doc Num	Name	Doc Description
1758459	WELL LOCATION PLAT	LF@2126712 1758459
1758460	30 DAY NOTICE LETTER	LF@2126714 1758460
1758461	EXCEPTION LOC REQUEST	LF@2126716 1758461
1758462	EXCEPTION LOC WAIVERS	LF@2126718 1758462
1758463	PROPOSED SPACING UNIT	LF@2126720 1758463
1940510	SURFACE CASING CHECK	LF@2139369 1940510
400017443	APD ORIGINAL	LF@2126710 400017443

Total Attach: 7 Files