

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refilling ☐
Sidetrack ☐

Document Number:

400029922

Plugging Bond Surety

20030058

3. Name of Operator: EOG RESOURCES INC

4. COGCC Operator Number: 27742

5. Address: 600 17TH ST STE 1100N

City: DENVER State: CO Zip: 80202

6. Contact Name: Nick Mathis Phone: (303)262-2894 Fax: (303)262-2894

Email: Nick.Mathis@eogresources.com

7. Well Name: Garden Creek Well Number: 06-11H

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 10965

WELL LOCATION INFORMATION

10. QtrQtr: SESE Sec: 11 Twp: 11N Rng: 62W Meridian: 6

Latitude: 40.931011 Longitude: -104.279628

Footage at Surface: 501 FNL/FSL FSL FEL/FWL 501 FEL

11. Field Name: Wildcat Field Number: 99999

12. Ground Elevation: 5163 13. County: WELD

14. GPS Data:

Date of Measurement: 12/22/2009 PDOP Reading: 1.6 Instrument Operator's Name: Uintah Engineering & Land Surveying

15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 718 FSL 928 FEL 2550 FNL 600 FEL FWL
Sec: 11 Twp: 11N Rng: 62W Sec: 11 Twp: 11N Rng: 62W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 498 ft

18. Distance to nearest property line: 501 ft 19. Distance to nearest well permitted/completed in the same formation: 24657 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR			

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
EOG will earn the lease, upon drilling the well, pursuant to the Farmout Option Contract between EOG and Anadarko.

25. Distance to Nearest Mineral Lease Line: 600 ft 26. Total Acres in Lease: 548

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☐ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Back fill and cover

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	20	16		60		0	0
SURF	13+1/2	9+5/8	36	1,220	625	1,220	0
1ST	8+3/4	7	23	7,237	765	7,237	0
1ST LINER	6+1/4	4+1/2	11.6	11,655	390	11,655	6,387

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments _____

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Nick Mathis

Title: Regulatory Assistant Date: 1/21/2010 Email: Nick_Mathis@eogresources.co

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 3/2/2010

API NUMBER 05 123 31221 00	Permit Number: _____ Expiration Date: <u>2/29/2012</u>
--------------------------------------	--

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COGCC ENG COA – SME 1) Provide 24 hr notice of MIRU to Bo Brown at 970-392-4124 or e-mail at bo.brown@state.co.us. 2) Note surface casing setting depth change from 1200' to 1220'. Increase cement coverage accordingly and cement to surface. Set surface casing per Rule 317d, setting surface casing less than the approved depth is a permit violation unless prior written approval is obtained from the COGCC. 3) If production casing is set, cement coverage shall be at a minimum from the production casing shoe to 200' above Niobrara. Verify all placed cement with cement bond log. 4) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name	Doc Description
1725594	SURFACE CASING CHECK	LF@2426189 1725594
400030748	WELL LOCATION PLAT	LF@2304296 400030748
400030749	TOPO MAP	LF@2304300 400030749
400030750	SURFACE AGRMT/SURETY	LF@2304302 400030750
400030752	DEVIATED DRILLING PLAN	LF@2304305 400030752
400030753	DRILLING PLAN	LF@2304309 400030753
400030754	DEVIATED DRILLING PLAN	LF@2304312 400030754
400030755	FORM 2 SUBMITTED	LF@2304315 400030755

Total Attach: 8 Files