

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refilling ☐
Sidetrack ☐

Document Number:

400019232

Plugging Bond Surety

20030009

3. Name of Operator: NOBLE ENERGY INC

4. COGCC Operator Number: 100322

5. Address: 1625 BROADWAY STE 2200

City: DENVER State: CO Zip: 80202

6. Contact Name: LINDA PAVELKA Phone: (303)228-4064 Fax: (303)228-4286
Email: lpavelka@nobleenergyinc.com

7. Well Name: SGV FEDERAL Well Number: 8-11B

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7684

WELL LOCATION INFORMATION

10. QtrQtr: NWNW Sec: 8 Twp: 8S Rng: 95W Meridian: 6

Latitude: 39.381736 Longitude: -108.026151

Footage at Surface: 1215 FNL/FSL FNL 350 FEL/FWL FEL

11. Field Name: PARACHUTE Field Number: 67350

12. Ground Elevation: 6626 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 12/15/2008 PDOP Reading: 3.9 Instrument Operator's Name: JOHN RICHARDSON

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 488 FNL 701 FWL 488 FNL 701 FWL
Sec: 8 Twp: 8S Rng: 95W Sec: 8 Twp: 8S Rng: 95W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 8057 ft

18. Distance to nearest property line: 4846 ft 19. Distance to nearest well permitted/completed in the same formation: 330 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
ILES	ILES	139-59	40	NWNW
WILLIAMS FORK	WMFK	139-59	40	NWNW

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: COC58670

22. Surface Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
SEE ATTACHED

25. Distance to Nearest Mineral Lease Line: 701 ft 26. Total Acres in Lease: 1086

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: EVAP. PIT

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	20	16	LINE PIPE	60	15	60	0
SURF	12+1/4	8+5/8	24	1,500	425	1,500	0
1ST	7+7/8	4+1/2	11.6	7,674	460	7,674	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments THE PRODUCTION CASING TOP OF CEMENT WILL BE 200' ABOVE TOP OF GAS.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: LINDA PAVELKA

Title: REGULATORY SPECIALIST Date: 12/9/2009 Email: lpavelka@nobleenergyinc.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 2/11/2010

API NUMBER

05 045 19129 00

Permit Number: _____ Expiration Date: 2/10/2012

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1)24 HOUR SPUD NOTICE REQUIRED. E-MAIL: david.andrews@state.co.us 2)GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE 3)CEMENT TOP VERIFICATION BY CBL REQUIRED. 4)THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 000 FEET DEEP.

Attachment Check List

Att Doc Num	Name	Doc Description
400019889	OIL & GAS LEASE	LF@2201380 400019889
400019890	DEVIATED DRILLING PLAN	LF@2201381 400019890
400020999	PLAT	LF@2201383 400020999
400021000	FED. DRILLING PERMIT	LF@2201384 400021000
400021001	FORM 2 SUBMITTED	LF@2395149 400021001

Total Attach: 5 Files