

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400029292

Plugging Bond Surety

20040060

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: BARRETT CORPORATION* BILL

4. COGCC Operator Number: 10071

5. Address: 1099 18TH ST STE 2300

City: DENVER State: CO Zip: 80202

6. Contact Name: Matt Barber Phone: (303)312-8168 Fax: (303)291-0420
Email: mbarber@billbarrettcorp.com

7. Well Name: Werner Well Number: 31D-26-692

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7648

WELL LOCATION INFORMATION

10. QtrQtr: SWSE Sec: 23 Twp: 6S Rng: 92W Meridian: 6

Latitude: 39.506908 Longitude: -107.630502

Footage at Surface: 543 FNL/FSL FSL 1609 FEL/FWL FEL

11. Field Name: Mamm Creek Field Number: 52500

12. Ground Elevation: 5950.4 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 10/08/2009 PDOP Reading: 6.0 Instrument Operator's Name: James A Kalmon

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FNL/FSL Bottom Hole: FNL/FSL FNL/FSL
183 FNL 1996 FEL 183 FNL 1996 FEL
Sec: 26 Twp: 6S Rng: 92W Sec: 26 Twp: 6S Rng: 92W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 293 ft

18. Distance to nearest property line: 283 ft 19. Distance to nearest well permitted/completed in the same formation: 327 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Iles	ILES	191-10	640	All
Williams Fork	WMFK	191-8	640	All

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
See attached Lease Boundary Map

25. Distance to Nearest Mineral Lease Line: 677 ft 26. Total Acres in Lease: 2200

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Evaporation & Backfilling

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	26	16	42	40		40	0
SURF	12+1/4	9+5/8	36	800	250	800	0
1ST	8+3/4	4+1/2	11.6	7,648	490	7,648	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments See addendum for visible improvements within 400' of this location.
This well is located at the pending Werner 44C-23-692 Form 2A.
BBC is the surface owner.
Casing comments: production string second hole size = 7 7/8, production cement top = 500' above top of gas

34. Location ID: 416197

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Matt Barber

Title: Permit Analyst Date: 1/21/2010 Email: mbarber@billbarrettcorp.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 3/19/2010

API NUMBER

05 045 19248 00

Permit Number: _____ Expiration Date: 3/17/2012

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1)24 HOUR SPUD NOTICE REQUIRED. E-MAIL: Shaun.Kellerby@state.co.us 2)GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE 3)NEW MAMM CREEK FIELD NOTICE TO OPERATORS APPLIES TO THIS WELL. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE 4)THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 390 FEET DEEP.

Attachment Check List

Att Doc Num	Name	Doc Description
400030798	ACCESS ROAD MAP	LF@2222071 400030798
400030799	LEASE MAP	LF@2222072 400030799
400030800	DEVIATED DRILLING PLAN	LF@2222073 400030800
400030801	LOCATION DRAWING	LF@2222074 400030801
400030802	WELL LOCATION PLAT	LF@2222075 400030802
400030805	DRILLING PLAN	LF@2222076 400030805
400031217	FORM 2 SUBMITTED	LF@2222077 400031217

Total Attach: 7 Files