

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400032253

Plugging Bond Surety

20030058

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: EOG RESOURCES INC

4. COGCC Operator Number: 27742

5. Address: 600 17TH ST STE 1100N

City: DENVER State: CO Zip: 80202

6. Contact Name: Nick Mathis Phone: (303)262-2894 Fax: (303)262-2895

Email: Nick.Mathis@eogresources.com

7. Well Name: Randall Creek Well Number: 04-32H

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 11296

WELL LOCATION INFORMATION

10. QtrQtr: NENE Sec: 32 Twp: 12N Rng: 62W Meridian: 6

Latitude: 40.972000 Longitude: -104.339189

Footage at Surface: 501 FNL/FSL 1200 FEL/FWL FEL

11. Field Name: Wildcat Field Number: 99999

12. Ground Elevation: 5346 13. County: WELD

14. GPS Data:

Date of Measurement: 01/14/2010 PDOP Reading: 1.4 Instrument Operator's Name: Uintah Engineering and Land Surveying

15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 967 FNL 1096 FEL/FWL 600 FSL 600 FEL/FWL FEL  
Sec: 32 Twp: 12N Rng: 62W Sec: 32 Twp: 12N Rng: 62W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 501 ft

18. Distance to nearest property line: 501 ft 19. Distance to nearest well permitted/completed in the same formation: 7710 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR		640	ALL

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20090114

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
See attached Legal/Lease Description

25. Distance to Nearest Mineral Lease Line: 600 ft 26. Total Acres in Lease: 8940

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☐ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Backfill and Cover

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	20	16		60		0	0
SURF	13+1/2	9+5/8	36	1,400	730	1,400	0
1ST	8+3/4	7	23	7,543	800	7,543	0
1ST LINER	6+1/4	4+1/2	11.6	11,296	340	11,296	6,693

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments \_\_\_\_\_

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Nick Mathis

Title: Regulatory Assistant Date: 1/26/2010 Email: Nick\_Mathis@eogresources.co

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 3/4/2010

<b>API NUMBER</b> 05 123 31233 00	Permit Number: _____ Expiration Date: 3/2/2012
--------------------------------------	--

**CONDITIONS OF APPROVAL, IF ANY:** \_\_\_\_\_

**All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.**

COGCC ENG COA – SME 1) Provide 24 hr notice of MIRU to Bo Brown at 970-392-4124 or e-mail at bo.brown@state.co.us. 2) Set surface casing per Rule 317d, setting surface casing less than the approved depth is a permit violation unless prior written approval is obtained from the COGCC. 3) If production casing is set, cement coverage shall be at a minimum from the production casing shoe to 200' above Niobrara. Verify all placed cement with cement bond log. 4) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

### **Attachment Check List**

Att Doc Num	Name	Doc Description
1725586	SURFACE CASING CHECK	LF@2426187 1725586
2589074	LEGAL/LEASE DESCRIPTION	LF@2425841 2589074
400032280	DRILLING PLAN	LF@2327444 400032280
400032282	DEVIATED DRILLING PLAN	LF@2327445 400032282
400032283	DEVIATED DRILLING PLAN	LF@2327446 400032283
400032284	TOPO MAP	LF@2327447 400032284
400032286	WELL LOCATION PLAT	LF@2327448 400032286
400032538	FORM 2 SUBMITTED	LF@2327449 400032538

Total Attach: 8 Files