

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

1791176

Plugging Bond Surety

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: BARRETT CORPORATION* BILL

4. COGCC Operator Number: 10071

5. Address: 1099 18TH ST STE 2300

City: DENVER State: CO Zip: 80202

6. Contact Name: MATT BARBER Phone: (303)312-8168 Fax: (303)291-0420
Email: MBARBER@BILLBARRETTCORP.COM

7. Well Name: GGU FED Well Number: 12D-33-691

8. Unit Name (if appl): GIBSON GULCH Unit Number: COC-052447X

9. Proposed Total Measured Depth: 7651

WELL LOCATION INFORMATION

10. QtrQtr: SWNW Sec: 33 Twp: 6S Rng: 91W Meridian: 6

Latitude: 39.486076 Longitude: -107.567911

Footage at Surface: 2071 FNL/FSL 93 FEL/FWL FWL

11. Field Name: MAMM CREEK Field Number: 52500

12. Ground Elevation: 6373 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 08/27/2009 PDOP Reading: 2.9 Instrument Operator's Name: D. SLAUGH

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1475 FNL 664 FWL FWL Bottom Hole: FNL/FSL 1475 FNL 664 FWL FWL
Sec: 33 Twp: 6S Rng: 91W Sec: 33 Twp: 6S Rng: 91W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 2733 ft

18. Distance to nearest property line: 2744 ft 19. Distance to nearest well permitted/completed in the same formation: 340 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
ILES	ILES	191-65		
WILLIAMS FORK	WMFK	191-9		

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: COC-51440

22. Surface Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
SEC. 33, T6S-R91W-ALL

25. Distance to Nearest Mineral Lease Line: 664 ft 26. Total Acres in Lease: 640

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: EVAPORATION & BACKFIL

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	26	16	42	40		40	0
SURF	12+1/4	9+5/8	36	800	240	800	0
1ST	8+3/4	4+1/2	11.6	7,651	635	7,651	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments SEE SHEET 2R FOR IMPROVEMENTS WITHIN 400' OF THIS LOCATION. THIS WELL IS PART OF AN ENVIRONMENTAL ASSESSMENT THROUGH THE BLM GLENNWOOD SPRINGS ENERGY OFFICE.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: MATT BARBER

Title: PERMIT ANALYST Date: 11/3/2009 Email: MBARBER@BILLBARRETTCO

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 12/30/2009

API NUMBER

05 045 18990 00

Permit Number: _____ Expiration Date: 12/29/2011

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

24-HOUR SPUD NOTICE REQUIRED. E-MAIL david.Andrews@state.co.us GARFIELD COUNTY RULISON-FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE. NEW MAMM CREEK FIELD NOTICE TO OPERATORS APPLIES TO THIS WELL. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE. THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE-MINIMIS AMOUNTS. AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1. THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 000 FEET DEEP.

Attachment Check List

Att Doc Num	Name	Doc Description
1791176	APD ORIGINAL	LF@2170999 1791176
1791177	WELL LOCATION PLAT	LF@2171000 1791177
1791178	ACCESS ROAD MAP	LF@2171049 1791178
1791179	MINERAL LEASE MAP	LF@2171050 1791179
1791180	DEVIATED DRILLING PLAN	LF@2171001 1791180
1791181	FED. DRILLING PERMIT	LF@2171002 1791181
400013136	FORM 2 SUBMITTED	LF@2173308 400013136

Total Attach: 7 Files