

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

1904306

Plugging Bond Surety

20010102

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refiling ☒

Sidetrack ☐

3. Name of Operator: PETRO-CANADA RESOURCES (USA) INC

4. COGCC Operator Number: 72085

5. Address: 999 18TH ST STE 600

City: DENVER State: CO Zip: 80202-2499

6. Contact Name: SUSAN MILLER Phone: (303)297-2300 Fax: (303)297-80645

Email: SUSAN.MILLER@PETRO-CANADA.COM

7. Well Name: LINDBLAD Well Number: 20-25

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 7325

WELL LOCATION INFORMATION

10. QtrQtr: NENW Sec: 20 Twp: 6N Rng: 66W Meridian: 6

Latitude: 40.477130 Longitude: -104.806450

Footage at Surface: 1303 FNL/FSL FNL 1403 FEL/FWL FWL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4771 13. County: WELD

14. GPS Data:

Date of Measurement: 02/13/2008 PDOP Reading: 2.1 Instrument Operator's Name: M. ROBERT

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_ Bottom Hole: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_

Sec: \_\_\_\_\_ Twp: \_\_\_\_\_ Rng: \_\_\_\_\_ Sec: \_\_\_\_\_ Twp: \_\_\_\_\_ Rng: \_\_\_\_\_

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 401 ft

18. Distance to nearest property line: 700 ft 19. Distance to nearest well permitted/completed in the same formation: 869 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA-CODELL	NB-CD	381-5	160	NW

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
6-66: SECTION 20: NW/4

25. Distance to Nearest Mineral Lease Line: 1249 ft 26. Total Acres in Lease: 160

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	26	650	466	650	0
1ST	7+7/8	4+1/2	11.6	7,325	1,072	7,325	650

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments CONDUCTOR CASING WILL NOT BE UTILIZED. NO CHANGES TO LOCATION SINCE ORIGINAL SUBMITTAL.

34. Location ID: 310636

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: SUSAN MILLER

Title: REG ANALYST Date: 5/7/2009 Email: SUSAN.MILLER@PETRO-CA

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nashin Director of COGCC Date: 8/31/2009

#### API NUMBER

05 123 26734 00

Permit Number: 20092565 Expiration Date: 8/31/2011

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) PROVIDE 24 HOUR NOTICE OF MIRU TO ED BINKLEY AT 970-506-9834 OR E-MAIL AT ED.BINKLEY@STATE.CO.US 2) COMPLY WITH RULE 317.I AND PROVIDE CEMENT COVERAGE FROM TD TO A MINIMUM OF 200' ABOVE NIOBRARA. VERIFY ALL PLACED CEMENT COVERAGE WITH CEMENT BOND LOG.

1) PROVIDE 24 HOUR NOTICE OF MIRU TO ED BINKLEY AT 970-506-9834 OR E-MAIL AT ED.BINKLEY@STATE.CO.US 2) COMPLY WITH RULE 317.I AND PROVIDE CEMENT COVERAGE FROM TD TO A MINIMUM OF 200' ABOVE NIOBRARA. VERIFY ALL PLACED CEMENT COVERAGE WITH CEMENT BOND LOG.

### **Attachment Check List**

Att Doc Num	Name	Doc Description
1904307	SURFACE AGRMT/SURETY	LF@2052455 1904307
400003957	APD ORIG & 1 COPY	LF@2052454 400003957

Total Attach: 2 Files