

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400009020

Plugging Bond Surety

20040083

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☐ COALBED ☒ OTHER _____
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: PIONEER NATURAL RESOURCES USA INC

4. COGCC Operator Number: 10084

5. Address: 1401 17TH ST STE 1200

City: DENVER State: CO Zip: 80202

6. Contact Name: Georgina Kovacik Phone: (303)675-2611 Fax: (303)294-1251

Email: georgina.kovacik@pxd.com

7. Well Name: Grants Well Number: 14-34 Tr

8. Unit Name (if appl): Cottontail Pass Unit Number: COC59968A

9. Proposed Total Measured Depth: 1980

WELL LOCATION INFORMATION

10. QtrQtr: SWSW Sec: 34 Twp: 32S Rng: 66W Meridian: 6

Latitude: 37.209020 Longitude: -104.773050

Footage at Surface: 571 FNL/FSL FSL 636 FEL/FWL FWL

11. Field Name: Purgatoire River Field Number: 70830

12. Ground Elevation: 7485 13. County: LAS ANIMAS

14. GPS Data:

Date of Measurement: 08/12/2009 PDOP Reading: 3.7 Instrument Operator's Name: R. Coberly

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____

Sec: _____ Twp: _____ Rng: _____ Sec: _____ Twp: _____ Rng: _____

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☐ No

17. Distance to the nearest building, public road, above ground utility or railroad: 571 ft

18. Distance to nearest property line: 571 ft 19. Distance to nearest well permitted/completed in the same formation: 1312 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Raton	RTON	NA		NA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
See attached

25. Distance to Nearest Mineral Lease Line: 571 ft 26. Total Acres in Lease: 280

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Drilling pit

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	12+3/4	12+3/4	33.38 ppf	6			
SURF	11	8+5/8	24 ppf	650	136	650	0
S.C. 1.1	7+7/8	5+1/2	15.5 ppf	1,980	293	1,980	0

32. BOP Equipment Type: ☐ Annular Preventer ☐ Double Ram ☒ Rotating Head ☐ None

33. Comments _____

34. Location ID: 309259

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Georgina Kovacik

Title: Engineering Tech Date: 10/8/2009 Email: georgina.kovacik@pxd.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 12/23/2009

API NUMBER

05 071 09783 00

Permit Number: _____ Expiration Date: 12/22/2011

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) Provide 48 hour notice of MIRU to John Duran at 719-846-4715 or email John.Duran@state.co.us. 2) Provide cement coverage of production casing from TD to 50' above surface casing shoe. Verify coverage with cement bond log. 3) Immediately cease operations and notify the COGCC in the event of any operational problem that could potentially impact water wells in the area.

Attachment Check List

Att Doc Num	Name	Doc Description
2109247	SURFACE CASING CHECK	LF@2185863 2109247.00000
400009043	FORM 2 SUBMITTED	LF@2166291 400009043
400009044	LEGAL/LEASE DESCRIPTION	LF@2166292 400009044
400009045	WELL LOCATION PLAT	LF@2166293 400009045
400009046	TOPO MAP	LF@2166294 400009046
400009047	30 DAY NOTICE LETTER	LF@2166295 400009047
400009048	CONST. LAYOUT DRAWINGS	LF@2166296 400009048
400009049	CONSULT NOTICE	LF@2166297 400009049

Total Attach: 8 Files