

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refiling ☐  
Sidetrack ☐

Document Number:

400007238

Plugging Bond Surety

20030009

3. Name of Operator: NOBLE ENERGY INC

4. COGCC Operator Number: 100322

5. Address: 1625 BROADWAY STE 2200

City: DENVER State: CO Zip: 80202

6. Contact Name: MARI CLARK Phone: (303)228-4413 Fax: (303)2284286  
Email: mclark@nobleenergyinc.com

7. Well Name: SAUER G Well Number: 04-29D

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 7348

WELL LOCATION INFORMATION

10. QtrQtr: SESW Sec: 33 Twp: 5N Rng: 65W Meridian: 6

Latitude: 40.350690 Longitude: -104.670610

Footage at Surface: 805 FNL/FSL FSL 2020 FEL/FWL FWL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4662 13. County: WELD

14. GPS Data:

Date of Measurement: 06/19/2009 PDOP Reading: 2.0 Instrument Operator's Name: ROBERT DALEY

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FNL/FSL Bottom Hole: FNL/FSL FNL/FSL  
75 FNL 1404 FWL 75 FNL 1404 FWL  
Sec: 4 Twp: 4N Rng: 65W Sec: 4 Twp: 4N Rng: 65W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 705 ft

18. Distance to nearest property line: 625 19. Distance to nearest well permitted/completed in the same formation: 754 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL	407-87	160	GWA
NIOBRARA	NBRR	407-87	160	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
Please see attached oil and gas lease.

25. Distance to Nearest Mineral Lease Line: 75 ft 26. Total Acres in Lease: 76

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☒ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	550	232	550	0
1ST	7+7/8	4+1/2	11.6	7,348	673	7,348	

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☐ Rotating Head ☐ None

33. Comments NO CONDUCTOR CASING WILL BE USED. WELL WILL BE TWINNED WITH EXISTING SAUER 32-2 & PROPOSED SAUER G04-28D. FORM 4 AS DRILLED SUNDRY SUBMITTED. CMT TOP FOR 1ST STRING WILL BE 200' ABOVE NIOBRARA.

34. Location ID: 327497

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: MARI CLARK

Title: REG. ANALYST Date: 10/15/2009 Email: mclark@nobleenergyinc.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 11/24/2009

#### API NUMBER

05 123 30793 00

Permit Number: \_\_\_\_\_ Expiration Date: 11/23/2011

CONDITIONS OF APPROVAL, IF ANY: \_\_\_\_\_

**All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.**

1) Provide 24 hour notice of MIRU to Ed Binkley at 970-506-9834 or e-mail at ed.binkley@state.co.us 2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Sussex to 200' above Sussex. Verify coverage with cement bond log. 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

1) Provide 24 hour notice of MIRU to Ed Binkley at 970-506-9834 or e-mail at ed.binkley@state.co.us 2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Sussex to 200' above Sussex. Verify coverage with cement bond log. 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

### **Attachment Check List**

Att Doc Num	Name	Doc Description
2097947	SURFACE CASING CHECK	LF@2171806 2097947
400009217	WELL LOCATION PLAT	LF@2164909 400009217
400009218	SURFACE AGRMT/SURETY	LF@2164910 400009218
400009219	30 DAY NOTICE LETTER	LF@2164911 400009219
400009220	LOCATION DRAWING	LF@2164912 400009220
400009221	DEVIATED DRILLING PLAN	LF@2164917 400009221
400010025	PROPOSED SPACING UNIT	LF@2164918 400010025
400010028	OIL & GAS LEASE	LF@2164919 400010028
400010030	FORM 2 SUBMITTED	LF@2164920 400010030

Total Attach: 9 Files