

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

1712323

Plugging Bond Surety

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: WILLIAMS PRODUCTION RMT COMPANY

4. COGCC Operator Number: 96850

5. Address: 1515 ARAPAHOE ST STE 1000

City: DENVER State: CO Zip: 80202

6. Contact Name: JENNIFER HEAD Phone: (303)606-4342 Fax: (303)629-8268

Email: JENNIFER.HEAD@WILLIAMS.COM

7. Well Name: FEDERAL RGU Well Number: 413-24-198

8. Unit Name (if appl): RYAN GULCH UNIT Unit Number: COC068239
X

9. Proposed Total Measured Depth: 12592

WELL LOCATION INFORMATION

10. QtrQtr: NWSW Sec: 24 Twp: 1S Rng: 98W Meridian: 6

Latitude: 39.946513 Longitude: -108.347569

Footage at Surface: 1729 FNL/FSL FSL FEL/FWL 1072 FWL

11. Field Name: SULPHUR CREEK Field Number: 80090

12. Ground Elevation: 6536 13. County: RIO BLANCO

14. GPS Data:

Date of Measurement: 10/09/2008 PDOP Reading: 2.4 Instrument Operator's Name: MARK BESSIE

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1628 FSL 631 FWL FWL Bottom Hole: FNL/FSL 1628 FSL 631 FWL FWL
Sec: 24 Twp: 1S Rng: 98W Sec: 24 Twp: 1S Rng: 98W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 3800 ft

18. Distance to nearest property line: 2 mi 19. Distance to nearest well permitted/completed in the same formation: 659 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
ILES	ILES			
SEGO	SEGO			
WILLIAMS FORK	WMFK			

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: COC060733

22. Surface Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
T1S, R98W: SECTION 24, LOTS 1-16; SECTION 25, LOTS 1-16

25. Distance to Nearest Mineral Lease Line: 631 ft 26. Total Acres in Lease: 1239

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: EVAPORATION & BACKFILL

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	26	18	48	80	135	80	0
SURF	14+3/4	9+5/8	36	3,844	1,545	3,844	0
1ST	8+3/4	4+1/2	11.6	12,592		12,592	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: JENNIFER HEAD

Title: REGULATORY Date: 8/13/2009 Email: JENNIFER.HEAD@WILLIAMS.

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 11/5/2009

API NUMBER

05 103 11616 00

Permit Number: _____ Expiration Date: 11/4/2011

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

24-HOUR SPUD NOTICE REQUIRED. E-MAIL david.Andrews@state.co.us RESERVE PIT MUST BE LINED CEMENT TOP VERIFICATION BY CBL REQUIRED. OPERATOR MUST ENSURE 110 PERCENT SECONDARY CONTAINMENT FOR ANY VOLUME OF FLUIDS CONTAINED AT WELL-SITE DURING DRILLING AND COMPLETION OPERATIONS. IF FLUIDS ARE CONVEYED VIA PIPELINE, OPERATOR MUST IMPLEMENT BEST MANAGEMENT PRACTICES TO CONTAIN ANY UNINTENTIONAL RELEASE OF FLUIDS. THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE-MINIMIS AMOUNTS. AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1. THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 3000 FEET DEEP.

Attachment Check List

Att Doc Num	Name	Doc Description
1289030	ACCESS ROAD MAP	LF@2123751 1289030
1289031	HYDROLOGY MAP	LF@2123753 1289031
1289032	TOPO MAP	LF@2123755 1289032
1712324	WELL LOCATION PLAT	LF@2123671 1712324
1712325	ACCESS ROAD MAP	LF@2123757 1712325
1712326	DEVIATED DRILLING PLAN	LF@2123672 1712326
1712327	FED. DRILLING PERMIT	LF@2123673 1712327
1712328	DRILLING PLAN	LF@2123674 1712328
1712329	SURFACE AGRMT/SURETY	LF@2123675 1712329
1712330	LOCATION PICTURES	LF@2123749 1712330
400015955	APD ORIGINAL	LF@2123670 400015955

Total Attach: 11 Files