

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refiling ☐
Sidetrack ☐

Document Number:

400009717

Plugging Bond Surety

20030009

3. Name of Operator: NOBLE ENERGY INC

4. COGCC Operator Number: 100322

5. Address: 1625 BROADWAY STE 2200

City: DENVER State: CO Zip: 80202

6. Contact Name: KATE SHIRLEY Phone: (303)228-4449 Fax: (303)228-4280

Email: kshirley@nobleenergyinc.com

7. Well Name: STROH H Well Number: 12-32

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7750

WELL LOCATION INFORMATION

10. QtrQtr: SWNW Sec: 12 Twp: 3N Rng: 65W Meridian: 6

Latitude: 40.240430 Longitude: -104.619840

Footage at Surface: 2438 FNL/FSL FNL 235 FEL/FWL FWL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4837 13. County: WELD

14. GPS Data:

Date of Measurement: 05/06/2009 PDOP Reading: 1.9 Instrument Operator's Name: DAVID C. HOLMES

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____

Sec: _____ Twp: _____ Rng: _____ Sec: _____ Twp: _____ Rng: _____

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 200 ft

18. Distance to nearest property line: 235 ft 19. Distance to nearest well permitted/completed in the same formation: 830 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL	407-87	160	GWA
J-SAND	JSND	232-23	160	GWA
NIOBRARA	NBRR	407-87	160	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
T3N-65W-SEC. 12: N/2

25. Distance to Nearest Mineral Lease Line: 235 ft 26. Total Acres in Lease: 320

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☒ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	650	230	650	0
1ST	7+7/8	4+1/2	11.6	7,750	481	7,750	

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☐ Rotating Head ☐ None

33. Comments NO CONDUCTOR CASING WILL BE USED. THE PRODUCTION CASING TOP OF CEMENT WILL BE 200' ABOVE NIOBRARA. THE UNIT CONFIGURATION FOR THE CODELL, NIOBRARA AND J-SAND IS T3N, R65W, SEC. 11: SENE, NESE, SEC. 12: SWNW, NWSW

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: KATE SHIRLEY

Title: REGULATORY SPECIALIST Date: 10/13/2009 Email: kshirley@nobleenergyinc.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 12/15/2009

API NUMBER

05 123 30885 00

Permit Number: _____ Expiration Date: 12/14/2011

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) Provide 24 hour notice of MIRU to Ed Binkley at 970-506-9834 or e-mail at ed.binkley@state.co.us 2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Sussex to 200' above Sussex. Verify coverage with cement bond log.

Attachment Check List

Att Doc Num	Name	Doc Description
2109250	SURFACE CASING CHECK	LF@2185856 2109250.00000
400009722	WELL LOCATION PLAT	LF@2165401 400009722
400009723	LOCATION DRAWING	LF@2165402 400009723
400009724	30 DAY NOTICE LETTER	LF@2165403 400009724
400009725	EXCEPTION LOC WAIVERS	LF@2165404 400009725
400009726	PROPOSED SPACING UNIT	LF@2165405 400009726
400009750	FORM 2 SUBMITTED	LF@2165406 400009750

Total Attach: 7 Files