

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400041924

Plugging Bond Surety

20090025

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refiling ☒

Sidetrack ☐

3. Name of Operator: AUGUSTUS ENERGY PARTNERS LLC

4. COGCC Operator Number: 10275

5. Address: P O BOX 250

City: WRAY State: CO Zip: 80758

6. Contact Name: Loni Davis Phone: (970)332-3585 Fax: (970)332-3587

Email: ldavis@augustusenergy.com

7. Well Name: Lippert Trust Well Number: 13-01 1S45W

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 2499

WELL LOCATION INFORMATION

10. QtrQtr: NWSW Sec: 1 Twp: 1S Rng: 45W Meridian: 6

Latitude: 39.996090 Longitude: -102.373310

Footage at Surface: 2151 FNL/FSL 320 FEL/FWL FWL

11. Field Name: Duke Field Number: 18890

12. Ground Elevation: 3934 13. County: YUMA

14. GPS Data:

Date of Measurement: 02/13/2010 PDOP Reading: 2.2 Instrument Operator's Name: Neal McCormick

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_ Bottom Hole: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_

Sec: \_\_\_\_\_ Twp: \_\_\_\_\_ Rng: \_\_\_\_\_ Sec: \_\_\_\_\_ Twp: \_\_\_\_\_ Rng: \_\_\_\_\_

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☐ No

17. Distance to the nearest building, public road, above ground utility or railroad: 320 ft

18. Distance to nearest property line: 320 ft 19. Distance to nearest well permitted/completed in the same formation: 904 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR			

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
1S45W: Sec 1: SW/4

25. Distance to Nearest Mineral Lease Line: 320 ft 26. Total Acres in Lease: 160

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	9+1/2	7	17	460	200	460	
1ST	6+1/4	4+1/2	10.5	2,600	75	2,600	1,800

32. BOP Equipment Type: ☐ Annular Preventer ☐ Double Ram ☐ Rotating Head ☒ None

33. Comments No Conductor Casing will be used. This is an expired permit with an existing API #05-125-11268-00, the system would not let me put it in the API Field. Per our Geologist the producing formation depth will be less than 2500'

34. Location ID: 338376

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Loni J. Davis

Title: Oper. Acctg. & Reg. Spec. Date: 2/19/2010 Email: ldavis@augustusenergy.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 3/26/2010

#### API NUMBER

05 125 11268 00

Permit Number: \_\_\_\_\_ Expiration Date: 3/24/2012

CONDITIONS OF APPROVAL, IF ANY: \_\_\_\_\_

**All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.**

1) Provide 24 hr notice of spud to Craig Quint at 719-767-8939 or e-mail at craig.quint@state.co.us. 2) Set surface casing at least 50' into Pierre Shale for aquifer coverage, (460' minimum - as proposed). Setting surface casing less than the approved depth is a permit violation unless prior written approval is obtained from the COGCC. 3) If completed, provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log. 4) If dry hole, set 35 sks cement 50' above Niobrara top, 35 sks cement ½ out, ½ in surface casing, 10 sks cement at top of surface casing, cut casing 4' below GL, weld on plate, 5 sks cement in rat hole & 5 sks cement in mouse hole. 5) The completed interval must be above a depth of 2500 feet (well is outside Rule 318B spacing area).

### **Attachment Check List**

Att Doc Num	Name	Doc Description
2099340	SURFACE CASING CHECK	LF@2434362 2099340
400041926	PLAT	LF@2427040 400041926
400041927	30 DAY NOTICE LETTER	LF@2427041 400041927
400041928	SURFACE AGRMT/SURETY	LF@2427042 400041928
400041930	TOPO MAP	LF@2427043 400041930
400041969	FORM 2 SUBMITTED	LF@2427044 400041969

Total Attach: 6 Files