

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refiling ☐
Sidetrack ☐

Document Number:

400002162

Plugging Bond Surety

20010124

3. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP 4. COGCC Operator Number: 47120

5. Address: P O BOX 173779

City: DENVER State: CO Zip: 80217-3779

6. Contact Name: Cheryl Light Phone: (720)929-6461 Fax: (720)929-7461
Email: Cheryl.Light@anadarko.com

7. Well Name: P VILLE FEDERAL Well Number: 22-7

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 8012

WELL LOCATION INFORMATION

10. QtrQtr: SENW Sec: 7 Twp: 3N Rng: 66W Meridian: 6

Latitude: 40.242100 Longitude: -104.825020

Footage at Surface: 1539 FNL/FSL FNL 1352 FEL/FWL FWL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4790 13. County: WELD

14. GPS Data:

Date of Measurement: 02/26/2009 PDOP Reading: 6.0 Instrument Operator's Name: Travis Kraich

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 2600 FNL 1350 FWL FWL Bottom Hole: FNL/FSL 2600 FNL 1350 FWL FWL
Sec: 7 Twp: 3N Rng: 66W Sec: 7 Twp: 3N Rng: 66W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 1349 ft

18. Distance to nearest property line: 1129 ft 19. Distance to nearest well permitted/completed in the same formation: 937 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
J-Sand	JSND		160	GWA
Niobrara/Codell	NB-CD	407-87	160	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20010125

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
NW/4- SECTION 7- TOWNSHIP 3 NORTH- RANGE 66 WEST

25. Distance to Nearest Mineral Lease Line: 67 ft 26. Total Acres in Lease: 164

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	900	630	900	
1ST	7+7/8	4+1/2	11.6	8,012	200	8,012	

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☒ Rotating Head ☐ None

33. Comments No conductor casing will be used

34. Location ID: 318772

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Cheryl Light

Title: Senior Regulatory Analyst Date: 8/18/2009 Email: cheryl.light@anadarko.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 11/18/2009

API NUMBER

05 123 30771 00

Permit Number: _____ Expiration Date: 11/17/2011

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us 2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log. 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name	Doc Description
400002166	OIL & GAS LEASE	lease nw7.pdf
400002167	MULTI-WELL PLAN	P VILLE FEDERAL 4 PAD 3N66W7.pdf
400002168	DRILLING PLAN	P Ville Federal 22-7 Directional 04-02-09.pdf
400002169	WELL LOCATION PLAT	P VILLE FEDERAL 22-7 PLAT.pdf
400002170	TOPO MAP	P VILLE FEDERAL 22-7 TOPO.pdf
400002171	30 DAY NOTICE LETTER	P VILLE FEDERAL NOTICE LETTER.pdf
400002769	PROPOSED SPACING UNIT	P VILLE FEDERAL 22-7 SPACING MAP.pdf

Total Attach: 7 Files