

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



|    |    |    |    |
|----|----|----|----|
| DE | ET | OE | ES |
|----|----|----|----|

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refiling ☐  
Sidetrack ☐

Document Number:

400003132

Plugging Bond Surety

20010124

3. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP

4. COGCC Operator Number: 47120

5. Address: P O BOX 173779

City: DENVER State: CO Zip: 80217-3779

6. Contact Name: Cheryl Light Phone: (720)929-6461 Fax: (720)929-7461

Email: cheryl.light@anadarko.com

7. Well Name: BELLA FEDERAL Well Number: 36-7

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 8210

WELL LOCATION INFORMATION

10. QtrQtr: SESE Sec: 7 Twp: 3N Rng: 66W Meridian: 6

Latitude: 40.234400 Longitude: -104.814900

Footage at Surface: 895 FNL/FSL FSL 1161 FEL/FWL FEL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4840 13. County: WELD

14. GPS Data:

Date of Measurement: 07/22/2009 PDOP Reading: 6.0 Instrument Operator's Name: Daniel J. Corriell

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 100 FSL 2540 FEL FEL Bottom Hole: FNL/FSL 100 FSL 2540 FEL FEL  
Sec: 7 Twp: 3N Rng: 66W Sec: 7 Twp: 3N Rng: 66W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 264 ft

18. Distance to nearest property line: 895 ft 19. Distance to nearest well permitted/completed in the same formation: 843 ft

20. LEASE, SPACING AND POOLING INFORMATION

| Objective Formation(s) | Formation Code | Spacing Order Number(s) | Unit Acreage Assigned to Well | Unit Configuration (N/2, SE/4, etc.) |
|------------------------|----------------|-------------------------|-------------------------------|--------------------------------------|
| J- Sand                | JSND           |                         | 160                           | GWA                                  |
| Niobrara/Codell        | NB-CD          | 407-87                  | 160                           | GWA                                  |

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
See attached copy of Oil and Gas Lease

25. Distance to Nearest Mineral Lease Line: 100 ft 26. Total Acres in Lease: 5794

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

| Casing Type | Size of Hole | Size of Casing | Weight Per Foot | Setting Depth | Sacks Cement | Cement Bottom | Cement Top |
|-------------|--------------|----------------|-----------------|---------------|--------------|---------------|------------|
| SURF        | 12+1/4       | 8+5/8          | 24              | 650           | 455          | 650           |            |
| 1ST         | 7+7/8        | 4+1/2          | 11.6            | 8,210         | 200          | 8,210         |            |

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☒ Rotating Head ☐ None

33. Comments No conductor casing will be used

34. Location ID: 336647

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Cheryl Light

Title: Senior Regulatory Analyst Date: 8/31/2009 Email: cheyrl.light@anadarko.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nashin Director of COGCC Date: 11/20/2009

**API NUMBER**

05 123 30776 00

Permit Number: \_\_\_\_\_ Expiration Date: 11/19/2011

**CONDITIONS OF APPROVAL, IF ANY:**

**All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.**

1) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us 2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log. 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

### **Attachment Check List**

| Att Doc Num | Name                  | Doc Description                          |
|-------------|-----------------------|--|
| 400003133   | MULTI-WELL PLAN       | BELLA FEDERAL 5-PAD 3N66W7.pdf           |
| 400003134   | DRILLING PLAN         | BELLA FEDERAL 36-7 DIRECTIONAL.pdf       |
| 400003135   | OIL & GAS LEASE       | BELLA FEDERAL 36-7 LEASE.pdf             |
| 400003136   | WELL LOCATION PLAT    | BELLA FEDERAL 36-7 PLAT.pdf              |
| 400003138   | TOPO MAP              | BELLA FEDERAL 36-7 TOPO 33N66W7.pdf      |
| 400003139   | 30 DAY NOTICE LETTER  | BELLA NOTICE LETTER.pdf                  |
| 400003140   | SURFACE AGRMT/SURETY  | SURFACE USE AGREEMENT.pdf                |
| 400003192   | EXCEPTION LOC WAIVERS | BELLA 36-7 EXCEPTION LOCATION WAIVER.pdf |
| 400003215   | PROPOSED SPACING UNIT | BELLA FEDERAL 36-7 SPACING MAP.pdf       |

Total Attach: 9 Files