

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

1692412

Plugging Bond Surety

20050043

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☒

Refiling ☒

Sidetrack ☐

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: NICK G. CURRAN Phone: (720)876-5288 Fax: (720)876-6288
Email: NICK.CURRAN@ENCANA.COM

7. Well Name: HURT Well Number: 7-8-11

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 8188

WELL LOCATION INFORMATION

10. QtrQtr: SWSE Sec: 11 Twp: 2N Rng: 68W Meridian: 6

Latitude: 40.147430 Longitude: -104.968740

Footage at Surface: 515 FNL/FSL FSL 2152 FEL/FWL FEL

11. Field Name: WATTENBERG Field Number: _____

12. Ground Elevation: 4868 13. County: WELD

14. GPS Data:

Date of Measurement: 07/31/2008 PDOP Reading: 1.7 Instrument Operator's Name: BEN ADSIT

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 50 FSL 660 FEL FEL Bottom Hole: FNL/FSL 50 FSL 660 FEL FEL
Sec: 11 Twp: 2N Rng: 68W Sec: 11 Twp: 2N Rng: 68W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 492 ft

18. Distance to nearest property line: 475 ft 19. Distance to nearest well permitted/completed in the same formation: 1111 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL	407-87	160	GWA
J SAND	JSND		160	GWA
NIOBRARA	NBRR	407-87	160	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
T2N-R68W SEC. 11: A 0.803 ACRE TRACT IN THE SESE

25. Distance to Nearest Mineral Lease Line: 50 ft 26. Total Acres in Lease: 0

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	650	280	650	0
1ST	7+7/8	4+1/2	11.6	8,188	280	8,188	7,133
			Stage Tool	5,123	240	5,123	4,122

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments NO CONDUCTOR CASING WILL BE USED. NO NEW VISIBLE IMPROVEMENTS WITHIN 400' SINCE ORIGINALLY PERMITTED.

34. Location ID: 336375

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: NICK G. CURRAN

Title: PERMITTING AGENT Date: 10/20/2009 Email: NICK.CURRAN@ENCANA.CO

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 11/20/2009

API NUMBER

05 123 29280 00

Permit Number: _____ Expiration Date: 11/19/2011

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us 2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Shannon to 200' above Sussex. Verify coverage with cement bond log. 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name	Doc Description
1692433	WELL LOCATION PLAT	LF@2161479 1692433
1692434	TOPO MAP	LF@2161453 1692434
1692435	MINERAL LEASE MAP	LF@2161452 1692435
1692436	SURFACE AGRMT/SURETY	LF@2161480 1692436
1692437	30 DAY NOTICE LETTER	LF@2161481 1692437
1692438	PROPOSED SPACING UNIT	LF@2161483 1692438
1940935	DEVIATED DRILLING PLAN	LF@2161482 1940935
400010778	FORM 2 SUBMITTED	LF@2166767 400010778
400018569	APD ORIGINAL	LF@2161478 400018569

Total Attach: 9 Files