

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

1784376

Plugging Bond Surety

20030009

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: NOBLE ENERGY INC

4. COGCC Operator Number: 100322

5. Address: 1625 BROADWAY STE 2200

City: DENVER State: CO Zip: 80202

6. Contact Name: LINDA PAVELKA Phone: (303)228-4064 Fax: (303)228-4286

Email: LPAVELKA@NOBLEENERGYINC.COM

7. Well Name: WAKEFIELD TRUST Well Number: 42-12

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 2450

WELL LOCATION INFORMATION

10. QtrQtr: SENE Sec: 12 Twp: 2S Rng: 45W Meridian: 6

Latitude: 39.899650 Longitude: -102.355040

Footage at Surface: 1810 FNL/FSL 212 FEL/FWL FEL

11. Field Name: VERNON Field Number: 86500

12. Ground Elevation: 3899 13. County: YUMA

14. GPS Data:

Date of Measurement: 08/11/2009 PDOP Reading: 1.7 Instrument Operator's Name: STEVEN A. LUND

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_ Bottom Hole: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_

Sec: \_\_\_\_\_ Twp: \_\_\_\_\_ Rng: \_\_\_\_\_ Sec: \_\_\_\_\_ Twp: \_\_\_\_\_ Rng: \_\_\_\_\_

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 155 ft

18. Distance to nearest property line: 212 ft 19. Distance to nearest well permitted/completed in the same formation: 1847 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR			

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
PLEASE SEE ATTACHED COPY OF THE OIL GAS LEASE

25. Distance to Nearest Mineral Lease Line: 830 ft 26. Total Acres in Lease: 1243

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	9+7/8	7	17	350	125	350	0
1ST	6+1/4	4+1/2	10.5	2,450	125	2,450	0

32. BOP Equipment Type: ☐ Annular Preventer ☐ Double Ram ☐ Rotating Head ☒ None

33. Comments NO CONDUCTOR CASING WILL BE USED. RIG DERRICK HEIGHT IS 75'.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: LINDA PAVELKA

Title: REGULATORY Date: 9/9/2009 Email: LPVELKA@NOBLEENERGYI

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 10/23/2009

#### API NUMBER

05 125 11721 00

Permit Number: \_\_\_\_\_ Expiration Date: 10/22/2011

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

PRODUCING INTERVAL MUST BE ABOVE 2500 FEET

1) Provide 24 hr notice of spud to Colby Horton at 970-867-2517 or e-mail at colby.horton@state.co.us. 2) Set surface casing at least 50' into Pierre Shale for aquifer coverage, (350' minimum - as proposed). Setting surface casing less than the approved depth is a permit violation unless prior written approval is obtained from the COGCC. 3) If completed, provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log. 4) If dry hole, set 35 sks cement 50' above Niobrara top, 35 sks cement ½ out, ½ in surface casing, 10 sks cement at top of surface casing, cut casing 4' below GL, weld on plate, 5 sks cement in rat hole 5 sks cement in mouse hole.

### **Attachment Check List**

Att Doc Num	Name	Doc Description
1784377	WELL LOCATION PLAT	LF@2139008 1784377
1784378	TOPO MAP	LF@2139009 1784378
1784379	OIL & GAS LEASE	LF@2139010 1784379
1784380	SURFACE AGRMT/SURETY	LF@2139011 1784380
1784381	30 DAY NOTICE LETTER	LF@2139012 1784381
2097553	SURFACE CASING CHECK	LF@2157157 2097553
400012813	APD ORIGINAL	LF@2139007 400012813

Total Attach: 7 Files