

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

1904922

Plugging Bond Surety

20010102

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refiling ☒

Sidetrack ☐

3. Name of Operator: PETRO-CANADA RESOURCES (USA) INC

4. COGCC Operator Number: 72085

5. Address: 999 18TH ST STE 600

City: DENVER State: CO Zip: 80202-2499

6. Contact Name: SUSAN MILLER Phone: (303)297-2100 Fax: (303)297-7708

Email: SUSAN.MILLER@PETRO-CANADA.COM

7. Well Name: HKS Well Number: 6-22(DIR)

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7733

WELL LOCATION INFORMATION

10. QtrQtr: SWNW Sec: 6 Twp: 6N Rng: 66W Meridian: 6

Latitude: 40.519330 Longitude: -104.827750

Footage at Surface: 1522 FNL/FSL FNL 1249 FEL/FWL FWL

11. Field Name: Eaton Field Number: 19350

12. Ground Elevation: 4890 13. County: WELD

14. GPS Data:

Date of Measurement: 04/02/2008 PDOP Reading: 1.6 Instrument Operator's Name: BEN ADSIT

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 663 FNL 702 FWL FWL Bottom Hole: FNL/FSL 663 FNL 702 FWL FWL
Sec: 6 Twp: 6N Rng: 66W Sec: 6 Twp: 6N Rng: 66W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 339 ft

18. Distance to nearest property line: 155 ft 19. Distance to nearest well permitted/completed in the same formation: 1030 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA-CODELL	NB-CD	407-87	80	W2NW

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
6-66 SEC. 6: NW/4

25. Distance to Nearest Mineral Lease Line: 1121 ft 26. Total Acres in Lease: 160

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	26	875	628	875	0
1ST	7+7/8	4+1/2	11.6	7,733	1,100	7,733	875

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments CONDUCTOR CASING WILL NOT BE UTILIZED. NO CHANGES TO LOCATION SINCE ORIGINAL SUBMITTAL.

34. Location ID: 333294

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: Y Print Name: SUSAN MILLER

Title: REGULATORY ANALYST Date: 6/15/2009 Email: SUSAN.MILLER@PETRO-CA

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nashin Director of COGCC Date: 9/30/2009

API NUMBER

05 123 27124 00

Permit Number: 20092706 Expiration Date: 9/29/2011

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) Provide 24 hour notice of MIRU to Ed Binkley at 970-506-9834 or e-mail at ed.binkley@state.co.us 2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log. 3) Run and submit Directional Survey from TD to base of surface casing. The operator shall comply with Rule 321, and it shall be the operator's responsibility to ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name	Doc Description
1904923	WELL LOCATION PLAT	LF@2085782 1904923
1904924	SURFACE AGRMT/SURETY	LF@2085783 1904924
400007611	APD ORIG & 1 COPY	LF@2085781 400007611

Total Attach: 3 Files