

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

1759224

Plugging Bond Surety

20050043

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: NICK G. CURRAN Phone: (720)876-5288 Fax: (720)876-6288  
Email: NICK.CURRAN@ENCANA.COM

7. Well Name: RAY NELSON Well Number: 0-4-32

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 8224

WELL LOCATION INFORMATION

10. QtrQtr: SWNW Sec: 32 Twp: 2N Rng: 68W Meridian: 6

Latitude: 40.097180 Longitude: -105.034420

Footage at Surface: 1893 FNL/FSL FNL 690 FEL/FWL FWL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4948 13. County: WELD

14. GPS Data:

Date of Measurement: 07/27/2009 PDOP Reading: 1.2 Instrument Operator's Name: CRAIG BURKE

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 2500 FNL 50 FWL FWL Bottom Hole: FNL/FSL 2500 FNL 50 FWL FWL  
Sec: 32 Twp: 2N Rng: 68W Sec: 32 Twp: 2N Rng: 68W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 364 ft

18. Distance to nearest property line: 348 ft 19. Distance to nearest well permitted/completed in the same formation: 860 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL	407-87	160	GWA
J SAND	JSND	232-23	160	GWA
NIOBRARA	NBRR	407-87	160	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
T2N-R68W SEC. 32; PART OF S2NW LYING S & E OF RAILROAD R.O.W., SW, PART OF N2SE

25. Distance to Nearest Mineral Lease Line: 50 ft 26. Total Acres in Lease: 245

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	700	130	700	0
1ST	7+7/8	4+1/2	11.6	8,224	280	8,224	7,147
			Stage Tool	5,131	240	5,131	4,146

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments NO CONDUCTOR CASING WILL BE USED.

34. Location ID: 336463

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: NICK G. CURRAN

Title: PERMITTING AGENT Date: 9/15/2009 Email: NICK.CURRAN@ENCANA.CO

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 12/9/2009

#### API NUMBER

05 123 30852 00

Permit Number: \_\_\_\_\_ Expiration Date: 12/8/2011

CONDITIONS OF APPROVAL, IF ANY: \_\_\_\_\_

**All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.**

1) Note surface casing setting depth change from 300' to 700'. Increase cement coverage accordingly and cement to surface. 2) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us 3) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Shannon to 200' above Sussex. Verify coverage with cement bond log. 4) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

### **Attachment Check List**

Att Doc Num	Name	Doc Description
1759225	WELL LOCATION PLAT	LF@2143699 1759225
1759226	TOPO MAP	LF@2143700 1759226
1759227	MINERAL LEASE MAP	LF@2143667 1759227
1759228	SURFACE AGRMT/SURETY	LF@2143701 1759228
1759229	30 DAY NOTICE LETTER	LF@2143702 1759229
1759230	DEVIATED DRILLING PLAN	LF@2143703 1759230
1759231	PROPOSED SPACING UNIT	LF@2143704 1759231
1759686	30 DAY NOTICE LETTER	LF@2177441 1759686
1760167	SURFACE AGRMT/SURETY	LF@2194088 1760167
1769208	SURFACE CASING CHECK	LF@2170107 1769208
400023599	APD ORIGINAL	LF@2143698 400023599

Total Attach: 11 Files