

FORM
2
Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE ZONE COMMINGLE ZONE

Refiling
Sidetrack

Document Number:
400028665
Plugging Bond Surety
20060021

3. Name of Operator: ROSETTA RESOURCES OPERATING LP 4. COGCC Operator Number: 10159

5. Address: 717 TEXAS STE 2800
City: HOUSTON State: TX Zip: 77002

6. Contact Name: SHAWN HILDRETH Phone: (713)335-4104 Fax: (281)763-2320
Email: SHAWN.HILDRETH@ROSETTARESOURCE.COM

7. Well Name: COX Well Number: 34-06

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 2499

WELL LOCATION INFORMATION

10. QtrQtr: SENW Sec: 34 Twp: 1S Rng: 44W Meridian: 6
Latitude: 39.927690 Longitude: -102.290521

Footage at Surface: _____ FNL/FSL _____ FEL/FWL _____
2321 FNL 2066 FWL

11. Field Name: VERNON Field Number: 86500

12. Ground Elevation: 3848 13. County: YUMA

14. GPS Data:

Date of Measurement: 12/12/2009 PDOP Reading: 1.5 Instrument Operator's Name: CHRIS PEARSON

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: _____ FNL/FSL _____ FEL/FWL _____ Bottom Hole: _____ FNL/FSL _____ FEL/FWL _____
Sec: _____ Twp: _____ Rng: _____ Sec: _____ Twp: _____ Rng: _____

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 2025 ft

18. Distance to nearest property line: 525 ft 19. Distance to nearest well permitted/completed in the same formation: 655 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	315-3	160	NW/4

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No Surface Owners Agreement Attached or \$25,000 Blanket Surface Bon \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
T1S R44W S34:W/2

25. Distance to Nearest Mineral Lease Line: 525 ft 26. Total Acres in Lease: 320

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? Yes No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal: Offsite Onsite

Method: Land Farming Land Spreading Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	9+7/8	7	17	400	180	400	0
1ST	6+1/8	4+1/2	10.5	2,499	90	2,499	2,099

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments NO CONDUCTOR CASING WILL BE USED.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: SHAWN HILDRETH

Title: REGULATORY ANALYST Date: 1/15/2010 Email: SHAWN.HILDRETH@ROSETT

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nashin Director of COGCC Date: 3/2/2010

API NUMBER
05 125 11762 00

Permit Number: _____ Expiration Date: 2/29/2012

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) Provide 24 hr notice of spud to Mike Leonard at 719-767-2805 or e-mail mike.leonard@state.co.us. 2) Set surface casing at least 50' into Pierre Shale for aquifer coverage, (350' minimum - as proposed). Setting surface casing less than the approved depth is a permit violation unless prior written approval is obtained from the COGCC. 3) If completed, provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log. 4) If dry hole, set 35 sks cement 50' above Niobrara top, 35 sks cement ½ out, ½ in surface casing, 10 sks cement at top of surface casing, cut casing 4' below GL, weld on plate, 5 sks cement in rat hole & 5 sks cement in mouse hole.

The producing interval must be above 2500 feet in depth.

Attachment Check List

Att Doc Num	Name	Doc Description
1828776	TOPO MAP	LF@2419999 1828776
1828777	WELL LOCATION PLAT	LF@2419998 1828777
400028674	PLAT	LF@2218860 400028674
400028675	TOPO MAP	LF@2218861 400028675
400028683	30 DAY NOTICE LETTER	LF@2218862 400028683
400029102	FORM 2 SUBMITTED	LF@2218863 400029102

Total Attach: 6 Files