

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refiling ☐
Sidetrack ☐

Document Number:

400036071

Plugging Bond Surety

20010124

3. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP

4. COGCC Operator Number: 47120

5. Address: P O BOX 173779

City: DENVER State: CO Zip: 80217-3779

6. Contact Name: Cheryl Light Phone: (720)929-6461 Fax: (720)929-7461

Email: Cheryl.Light@anadarko.com

7. Well Name: KERR-MCGEE Well Number: 23-3

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 8619

WELL LOCATION INFORMATION

10. QtrQtr: NWSW Sec: 3 Twp: 1N Rng: 68W Meridian: 6

Latitude: 40.077623 Longitude: -104.994857

Footage at Surface: 1674 FNL/FSL FSL 1142 FEL/FWL FWL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 5042 13. County: WELD

14. GPS Data:

Date of Measurement: 12/10/2009 PDOP Reading: 1.8 Instrument Operator's Name: Jerry F. Harcek

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1350 FSL 2590 FEL FEL Bottom Hole: FNL/FSL 1350 FSL 2590 FEL FEL
Sec: 3 Twp: 1N Rng: 68W Sec: 3 Twp: 1N Rng: 68W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 1085 ft

18. Distance to nearest property line: 173 ft 19. Distance to nearest well permitted/completed in the same formation: 1298 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara/Codell	NB-CD	407	160	E/2SW4 & W/2SE4

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
See attached lease

25. Distance to Nearest Mineral Lease Line: 1312 ft 26. Total Acres in Lease: 5752

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	950	665	950	0
1ST	7+7/8	4+1/2	11.6	8,619	200	8,619	

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☒ Rotating Head ☐ None

33. Comments No conductor casing will be used. Location is outside the drilling window; exception granted

34. Location ID: 302913

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Cheryl Light

Title: Senior Regulatory Analyst Date: 2/11/2010 Email: DJRegulatory@anadarko.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nashin Director of COGCC Date: 3/26/2010

API NUMBER

05 123 31367 00

Permit Number: _____ Expiration Date: 3/24/2012

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us 2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Shannon to 200' above Sussex. Verify coverage with cement bond log. 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Location is outside the drilling window; exception granted

Attachment Check List

Att Doc Num	Name	Doc Description
2099413	SURFACE CASING CHECK	LF@2437893 2099413
400036116	30 DAY NOTICE LETTER	LF@2426311 400036116
400036119	MULTI-WELL PLAN	LF@2426312 400036119
400036121	DEVIATED DRILLING PLAN	LF@2426313 400036121
400036126	WELL LOCATION PLAT	LF@2426314 400036126
400036127	PROPOSED SPACING UNIT	LF@2426315 400036127
400036131	TOPO MAP	LF@2426316 400036131
400036132	EXCEPTION LOC WAIVERS	LF@2426317 400036132
400036133	OIL & GAS LEASE	LF@2426318 400036133
400036134	SURFACE AGRMT/SURETY	LF@2426319 400036134
400039446	FORM 2 SUBMITTED	LF@2426320 400039446

Total Attach: 11 Files