

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400046627

Plugging Bond Surety

20090069

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refiling ☒

Sidetrack ☐

3. Name of Operator: DELTA PETROLEUM CORPORATION

4. COGCC Operator Number: 16800

5. Address: 370 17TH ST STE 4300

City: DENVER State: CO Zip: 80202

6. Contact Name: Kallasandra Moran Phone: (303)575-0323 Fax: (303)575-0324

Email: kmoran@deltapetro.com

7. Well Name: Vega Well Number: 4-414

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 9026

WELL LOCATION INFORMATION

10. QtrQtr: SENE Sec: 4 Twp: 10S Rng: 93W Meridian: 6

Latitude: 39.222155 Longitude: -107.765689

Footage at Surface: 1582 FNL/FSL FNL 290 FEL/FWL FEL

11. Field Name: Vega Field Number: 85930

12. Ground Elevation: 8124 13. County: MESA

14. GPS Data:

Date of Measurement: 07/02/2008 PDOP Reading: 6.0 Instrument Operator's Name: J. Kirkpatrick, Bookcliff Surveying

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 720 FNL 1060 FEL 720 FEL 1060 FEL
Sec: 4 Twp: 10S Rng: 93W Sec: 4 Twp: 10S Rng: 93W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 1059 ft

18. Distance to nearest property line: 291 ft 19. Distance to nearest well permitted/completed in the same formation: 311 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Mesa Verde	MVRD	399-4	640	All

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
T10S R 93W: Sec. 4: E/2NE, NE/SW, N/2SE

25. Distance to Nearest Mineral Lease Line: 288 ft 26. Total Acres in Lease: 200

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Closed loop

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	24	16	55	60	200	60	0
SURF	12+1/4	8+5/8	24, 32	2,200	740	2,200	0
1ST	7+7/8	4+1/2	11.6	9,026	477	9,026	5,576

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Delta Petroleum is the surface owner, therefore Rule 306 is not applicable. There will not be a 30 day letter or SUA attached.

Casing plan – Production casing top of cement will be > 500' above top of gas.

The SHL was changed (and approved by sundry 9/17/2008) since the original APD was filed. This refile APD reflects all changes approved by sundry. There have been no changes to land use or well construction. Pad 12 is an existing pad, no new construction or consultation is required. Drilling has not begun on this pad. No wells have been drilled. No rig is on site. The location does not require a variance from any of the rules listed in Rule 306.d.(1). (A).(ii). 5/6/10 plg.

34. Location ID: 334429

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Kallasandra Moran

Title: Permit Representative Date: 3/12/2010 Email: kmoran@deltapetro.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: 5/9/2010

David S. Neslin

API NUMBER

05 077 09565 00

Permit Number: _____

Expiration Date: 5/8/2011

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2) CEMENT TOP VERIFICATION BY CBL REQUIRED.

3) THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE MINIMIS AMOUNTS. AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1.

4) NO PORTION OF ANY PIT THAT WILL BE USED TO HOLD LIQUIDS SHALL BE CONSTRUCTED ON FILL MATERIAL, UNLESS THE PIT AND FILL SLOPE ARE DESIGNED AND CERTIFIED BY A PROFESSIONAL ENGINEER, SUBJECT TO REVIEW AND APPROVAL BY THE DIRECTOR PRIOR TO CONSTRUCTION OF THE PIT. THE CONSTRUCTION AND LINING OF THE PIT SHALL BE SUPERVISED BY A PROFESSIONAL ENGINEER OR THEIR AGENT. THE ENTIRE BASE OF THE PIT MUST BE IN CUT.

5) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 440 FEET DEEP.

Attachment Check List

Att Doc Num	Name	Doc Description
400047798	FORM 2 SUBMITTED	LF@2438894 400047798

Total Attach: 1 Files