

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400047251

Plugging Bond Surety

20040060

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: BARRETT CORPORATION\* BILL

4. COGCC Operator Number: 10071

5. Address: 1099 18TH ST STE 2300

City: DENVER State: CO Zip: 80202

6. Contact Name: Matt Barbre Phone: (303)312-8168 Fax: (303)291-0420  
Email: mbarber@billbarrettcorp.com

7. Well Name: GGU Barge Well Number: 22C-32-691

8. Unit Name (if appl): GIBSON GULCH Unit Number: COC052447  
X

9. Proposed Total Measured Depth: 7530

WELL LOCATION INFORMATION

10. QtrQtr: SENW Sec: 32 Twp: 6S Rng: 91W Meridian: 6

Latitude: 39.486021 Longitude: -107.579960

Footage at Surface: 2023 FNL/FSL 1997 FEL/FWL FWL

11. Field Name: MAMM CREEK Field Number: 52500

12. Ground Elevation: 6370 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 12/21/2009 PDOP Reading: 1.9 Instrument Operator's Name: D. SLAUGH (TRI-STATE)

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1800 FNL 1990 FWL FWL Bottom Hole: FNL/FSL 180 FNL 1990 FWL FWL  
Sec: 32 Twp: 6S Rng: 91W Sec: 32 Twp: 6S Rng: 91W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 3057 ft

18. Distance to nearest property line: 658 ft 19. Distance to nearest well permitted/completed in the same formation: 327

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
ILES	ILES	191-65		
WILLIAMS FORK	WMFK	191-9		

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
SEE ATTACHED MAP

25. Distance to Nearest Mineral Lease Line: 481 ft 26. Total Acres in Lease: 1729

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: EVAPORATING AND BACK

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	26	16	42	40	0	40	0
SURF	12+1/4	9+5/8	36	760	230	760	0
1ST	8+3/4	4+1/2	11.6	7,530	655	7,530	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments BILL BARRETT CORPORATION IS THE SURFACE LESSEE. THERE ARE NO VISIBLE IMPROVEMENTS WITHIN 400'. THIS WELL LOCATION IS LOCATED AT THE PENDING GGU BARGE FED (MDP #3 PAD) 33D-32-691. IN ADDITION, THIS WELL IS APPROVED UNDER A FEDERAL ENVIRONMENTAL ASSESSMENT THROUGH THE BLM SILT, CO. OFFICE.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Matt Barber

Title: Permit Analyst Date: 3/16/2010 Email: mbarber@billbarrettcorp.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 5/9/2010

#### API NUMBER

05 045 19458 00

Permit Number: \_\_\_\_\_ Expiration Date: 5/8/2012

CONDITIONS OF APPROVAL, IF ANY: \_\_\_\_\_

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2) GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE

3) NEW MAMM CREEK FIELD NOTICE TO OPERATORS APPLIES TO THIS WELL. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE

4) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 153 FEET DEEP.

### **Attachment Check List**

Att Doc Num	Name	Doc Description
400047252	DEVIATED DRILLING PLAN	LF@2440444 400047252
400047253	DRILLING PLAN	LF@2440445 400047253
400047254	WELL LOCATION PLAT	LF@2440446 400047254
400047255	LOCATION DRAWING	LF@2440447 400047255
400047258	MULTI-WELL PLAN	LF@2440448 400047258
400047259	LEASE MAP	LF@2440449 400047259
400047835	FORM 2 SUBMITTED	LF@2440450 400047835
400049636	ACCESS ROAD MAP	LF@2440451 400049636

Total Attach: 8 Files