

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER GAS
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☒

Refiling ☐
Sidetrack ☐

Document Number:

1698163

Plugging Bond Surety

20100017

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: JEVIN CROTEAU Phone: (720)876-5339 Fax: (720)876-6339
Email: JEVIN.CROTEAU@ENCANA.COM

7. Well Name: IONE Well Number: 8-2-8

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 8115

WELL LOCATION INFORMATION

10. QtrQtr: NENE Sec: 8 Twp: 2N Rng: 66W Meridian: 6

Latitude: 40.159410 Longitude: -104.792270

Footage at Surface: 160 FNL/FSL FNL 170 FEL/FWL FEL

11. Field Name: SPINDLE Field Number: 77900

12. Ground Elevation: 4905 13. County: WELD

14. GPS Data:

Date of Measurement: 02/04/2010 PDOP Reading: 1.1 Instrument Operator's Name: CRAIG BURKE

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1400 FNL 50 FEL FEL Bottom Hole: FNL/FSL 1400 FNL 50 FEL FEL
Sec: 8 Twp: 2N Rng: 66W Sec: 8 Twp: 2N Rng: 66W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 268 ft

18. Distance to nearest property line: 160 ft 19. Distance to nearest well permitted/completed in the same formation: 850 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL	407	160	GWA
J SAND	JSND	232-23	160	GWA
NIOBRARA	NBRR	407	160	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
ALL OF SEC. 2, S2 OF SEC. 4 NE OF SEC. 10, T2N, R66W

25. Distance to Nearest Mineral Lease Line: 50 ft 26. Total Acres in Lease: 1680

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	800	350	800	0
1ST	7+7/8	4+1/2	11.6	8,115	280	8,115	7,052

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments NO CONDUCTOR CASING WILL BE USED. PROPOSED SPACING UNIT: SEC 8: E2NE; SEC 9:W2NW

34. Location ID: 413212

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: JEVIN CROTEAU

Title: REGULATORY ANALYST Date: 3/29/2010 Email: JEVIN.CROTEAU@ENCANA.C

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nashin Director of COGCC Date: 5/11/2010

API NUMBER

05 123 31576 00

Permit Number: _____ Expiration Date: 5/10/2012

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us
- 2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Sussex to 200' above Sussex. Verify coverage with cement bond log.
- 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name	Doc Description
1698162	WELL LOCATION PLAT	LF@2442855 1698162
1698163	APD ORIGINAL	LF@2442854 1698163
1698164	TOPO MAP	LF@2442930 1698164
1698165	LEASE MAP	LF@2442931 1698165
1698166	SURFACE AGRMT/SURETY	LF@2442856 1698166
1698167	30 DAY NOTICE LETTER	LF@2442857 1698167
1698168	DEVIATED DRILLING PLAN	LF@2442858 1698168
1698169	EXCEPTION LOC REQUEST	LF@2442859 1698169
1698170	EXCEPTION LOC REQUEST	LF@2442860 1698170
1698171	WAIVERS	LF@2442861 1698171
2109972	PROPOSED SPACING UNIT	LF@2442904 2109972

Total Attach: 11 Files