

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refiling ☐  
Sidetrack ☐

Document Number:

400036839

Plugging Bond Surety

20030009

3. Name of Operator: NOBLE ENERGY INC

4. COGCC Operator Number: 100322

5. Address: 1625 BROADWAY STE 2200

City: DENVER State: CO Zip: 80202

6. Contact Name: MARI CLARK Phone: (303)228-4413 Fax: (303)228-4286

Email: mclark@nobleenergyinc.com

7. Well Name: REI H Well Number: 17-29D

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 7972

WELL LOCATION INFORMATION

10. QtrQtr: SESW Sec: 8 Twp: 3N Rng: 65W Meridian: 6

Latitude: 40.233890 Longitude: -104.689780

Footage at Surface: 455 FNL/FSL FSL 1965 FEL/FWL FWL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4899 13. County: WELD

14. GPS Data:

Date of Measurement: 11/13/2009 PDOP Reading: 1.8 Instrument Operator's Name: ROBERT DALEY

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 75 FSL 1220 FEL/FWL FWL Bottom Hole: FNL/FSL 75 FSL 1220 FEL/FWL FWL  
Sec: 8 Twp: 3N Rng: 65W Sec: 8 Twp: 3N Rng: 65W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 730 ft

18. Distance to nearest property line: 290 19. Distance to nearest well permitted/completed in the same formation: 819 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL	407-87	160	GWA
J SAND	JSND	232-23	160	GWA
NIOBRARA	NBRR	407-87	160	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20030012

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
ALL: SECTION 8, T3N-65W

25. Distance to Nearest Mineral Lease Line: 75 ft 26. Total Acres in Lease: 2259

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: CLOSED LOOP

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	650	230	650	0
1ST	7+7/8	4+1/2	11.6	7,972	765	7,972	

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☐ Rotating Head ☐ None

33. Comments NO CONDUCTOR CASING WILL BE USED. 1ST STRING TOP OF CEMENT = 200' ABOVE NIOBRARA. UNIT CONFIGURATION = S/2SW, SECTION 8 & N/2NW OF SECTION 17, T3N, R65W. WELL IS TO BE TWINNED WITH EXISTING BB DRAW H8-14JI Noble requests approval of a Rule 318Aa exception location: Wellhead is to be located outside of a GWA drilling window.

34. Location ID: 330968

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: MARI CLARK

Title: REG. ANALYST II Date: 4/8/2010 Email: mclark@nobleenergyinc.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David G. Neslin Director of COGCC Date: 5/12/2010

#### API NUMBER

05 123 31584 00

Permit Number: \_\_\_\_\_ Expiration Date: 5/11/2012

CONDITIONS OF APPROVAL, IF ANY:

**All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.**

- 1) Provide 24 hour notice of MIRU to Bo Brown at 970-330-6085 or e-mail at bobrown@state.co.us.
- 2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Sussex to 200' above Sussex. Verify coverage with cement bond log.
- 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

### **Attachment Check List**

Att Doc Num	Name	Doc Description
2553505	SURFACE CASING CHECK	LF@2472180 2553505
400053231	WELL LOCATION PLAT	LF@2451569 400053231
400053232	30 DAY NOTICE LETTER	LF@2451570 400053232
400053233	SURFACE AGRMT/SURETY	LF@2451571 400053233
400053234	DEVIATED DRILLING PLAN	LF@2451572 400053234
400053239	EXCEPTION LOC REQUEST	LF@2451573 400053239
400053240	EXCEPTION LOC WAIVERS	LF@2451574 400053240
400053241	PROPOSED SPACING UNIT	LF@2451575 400053241
400053491	FORM 2 SUBMITTED	LF@2451576 400053491

Total Attach: 9 Files