

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☒

Refiling ☒

Sidetrack ☐

Document Number:

400046351

Plugging Bond Surety

20060139

3. Name of Operator: OXY USA INC

4. COGCC Operator Number: 66561

5. Address: PO BOX 27757

City: HOUSTON State: TX Zip: 77227

6. Contact Name: Joan Proulx Phone: (970)263-3641 Fax: (970)263-3694

Email: joan\_proulx@oxy.com

7. Well Name: Currey Well Number: 16-11C

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 6529

WELL LOCATION INFORMATION

10. QtrQtr: SESW Sec: 16 Twp: 9S Rng: 94W Meridian: 6

Latitude: 39.272407 Longitude: -107.887721

Footage at Surface: 1113 FNL/FSL FSL 2446 FEL/FWL FWL

11. Field Name: Brush Creek Field Number: 7562

12. Ground Elevation: 6780 13. County: MESA

14. GPS Data:

Date of Measurement: 08/02/2006 PDOP Reading: 3.5 Instrument Operator's Name: Jim Grabowski

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1384 FSL 1945 FEL/FWL FWL Bottom Hole: FNL/FSL 1384 FSL 1945 FEL/FWL FWL  
Sec: 16 Twp: 9S Rng: 94W Sec: 16 Twp: 9S Rng: 94W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 2640 ft

18. Distance to nearest property line: 1146 ft 19. Distance to nearest well permitted/completed in the same formation: 284 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Mesa Verde	MVRD	429-4		

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
W2NE, E2SW, SE4, Sec 16

25. Distance to Nearest Mineral Lease Line: 646 ft 26. Total Acres in Lease: 400

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Other: Onsite Reserve Pit

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	24+0/0	16+0/0	0.25 Wall	40		40	0
SURF	12+1/4	8+5/8	32.0	1,500	360	1,500	0
1ST	7+7/8	4+1/2	11.6	6,529	590	6,529	1,500

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments

1. The pad has been built.
2. The pit has been constructed.
3. This refile will not require any expansion/additional surface disturbance of the pad.
4. The location does not require a variance from any of the rules listed in Rule 306.d.(1).(A).(ii).
5. The location is not in a wildlife restricted surface occupancy area.

30-day notice requirement has been waived per Surface Use Agreement.

34. Location ID: 334527

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Joan Proulx

Title: Regulatory Analyst Date: 3/11/2010 Email: joan\_proulx@oxy.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline Director of COGCC Date: 5/12/2010

Permit Number: \_\_\_\_\_ Expiration Date: 5/11/2011

**API NUMBER**

05 077 09640 00

**CONDITIONS OF APPROVAL, IF ANY:**

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2) CEMENT TOP VERIFICATION BY CBL REQUIRED.

3) THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE MINIMIS AMOUNTS. AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1.

4) NO PORTION OF ANY PIT THAT WILL BE USED TO HOLD LIQUIDS SHALL BE CONSTRUCTED ON FILL MATERIAL, UNLESS THE PIT AND FILL SLOPE ARE DESIGNED AND CERTIFIED BY A PROFESSIONAL ENGINEER, SUBJECT TO REVIEW AND APPROVAL BY THE DIRECTOR PRIOR TO CONSTRUCTION OF THE PIT. THE CONSTRUCTION AND LINING OF THE PIT SHALL BE SUPERVISED BY A PROFESSIONAL ENGINEER OR THEIR AGENT. THE ENTIRE BASE OF THE PIT MUST BE IN CUT.

5) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 258 FEET DEEP.

**Attachment Check List**

Att Doc Num	Name	Doc Description
400047773	FORM 2 SUBMITTED	LF@2438872 400047773

Total Attach: 1 Files