

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400048936

Plugging Bond Surety

20090069

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refiling ☒

Sidetrack ☐

3. Name of Operator: DELTA PETROLEUM CORPORATION

4. COGCC Operator Number: 16800

5. Address: 370 17TH ST STE 4300

City: DENVER State: CO Zip: 80202

6. Contact Name: Kallasandra Moran Phone: (303)575-0323 Fax: (303)575-0324
Email: kmoran@deltapetro.com

7. Well Name: BCU Well Number: 14-141

8. Unit Name (if appl): Buzzard Creek Unit Number: COC 47597A

9. Proposed Total Measured Depth: 8319

WELL LOCATION INFORMATION

10. QtrQtr: SWSW Sec: 14 Twp: 9S Rng: 93W Meridian: 6

Latitude: 39.272580 Longitude: -107.744930

Footage at Surface: 1184 FNL/FSL FSL 550 FEL/FWL FWL

11. Field Name: Buzzard Creek Field Number: 9500

12. Ground Elevation: 7399 13. County: MESA

14. GPS Data:

Date of Measurement: 04/28/2008 PDOP Reading: 0.0 Instrument Operator's Name: Ted Taggart, Wasatch Surveying

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1235 FSL 330 FEL/FWL FWL Bottom Hole: FNL/FSL 1235 FSL 330 FEL/FWL FWL
Sec: 14 Twp: 9S Rng: 93W Sec: 14 Twp: 9S Rng: 93W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 700 ft

18. Distance to nearest property line: 308 ft 19. Distance to nearest well permitted/completed in the same formation: 719 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Mesa Verde	MVRD	369-5		

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
See attached.

25. Distance to Nearest Mineral Lease Line: 330 ft 26. Total Acres in Lease: 205

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Closed loop

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	24	16	55	60	200	60	0
SURF	12+1/4	8+5/8	24, 32	2,200	740	2,200	0
1ST	7+7/8	4+1/2	11.6	8,319	477	8,319	5,225

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments #14 – GPS Data: No PDOP reading is available as per Surveyor - Control for survey was established using differentially corrected GPS from an Opus based control network. Well location was established using non-GPS conventional methods, therefore no PDOP reading was taken.

Casing plan – Production casing top of cement will be > 500' above top of gas.

Delta Petroleum is the surface owner, therefore Rule 306 is not applicable. There will not be a 30 day letter or SUA attached.

I certify that all conditions in the original permit are the same, except for distance to property line, which has been updated since Delta became surface owner. There have been no changes to land use or well construction. Pad BCU 14L is an existing pad. Pad expansion is required, COGCC Form 2A is including in permit package.

34. Location ID: 391336

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Kallasandra Moran

Title: Permit Representative Date: 3/24/2010 Email: kmoran@deltapetro.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved. *David S. Heslin*

COGCC Approved: _____ Director of COGCC Date: 5/13/2010

API NUMBER

05 077 10041 00

Permit Number: _____ Expiration Date: 5/12/2012

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2) CEMENT TOP VERIFICATION BY CBL REQUIRED.

3) THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE MINIMIS AMOUNTS. AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1.

4) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 210 FEET DEEP.

Attachment Check List

Att Doc Num	Name	Doc Description
400048939	LEGAL/LEASE DESCRIPTION	LF@2451097 400048939
400050601	FORM 2 SUBMITTED	LF@2451099 400050601

Total Attach: 2 Files