

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refiling ☐
Sidetrack ☐

Document Number:

400051862

Plugging Bond Surety

20010124

3. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP

4. COGCC Operator Number: 47120

5. Address: P O BOX 173779

City: DENVER State: CO Zip: 80217-3779

6. Contact Name: CHERYL LIGHT Phone: (720)929-6461 Fax: (720)929-7461
Email: CHERYL.LIGHT@ANADARKO.COM

7. Well Name: DRY CREEK Well Number: 7-27

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 8417

WELL LOCATION INFORMATION

10. QtrQtr: NENE Sec: 27 Twp: 1N Rng: 67W Meridian: 6

Latitude: 40.028030 Longitude: -104.870150

Footage at Surface: 483 FNL/FSL FNL 809 FEL/FWL FEL

11. Field Name: SPINDLE Field Number: 77900

12. Ground Elevation: 4993 13. County: WELD

14. GPS Data:

Date of Measurement: 09/09/2009 PDOP Reading: 2.3 Instrument Operator's Name: TRAVIS KRAICH

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 2130 FNL 2130 FEL 2130 FEL 2130 FNL 2130 FEL 2130
Sec: 27 Twp: 1N Rng: 67W Sec: 27 Twp: 1N Rng: 67W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 483 ft

18. Distance to nearest property line: 483 ft 19. Distance to nearest well permitted/completed in the same formation: 680 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
J-SAND	JSND	232	320	N/2
NIOBRARA-CODELL	NB-CD	407	80	W/2NE4
SUSSEX	SUSX		80	W/2NE4

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
SEE ATTACHED OIL & GAS LEASE.

25. Distance to Nearest Mineral Lease Line: 516 ft 26. Total Acres in Lease: 240

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	1,150	805	1,150	
1ST	7+7/8	4+1/2	11.6	8,417	200	8,417	
1ST LINER							

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☒ Rotating Head ☐ None

33. Comments NO CONDUCTOR CASING WILL BE USED.

34. Location ID: 305214

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: CHERYL LIGHT

Title: SR. REGULATORY ANALYST Date: 4/5/2010 Email: DJREGULATORY@ANADARK

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 5/13/2010

API NUMBER

05 123 31613 00

Permit Number: _____ Expiration Date: 5/12/2012

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us
- 2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Sussex to 200' above Sussex. Verify coverage with cement bond log.
- 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name	Doc Description
1760961	SURFACE AGRMT/SURETY	LF@2475476 1760961
400051869	WELL LOCATION PLAT	LF@2450819 400051869
400051870	TOPO MAP	LF@2450820 400051870
400051871	OIL & GAS LEASE	LF@2450821 400051871
400051872	SURFACE AGRMT/SURETY	LF@2450822 400051872
400051873	30 DAY NOTICE LETTER	LF@2450823 400051873
400051874	DEVIATED DRILLING PLAN	LF@2450824 400051874
400051875	MULTI-WELL PLAN	LF@2450825 400051875
400053571	FORM 2 SUBMITTED	LF@2450826 400053571

Total Attach: 9 Files