

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

APPLICATION FOR PERMIT TO:

1.  Drill,  Deepen,  Re-enter,  Recomplete and Operate

2. TYPE OF WELL

OIL  GAS  COALBED  OTHER \_\_\_\_\_  
SINGLE ZONE  MULTIPLE ZONE  COMMINGLE ZONE

Refiling   
Sidetrack

Document Number:  
1760740  
Plugging Bond Surety  
20040030

3. Name of Operator: AEON ENERGY CORP 4. COGCC Operator Number: 710

5. Address: 7551 W ALAMEDA AVE STE 402  
City: LAKEWOOD State: CO Zip: 80226

6. Contact Name: BARRY L. SNYDER Phone: (303)922-0590 Fax: (303)239-0590  
Email: AEONCO@AOL.COM

7. Well Name: STATE Well Number: 34-36

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 2800

WELL LOCATION INFORMATION

10. QtrQtr: SWSE Sec: 36 Twp: 12N Rng: 47W Meridian: 6  
Latitude: 40.970290 Longitude: -102.544420

Footage at Surface: 660 FNL/FSL FSL 1980 FEL/FWL FEL

11. Field Name: SEDGWICK DRAW Field Number: 76908

12. Ground Elevation: 3678 13. County: SEDGWICK

14. GPS Data:

Date of Measurement: 09/09/2008 PDOP Reading: 2.6 Instrument Operator's Name: SCOTT DEMANCHE

15. If well is  Directional  Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_ Bottom Hole: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_

Sec: \_\_\_\_\_ Twp: \_\_\_\_\_ Rng: \_\_\_\_\_ Sec: \_\_\_\_\_ Twp: \_\_\_\_\_ Rng: \_\_\_\_\_

16. Is location in a high density area? (Rule 603b)?  Yes  No

17. Distance to the nearest building, public road, above ground utility or railroad: 1948 ft

18. Distance to nearest property line: 660 ft 19. Distance to nearest well permitted/completed in the same formation: 1319 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR		40	SWSE

21. Mineral Ownership:  Fee  State  Federal  Indian Lease #: 8552.5

22. Surface Ownership:  Fee  State  Federal  Indian

23. Is the Surface Owner also the Mineral Owner?  Yes  No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease?  Yes  No

23b. If 23 is No  Surface Owners Agreement Attached or  \$25,000 Blanket Surface Bon  \$2,000 Surface Bond  \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
ALL SEC 36-T12N-R47W

25. Distance to Nearest Mineral Lease Line: 660 ft 26. Total Acres in Lease: 640

**DRILLING PLANS AND PROCEDURES**

27. Is H2S anticipated?  Yes  No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling?  Yes  No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling?  Yes  No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)?  Yes  No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal:  Offsite  Onsite  
Method:  Land Farming  Land Spreading  Disposal Facility Other: STEEL MUD TANKS

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	9+7/8	7	20	300	175	300	0
1ST	6+1/4	4+1/2	10.5	2,900	75	2,900	2,100

32. BOP Equipment Type:  Annular Preventer  Double Ram  Rotating Head  None

33. Comments NO CONDUCTOR PIPE WILL BE USED. NOTHING HAS CHANGED SINCE ORIGINAL APD WAS APPROVED AS API #115-06076-00

34. Location ID: 316903

35. Is this application in a Comprehensive Drilling Plan ?  Yes  No

36. Is this application part of submitted Oil and Gas Location Assessment ?  Yes  No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: BARRY L. SNYDER

Title: PRESIDENT Date: 3/10/2010 Email: AEONCO@AOL.COM

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 5/19/2010

<b>API NUMBER</b>
05 115 06076 00

Permit Number: \_\_\_\_\_ Expiration Date: 5/18/2012

**CONDITIONS OF APPROVAL, IF ANY:** \_\_\_\_\_

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COGCC ENG COA – SME

1. Provide 24 hr notice of MIRU to Colby Horton at 970-370-0040 or colby.horton@state.co.us..
2. Set surface casing per Rule 317d, cement to surface. Setting surface casing less than the approved depth is a permit violation unless prior written approval is obtained from the COGCC.
3. If completed, provide cement coverage from TD to 200' above Niobrara. Verify coverage with cement bond log.
4. If well is a dry hole set the following plugs: a) 35 sks cement from 50' above Niobrara top up b) 35 sks cement ½ out, ½ in surface casing c) 10 sks cement at top of surface casing, cut casing 4' below GL, weld on plate, 5 sks cement in rat hole and 5 sks cement in mouse hole. Restore surface location.

### **Attachment Check List**

Att Doc Num	Name	Doc Description
1760740	APD ORIGINAL	LF@2450001 1760740
1760742	30 DAY NOTICE LETTER	LF@2450003 1760742

Total Attach: 2 Files