

FORM  
2  
Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

APPLICATION FOR PERMIT TO:

1.  Drill,  Deepen,  Re-enter,  Recomplete and Operate

2. TYPE OF WELL

OIL  GAS  COALBED  OTHER \_\_\_\_\_  
SINGLE ZONE  MULTIPLE ZONE  COMMINGLE ZONE

Refiling   
Sidetrack

Document Number:  
400043474  
Plugging Bond Surety  
20030107

3. Name of Operator: WILLIAMS PRODUCTION RMT COMPANY 4. COGCC Operator Number: 96850

5. Address: 1515 ARAPAHOE ST STE 1000  
City: DENVER State: CO Zip: 80202

6. Contact Name: Lisa Dee Phone: (303)260-4538 Fax: (303)629-8268  
Email: Lisa.Dee@Williams.com

7. Well Name: Chevron TR Well Number: 342-32-597

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 8595

WELL LOCATION INFORMATION

10. QtrQtr: NENE Sec: 32 Twp: 5s Rng: 97w Meridian: 6  
Latitude: 39.574585 Longitude: -108.293610

Footage at Surface: 1031 FNL/FSL FNL 375 FEL/FWL FEL

11. Field Name: Trail Ridge Field Number: 83825

12. Ground Elevation: 8259 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 07/22/2008 PDOP Reading: 2.8 Instrument Operator's Name: Mark Bessie

15. If well is  Directional  Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1573 FNL 697 FEL 697 FEL 1573 FNL 697 FEL  
Sec: 32 Twp: 5s Rng: 97w Sec: 32 Twp: 5s Rng: 97w

16. Is location in a high density area? (Rule 603b)?  Yes  No

17. Distance to the nearest building, public road, above ground utility or railroad: 13517 ft

18. Distance to nearest property line: 5861 ft 19. Distance to nearest well permitted/completed in the same formation: 301 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Williams Fork	WMFK	510-17		

21. Mineral Ownership:  Fee  State  Federal  Indian Lease #: \_\_\_\_\_

22. Surface Ownership:  Fee  State  Federal  Indian

23. Is the Surface Owner also the Mineral Owner?  Yes  No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease?  Yes  No

23b. If 23 is No  Surface Owners Agreement Attached or  \$25,000 Blanket Surface Bon  \$2,000 Surface Bond  \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
See attached lease map

25. Distance to Nearest Mineral Lease Line: 1573 ft 26. Total Acres in Lease: 17315

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated?  Yes  No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling?  Yes  No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling?  Yes  No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)?  Yes  No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal:  Offsite  Onsite

Method:  Land Farming  Land Spreading  Disposal Facility Other: Evaporation & Backfilling

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	26	18	48#	60	100	60	0
SURF	14+3/4	9+5/8	32.3#	2,805		2,805	0
3RD	7+7/8	4+1/2	11.6#	8,595		8,595	

32. BOP Equipment Type:  Annular Preventer  Double Ram  Rotating Head  None

33. Comments Cement will be circulated to the surface in the Conductor & Surface Strings. Cement will be circulated to 200' above the uppermost Mesaverde sand in the Production String. Location Constructed, will be expanded. New pits will be constructed. See plat. Rule 305 30 Day Land Owner Notice Waived.

34. Location ID: 335915

35. Is this application in a Comprehensive Drilling Plan ?  Yes  No

36. Is this application part of submitted Oil and Gas Location Assessment ?  Yes  No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Lisa Dee

Title: Regulatory Specialist Date: 3/30/2010 Email: Lisa.Dee@Williams.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 5/19/2010

**API NUMBER**  
05 045 19477 00

Permit Number: \_\_\_\_\_ Expiration Date: 5/18/2012

**CONDITIONS OF APPROVAL, IF ANY:** \_\_\_\_\_

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2) GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE

3) CEMENT TOP VERIFICATION BY CBL REQUIRED.

4) COMPLY WITH ALL PROVISIONS OF THE JUNE 12, 2008 NOTICE TO OPERATORS DRILLING WELLS WITHIN 3/4 MILE OF THE RIM OF THE ROAN PLATEAU IN GARFIELD COUNTY - PIT DESIGN, CONSTRUCTION AND MONITORING REQUIREMENTS. SEE ATTACHED NOTICE.

5) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 000 FEET DEEP.

### **Attachment Check List**

Att Doc Num	Name	Doc Description
400043491	WELL LOCATION PLAT	LF@2446954 400043491
400043492	TOPO MAP	LF@2446955 400043492
400043493	LEASE MAP	LF@2446956 400043493
400043494	DEVIATED DRILLING PLAN	LF@2446957 400043494
400050848	SURFACE AGRMT/SURETY	LF@2446958 400050848
400051242	FORM 2 SUBMITTED	LF@2446959 400051242

Total Attach: 6 Files