

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

2582196

Plugging Bond Surety

20010124

APPLICATION FOR PERMIT TO:

1. ☐ Drill, ☐ Deepen, ☐ Re-enter, ☒ **Recomplete and Operate**

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☐ COMMINGLE ZONE ☒

Refiling ☐

Sidetrack ☐

3. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP

4. COGCC Operator Number: 47120

5. Address: P O BOX 173779

City: DENVER State: CO Zip: 80217-3779

6. Contact Name: CHERYL LIGHT Phone: (720)929-6461 Fax: (720)929-7461
Email: CHERYL.LIGHT@ANADARKO.COM

7. Well Name: UPRR 22 PAN AM UNIT U Well Number: 1

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7830

WELL LOCATION INFORMATION

10. QtrQtr: NWNE Sec: 21 Twp: 3N Rng: 65W Meridian: 6

Latitude: 40.215417 Longitude: -104.665142

Footage at Surface: 1003 FNL/FSL FNL 1624 FEL/FWL FEL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4828 13. County: WELD

14. GPS Data:

Date of Measurement: 11/13/2008 PDOP Reading: 2.1 Instrument Operator's Name: CODY MATTSON

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____

Sec: _____ Twp: _____ Rng: _____ Sec: _____ Twp: _____ Rng: _____

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 970 ft

18. Distance to nearest property line: 1003 ft 19. Distance to nearest well permitted/completed in the same formation: 85 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA-CODELL	NB-CD		160	NE/4

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
SEE ATTACHED LEASE

25. Distance to Nearest Mineral Lease Line: 1003 ft 26. Total Acres in Lease: 80

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	665	420	665	0
1ST	7+7/8	4+1/2	11.6	7,830	350	7,830	6,100

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☒ Rotating Head ☐ None

33. Comments _____

34. Location ID: 336444

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: CHERYL LIGHT

Title: REGULATORY Date: 4/16/2010 Email: DJREGULATORY@ANADARK

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 5/20/2010

API NUMBER

05 123 14457 00

Permit Number: _____ Expiration Date: 5/19/2012

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) Provide 24 hour notice of MIRU to Bo Brown at 970-330-6085 or e-mail at bobrown@state.co.us 2) Provide remedial cement from 4730' - 4210' (Sussex), and 920' – 610' (Fox Hills, last joint casing fell off bottom to 825'-870'). Verify w/ CBL. Also submit CBL for Niobrara TOC stated as 6100' by CBL. 3) Recomplete cannot be performed without approved Form 2.

1) Provide 24 hour notice of MIRU to Bo Brown at 970-330-6085 or e-mail at bobrown@state.co.us 2) Provide remedial cement from 4730' - 4210' (Sussex), and 920' – 610' (Fox Hills, last joint casing fell off bottom to 825'-870'). Verify w/ CBL. 3) Recomplete cannot be performed without approved Form 2.

1) Provide 24 hour notice of MIRU to Bo Brown at 970-330-6085 or e-mail at bobrown@state.co.us

2) Provide remedial cement from 4730' - 4210' (Sussex), and 720' – 610' (Fox Hills, SC shoe at 665'. Last joint casing fell off bottom to 825'-870'). Verify w/ CBL. Also submit CBL referenced for Niobrara TOC stated as 6100'.

Attachment Check List

Att Doc Num	Name	Doc Description
2553353	SURFACE CASING CHECK	LF@2465708 2553353
2582196	APD ORIGINAL	LF@2453631 2582196
2582197	30 DAY NOTICE LETTER	LF@2453632 2582197
2582198	SURFACE AGRMT/SURETY	LF@2453633 2582198
2582199	OIL & GAS LEASE	LF@2453634 2582199

Total Attach: 5 Files