

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☒

Refiling ☐  
Sidetrack ☐

Document Number:

400053460

Plugging Bond Surety

20100017

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: MIRACLE PFISTER Phone: (720)876-3761 Fax: (720)876-6060

Email: miracle.pfister@hotmail.com

7. Well Name: TWIN CREEK Well Number: 1-10C2 (01EB)

8. Unit Name (if appl): HUNTER MESA Unit Number: COC55972E

9. Proposed Total Measured Depth: 6921

WELL LOCATION INFORMATION

10. QtrQtr: SWSE Sec: 1 Twp: 7S Rng: 92W Meridian: 6

Latitude: 39.471450 Longitude: -107.612610

Footage at Surface: 846 FNL/FSL FSL 1902 FEL/FWL FEL

11. Field Name: MAMM CREEK Field Number: 52500

12. Ground Elevation: 6062.2 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 08/13/2008 PDOP Reading: 0.0 Instrument Operator's Name: TED TAGGART

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 800 FSL 2455 FEL FEL Bottom Hole: FNL/FSL 800 FSL 2455 FEL FEL  
Sec: 1 Twp: 7S Rng: 92W Sec: 1 Twp: 7S Rng: 92W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 329 ft

18. Distance to nearest property line: 594 ft 19. Distance to nearest well permitted/completed in the same formation: 449 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
ILES	ILES			
WILLIAMS FORK	WMFK			

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
T7S-R92W SEC 1: W/2SE/4, LESS THAT PART OF THE NW/4SE/4 LYING EAST OF A LINE LYING FIVE FEET EASTERLY OF AND PARALLEL TO THE EASTERLY BANK OF EAST DIVIDE CREEK; SEC 1: E/2SW/4; SEC 12: W/2NE/4, E/2NW/4, SW/4NW/4, NE/4SW/4, NW/4SE/4

25. Distance to Nearest Mineral Lease Line: 781 ft 26. Total Acres in Lease: 433

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	24	16	LINEPIPE	40	5	40	0
SURF	12+1/4	9+5/8	36	1,133	546	1,133	0
1ST	7+7/8	4+1/2	11.6	6,921	648	6,921	0

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments TOP OF CEMENT IS 500' ABOVE TOG. RELATED FORM 2A DOC # IS 400044633.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: MIRACLE PFISTER

Title: REGULATORY ANALYST Date: 4/8/2010 Email: miracle.pfister@encana.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 5/25/2010

API NUMBER

05 045 19507 00

Permit Number: \_\_\_\_\_ Expiration Date: 5/24/2012

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1)COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2)GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE

3)NEW MAMM CREEK FIELD NOTICE TO OPERATORS APPLIES TO THIS WELL. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE

4)THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 450 FEET DEEP.

### **Attachment Check List**

Att Doc Num	Name	Doc Description
400053631	DEVIATED DRILLING PLAN	LF@2449558 400053631
400053633	PLAT	LF@2449559 400053633
400053634	30 DAY NOTICE LETTER	LF@2449560 400053634
400054172	FORM 2 SUBMITTED	LF@2449561 400054172

Total Attach: 4 Files