

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400054629

Plugging Bond Surety

20010124

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP

4. COGCC Operator Number: 47120

5. Address: P O BOX 173779

City: DENVER State: CO Zip: 80217-3779

6. Contact Name: CHERYL LIGHT Phone: (720)929-6461 Fax: (720)929-7461  
Email: CHERYL.LIGHT@ANADARKO.COM

7. Well Name: HIGHWAY 160 Well Number: 41-2

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 8395

WELL LOCATION INFORMATION

10. QtrQtr: SWNE Sec: 2 Twp: 1N Rng: 66W Meridian: 6

Latitude: 40.083254 Longitude: -104.740446

Footage at Surface: 1496 FNL/FSL FNL 1569 FEL/FWL FEL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 5104 13. County: WELD

14. GPS Data:

Date of Measurement: 02/23/2010 PDOP Reading: 2.1 Instrument Operator's Name: TRAVIS KRAICH

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1290 FNL 50 FEL 50 FEL 50 FEL 50  
Bottom Hole: FNL/FSL 1290 FNL 50 FEL 50 FEL 50  
Sec: 2 Twp: 1N Rng: 66W Sec: 2 Twp: 1N Rng: 66W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 1076 ft

18. Distance to nearest property line: 1074 ft 19. Distance to nearest well permitted/completed in the same formation: 970 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
J-SAND	JSND		160	GWA
NIOBRARA-CODELL	NB-CD	407	160	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
SEE ATTACHED OIL & GAS LEASE

25. Distance to Nearest Mineral Lease Line: \_\_\_\_\_ 50 ft 26. Total Acres in Lease: \_\_\_\_\_ 320

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	1,130	770	1,130	
1ST	7+7/8	4+1/2	11.6	8,395	200	8,395	

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☒ Rotating Head ☐ None

33. Comments NO CONDUCTOR CASING WILL BE USED. NB-CD & JSND: E/2NE/4, SEC 2, T1N-R66W, W/2NW/4, SEC 1, T1N-R66W Changed surface casing depth from 1100' to 1130'.

34. Location ID: \_\_\_\_\_ 317936

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: CHERYL LIGHT

Title: SR. REGULATORY ANALYST Date: 4/29/2010 Email: DJREGULATORY@ANADARK

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 5/27/2010

API NUMBER

05 123 31683 00

Permit Number: \_\_\_\_\_ Expiration Date: 5/26/2012

CONDITIONS OF APPROVAL, IF ANY:

**All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.**

- 1) Note surface casing setting depth change from 1100' to 1130'. Increase cement coverage accordingly and cement to surface.
- 2) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us
- 3) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Sussex to 200' above Sussex. Verify coverage with cement bond log.
- 4) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

### **Attachment Check List**

Att Doc Num	Name	Doc Description
2621411	SURFACE CASING CHECK	LF@2465698 2621411
400054629	FORM 2 SUBMITTED	LF@2459761 400054629
400054630	WELL LOCATION PLAT	LF@2459762 400054630
400054631	TOPO MAP	LF@2459763 400054631
400054632	OIL & GAS LEASE	LF@2459764 400054632
400054634	SURFACE AGRMT/SURETY	LF@2459765 400054634
400054635	30 DAY NOTICE LETTER	LF@2459766 400054635
400054636	DEVIATED DRILLING PLAN	LF@2459767 400054636
400054637	PROPOSED SPACING UNIT	LF@2459768 400054637
400054638	MULTI-WELL PLAN	LF@2459769 400054638

Total Attach: 10 Files